



PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION
156 S. BROADWAY, SUITE 150
TURLOCK, CA 95380

PHONE: (209) 668-5520
FAX: (209) 668-5563
TDD: (800) 735-2929
engineering@turlock.ca.us

Addendum No. 2

July 17, 2026

City Project No.: 23-052
Geer Road Pavement Rehabilitation Project, Phases 1, 2 and 3

Plan holders:

This addendum includes revisions to Plans and Specifications and provides clarifications and answers to questions submitted to the City.

Revisions to Plans and Specifications

The following additions, deletions or modifications shall become part of the Contract Documents:

Strikethrough text (~~text~~) indicates deletions.

Bold Italicized text (***text***) indicates additions.

Item No. 1:

Revise Bid Schedule Bid Items 34, 87, 151 Shallow Utility Alternative Pavement Section:

Item	Description	Quantity	Unit
34	SHALLOW UTILITY ALTERNATIVE PAVEMENT SECTION	8500	LF SF
87	SHALLOW UTILITY ALTERNATIVE PAVEMENT SECTION	12000	LF SF
151	SHALLOW UTILITY ALTERNATIVE PAVEMENT SECTION	2000	LF SF

The unit of measurement for Bid Item "Shallow Utility Alternative Pavement Section" shall be Square Feet (SF) as called out in Section 10.23. The Bid Schedule incorrectly identifies the unit as Linear Feet (LF). No changes to the quantities. A revised Bid Schedule table is attached and supersedes the original Bid Schedule for this item.

Item No. 2:

Q: When requesting a bond for this project our bonding agent noticed that the bidders bond has Project NO. NO. 23-052, as shown in the pic attached to this email, please supply the corrected bond.

A: The bidder's bond form on Page 23 contains a typographical error. The project number should read "Project No. 23-052" instead of "Project No. No. 23-052." A corrected Page 23 is attached to this Addendum and shall replace the original Page 23 in the Contract Documents.

Item No. 3:

DELETE Appendix C – Federal Wage Rates in its entirety and **REPLACE** it with the updated Federal Wage Rate Determination attached to this Addendum.

The applicable Federal Wage Rate Determination for this project is Wage Determination No. CA20260018, Modification No. 6. All references in the Contract Documents to Wage Determination No. CA20260018, Modification No. 5 are hereby revised to reference Wage Determination No. CA20260018, Modification No. 6.

Item No. 4:

Q: The specifications have Exhibit 12-B (Part 1&2) as part of the documents, but is not listed on the Proposal Checklist. Please confirm if the Exhibit 12-B (Part 1 & 2) are required to be submitted on the day of the bid?

A: Yes. Exhibit 12-B, Bidder's List of Subcontractors (DBE and Non-DBE), Parts 1 and 2, shall be completed and submitted with the bid on the day of bid opening. The Proposal Checklist is hereby clarified to include Exhibit 12-B, Parts 1 and 2, as required bid submittals. A corrected Page 6 is attached to this Addendum and shall replace the original Page 6 in the Contract Documents.

Complete Proposal

Page No.

☐ PROPOSAL AND BIDDING FORM.....	5-19
☐ AFFIDAVIT	20
☐ INFORMATION REQUIRED OF BIDDER.....	21-22
☐ BIDDER'S BOND	23-24
☐ LIST OF SUBCONTRACTORS.....	25
☐ IRAN CONTRACTING ACT CERTIFICATION.....	26
☐ EQUAL EMPLOYMENT OPPORTUNITY CERTIFICATION.....	27
☐ PUBLIC CONTRACT CODE STATEMENTS.....	28-29
☐ NON-COLLUSION AFFIDAVIT*	30
☐ DEBARMENT AND SUSPENSION CERTIFICATION*	31
☐ NONLOBBYING CERTIFICATION FOR FEDERAL-AID CONTRACTS*.....	32
☐ DISCLOSURE OF LOBBYING ACTIVITIES*	33
☐ <i>EXHIBIT 12-B: BIDDERS LIST OF SUBCONTRACTORS (DBE AND NON-DBE)</i>	<i>35-37</i>

* Signing the bid form constitutes acceptance and certification

Item No. 5:

Q: Traffic Control General Note 14 for location 1 requires 8 PCMS throughout construction. The same note is shown for Location 2 and 3. Are 8 PCMS Boards required for each location or for the entire project?

A: Yes, per Section 5.26 Order of Work: "Phase 1 and Phase 3 shall be constructed concurrently. Phase 1 and Phase 3 shall be completed prior to the start of Phase 2." A total of sixteen (16) PCMS

are needed for Phase 1 and Phase 3. For Phase 2, eight (8) PCMS will also be needed. The eight (8) PCMS for Phase 2 may be reused and relocated from Phase 1 and Phase 3. The signs shall be placed, maintained, and relocated as necessary to support the Contractor's approved construction staging and traffic control operations and as directed by the Engineer.

Item No. 6:

Q: Please provide the RIM Elevations and Flow Line Elevations for two catch basin installations shown on Sheet DU-4 Phase 1.

A: The catch basins shall be replaced in place, with the existing pipe flow line elevations maintained. Rim elevations shall conform to the proposed finished surface grades.

NE Hawkeye Avenue Catch Basin Flow Line Elevation: 104.22

SE Hawkeye Avenue Catch Basin Flow Line Elevation: 103.75

Item No. 7:

Q: Construction Details for Curb Ramps and Driveways on Plan Sheet CD-1 and CD-2 show an 8" section of HMA against the minor concrete curb and gutter. Will this detail apply when the new curb ramps and driveways are adjacent to a new full depth structural section (1.1' Full Depth HMA at Intersections and .4' HMA over 1.0 of FDR)?

A: Where minor concrete improvements are constructed in advance of the adjacent roadway rehabilitation, the HMA section shown on Sheets CD-1 and CD-2 shall be used as necessary to restore the pavement removal adjacent to the new concrete and maintain a safe and serviceable interim surface.

Where the adjacent roadway is designated for a full-depth pavement structural section, the final pavement shall match the full-depth structural section shown for that location. The interim HMA restoration does not replace or reduce the required final pavement structural section. Separate interim restoration is not required where the permanent pavement section is constructed before the area is reopened to traffic.

Item No. 8:

Q: Please provide the RIM Elevation and Flow Line Elevation for catch basin installation shown on Sheet DU-3 Phase 2.

A: The proposed catch basin shall be installed at the location shown, with the existing storm drain pipe extended to the new basin. The existing pipe flow line shall be maintained at the connection. The rim elevation shall conform to the proposed finished surface grade.

NE Tuolumne Road Proposed Catch Basin Flow Line Elevation: 103.75

The Contractor shall verify existing conditions and connections in the field prior to construction and notify the Engineer of any discrepancy before proceeding with the work.

Item No. 9:

Q: Please provide the Profile for Unnamed Drainage System Extension of 6 LF 18" RCP shown on DU-3 Phase 2.

A: A separate profile will not be provided. The 6 LF of 18-inch RCP is a short extension connecting to the existing drainage system. The Contractor shall verify the existing connection elevation and install the pipe to provide positive drainage between the proposed inlet and existing system.

Item No. 10:

Q: Construction Details, Phase 1, Plan Sheet CD-4 and CD-5 show 1' of native soil in the medians. What bid item will pay for the generation and placement of this native soil?

A: The 1-foot native soil section shown within the median areas is part of the completed median section depicted in the Contract Documents. Suitable native material may be obtained from project excavation (i.e., Bid Item Roadway Excavations (F)) or other Contractor-furnished sources and shall be placed and compacted to a minimum of 90 percent relative compaction as specified and as needed to complete the detail.

No separate bid item or payment will be provided for furnishing, placing, grading, or compacting the native soil within the median section. All costs associated with this work shall be included in the applicable contract bid items.

Item No. 11:

Q: Per City of Turlock Standard Drawings, T1 through T3 call for a three-step trench repair sequence: a 2-inch cold mix or temporary material, followed by 6-inch Aggregate Base Class 2 plus HMA (1 inch greater than existing AC, minimum 5 inch final lift), followed by a full lane grind and 2 inch HMA overlay. Within areas designated for Full Depth Reclamation and Cold Plane/HMA, please confirm whether Step 1 alone is sufficient as an interim surface until FDR or Cold Plane/HMA reconstructs the section, allowing Steps 2 and 3 to be omitted at those locations.

A: Step 1 may be used as a temporary surface only and shall be maintained in a safe and serviceable condition until permanent pavement restoration is completed.

Where a utility trench is located entirely within an area subsequently reconstructed by Full Depth Reclamation-Cement, the FDR-C and overlying HMA construction may serve as the permanent pavement restoration, provided the trench backfill and temporary surface are completed and maintained in accordance with the Contract Documents.

Within Cold Plane/HMA areas, the structural trench repair required by the applicable City Standard Drawing shall be completed before the project-wide cold planing and HMA overlay. The project cold planing and overlay may satisfy the final lane grind and overlay component where the limits coincide.

All trench restoration shall be coordinated with the permanent pavement work and is subject to acceptance by the Engineer.

Item No. 12:

Q: The Disadvantaged Business Enterprise (DBE) Section of Exhibit 12-G of the specification has been crossed out. Section 5.08 - Subcontractor and Disadvantaged Business Enterprise Records

states that DBE requirements are on hold. With no DBE on the contract, can the City remove the Exhibit 12-B (Bidders List of Subcontractors (DBE and Non-DBE), Part 1 and Part 2 Forms from the specifications?

A: No. Exhibit 12-B, Bidder's List of Subcontractors (DBE and Non-DBE), Parts 1 and 2, shall remain in the Contract Documents and shall be submitted with the bid.

Although DBE contract goal setting is currently suspended, Exhibit 12-B remains a required bid document for identification of subcontractors and compliance with applicable subcontractor listing requirements.

Item No. 13:

Q: When are the Exhibit 12-B Part 1 and Part 2 forms (Page 35 of the specification) to be submitted to the city? If required, please allow 5 business days after the bid date to be submitted by the low bidder.

A: Exhibit 12-B, Bidder's List of Subcontractors (DBE and Non-DBE), Parts 1 and 2, shall be submitted with the bid and will not be accepted after bid opening.

Item No. 14:

Q: Section 10.21 - Full Depth Reclamation - Cement, Page 159, States "Mix design for the full depth reclamation - cement as well as the CLSM will be paid for on the basis of lump sum prices." Is the "CLSM" referenced here for shallow utilities or some other operation?

A: Section 10.21 has been revised for the removal of "as well as CLSM" as follows:

Delete "as well as the CLSM " from paragraph 10 of Section 10.21:

Mix design for the full depth reclamation - cement ~~as well as the CLSM~~ will be paid for on the basis of lump sum prices.

Delete "as well as the CLSM" from paragraph 13 of Section 10.21:

The contract lump sum prices paid for mix design (full depth reclamation - cement ~~as well as CLSM~~) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in preparing and testing the mix, including adding water, supplementary aggregate if required by the Engineer, setting control additives, mixing water with asphaltic emulsion, and applying sand cover, complete in place, as shown on the plans, as specified in State Standard Specifications and these Special Provisions, and as directed by the Engineer.

Item No. 15:

Q: Section 10.16 - Cold Planning AC Pavement states "At locations that are to be reconstructed utilizing Full Depth Reclamation-Cement, in lieu of cold planning the existing asphalt concrete, the contractor may pulverize and mix the entire asphalt concrete section into the base and subgrade soil" If cold plane is done before the FDR-C, in some location there may be less than a tenth of existing asphalt left to be mixed with the existing subgrade for the FDR-C process. Is there a requirement for how much existing asphalt is to be part of the FDR-C process?

A: No minimum amount of existing asphalt concrete is required to be incorporated into the Full Depth Reclamation-Cement process.

The Contractor may perform the work in accordance with Sections 10.16 and 10.21 of the Contract Documents. The Contractor's mix design shall be based on the actual materials incorporated into the reclaimed section and shall meet the strength requirements specified for the Full Depth Reclamation-Cement section.

Item No. 16:

Q: Is the project raising the elevations of the medians?

A: No. The project is not intended to raise the median elevations. Reconstructed median elevations generally match the adjacent existing roadway and are established by the proposed grading, drainage, and median improvements shown in the Contract Documents and in the existing contour grading provided in Addendum 1.

Item No. 17:

Q: Section 5.17 Public Safety states "During construction all streets shall have a minimum of one traffic lane, not less than 11 feet wide open for use by local traffic to access driveways of all businesses and residences". However, Section 5.26 Order of Work states "Geer Road is to remain open to traffic at ALL TIMES, with at least one - 12-foot lane open in each direction". Is the contractor required to keep an 11' or 12' lane open at all times?

A: For this project, the Contractor shall maintain at least one 12-foot-wide travel lane in each direction on Geer Road at all times, unless otherwise approved by the Engineer. In the event of a conflict between Section 5.17 and Section 5.26, the 12-foot lane requirement shall govern.

Item No. 18:

Q: Confirming Bid Item 9, Video Sewer and Storm Drain: please confirm the existing system quantities are based on utilities shown on plan sheets 51 through 54, 131 through 135, and 208 through 213.

A: No. Bid Item 9 is a lump-sum item and is not based on fixed plan quantities. The Contractor shall perform the required pre-construction and post-construction video inspections of the existing sewer and storm drain mains within the roadway reconstruction limits in accordance with Section 10.09. New storm drain pipelines installed as part of the project shall be inspected and tested in accordance with Sections 16-26 through 16-33 of the City of Turlock Standard Specifications.

Item No. 19:

Q: Is the 6" of AB required under the commercial driveways accounted for in the Aggregate Base Class 2 bid item or in the Minor Concrete (Alley/Commercial Driveway) bid item?

A: The aggregate base required beneath alley and commercial driveways shall be included in the Minor Concrete (Alley/Commercial Driveway) bid item. No separate payment will be made under the Aggregate Base Class 2 bid item for this work.

Item No. 20:

Q: Is the two foot HMA plug at the curbs/C & G accounted for in the HMA (Type A) bid item or in the Minor Concrete bid items?

A: The HMA plug adjacent to proposed curbs and gutters shall be paid for under the Hot Mix Asphalt (Type A) bid item.

Item No. 21:

Q: Can you specify which shallow utility alternate pavement detail will be used at each shallow utility?

A: The approximately 12-inch Shallow Utility Alternative Pavement Section shall be used where required by the Contract Documents. The approximately 9.5-inch section may only be used where specifically approved by the Engineer based on verified field conditions.

Final locations and section depths shall be determined based on utility depths verified through the Contractor's required potholing.

Item No. 22:

Q: Are the shallow utilities that will require the alternate pavement detail clearly defined on the project plans? This is needed as the location of these alternate pavement sections will affect our means and methods for FDR, Cold Plane, Grading and Minor Concrete. We need to know these locations to bid the project properly.

A: The anticipated locations based on the preliminary potholing investigations are shown on the DU plan sheets. In accordance with Sections 5.39, 10.18, 10.21, and 10.23, the Contractor shall verify utility locations and depths, perform the required potholing, and identify locations where utility clearances do not satisfy the requirements for Full Depth Reclamation-Cement. The Contractor shall construct the Shallow Utility Alternative Pavement Section at those locations. The quantities shown in the Bid Schedule are estimated quantities developed from the design-phase potholing effort and extrapolated based on the length of roadway within each construction phase. Actual quantities will be based on field-verified utility locations and depths.

Additionally, the unit of measurement for Bid Item "Shallow Utility Alternative Pavement Section" shall be Square Feet (SF) as called out in 10.23. The Bid Schedule incorrectly identifies the unit as Linear Feet (LF). A revised Bid Schedule table is attached and supersedes the original Bid Schedule for this item.

Item No. 23:

Q: Will the City allow for the final lift of HMA to be placed on all three locations after the initial lifts of asphalt are placed during stage construction work?

A: No. The construction phasing shown in the Contract Documents shall be maintained. Placement of the final lift of Hot Mix Asphalt shall be completed within each phase as part of that phase's work and shall not be postponed until completion of the initial asphalt lifts in other phases.

Revise Section 8.02 Project Milestones (2nd Paragraph) as follows

This section describes damages due to the City should the Contractor fail to meet certain project milestones. Attention is directed to Section 5 “Time of Performance” of the Agreement for liquidated damages for the Contractor’s failure to perform all work on this project by the Completion Date.

The final lift of paving shall be placed no later than 3 working days after the first lift of paving. If the final lift of paving is not placed in the same shift as the initial lift(s) of paving, the Contractor shall place uneven surface warning signs every 50-feet along the lip of gutter. The cost of uneven surface warning signs shall be considered as included in the various contract bid items and no additional compensation will be allowed therefore.

The Contractor shall perform all required earthwork, grading, and initial paving (first lift) no later than eight (8) calendar days after the date when existing asphalt concrete surfaces have been demolished by way of cold plane grinding from any given area. On road sections that require video inspections of the sewer and storm drain mains in accordance with Section 10.09 "VIDEO SEWER AND STORM DRAIN", this time restriction may be extended to twelve (12) total calendar days. In the event the Contractor fails to complete the required work in the timeframe indicated, the City may deduct from payments or credits due Contractor a sum equal to two thousand five hundred dollars (\$2,500) for each and every calendar day delay in finishing the work.

During road closures, the work must progress continuously until the work is complete and the roadway is fully reopened to traffic.

Item No. 24:

Q: The bid schedule does not include any bid items for temporary striping during construction, between phases or after intersection reconstruction. When a phase is complete or an intersection is reconstructed, is the city requiring permanent striping or will temporary striping be required? If temporary striping is required, please provide a bid item with quantities so all bidders can provide the same pricing.

A: Per Section 10.03, all traffic control devices, including delineators, temporary traffic stripes and pavement markings, barricades and barriers, warning signs and lights, temporary fencing, and flaggers, must comply with the latest version of MUTCD and in accordance with Section 11 of the City Standard Specification. Compensation is included under Item No. 2 – Traffic Control System.”

Item No. 25:

Q: Specification 5.38 Utility Coordination provided a table of utility owners, locations, and time to complete the work. We cannot find these relocations in the Drainage and Utility sheets, can the plans sheets numbers be provided that show these utility relocations?

A: The utility work identified in Section 5.38 consists primarily of adjustments of existing utility facilities to proposed grade, to be performed by the respective utility owners. This is shown on the DU Sheets. Notices to Owner have been issued, and the City’s Resident Engineer has initiated coordination with the utility owners. The Contractor shall coordinate the timing of this work with the Resident Engineer and the applicable utility owners in accordance with Section 5.38.

Item No. 26:

Q: Note 3 on the DU-1 Plans for Stages 1-3 states "All Storm Drain Pipelines shall be inspected and tested per section 16-26 thru 16-33 of the City of Turlock Standards. These standards include Ball and Flushing, Mandrel Test, Leakage Tests, Air Test and Video Inspection. However, Bid Item 9 is labeled "Video Sewer and Storm Drain" and no other testing is mentioned. Does the project require Video Inspection per Project Specification Section 10.09 or all The City of Turlock Requirements per City Specification 16-26 thru 16-33?

A: Video inspection in accordance with Section 10.09 is required for the existing sewer and storm drain mains located within the roadway reconstruction limits.

Storm drain pipe installed as part of the project shall be inspected and tested in accordance with the applicable City of Turlock Standard Specifications referenced in Note 3 on the Drainage and Utility sheets.

Item No. 27:

Q: In reference to the Utility Table shown in Specification 5.38, Can the City provide the following clarifications: In which phase or stage do these utility relocations need to be scheduled? Can all the relocations occur and start at the same time? Will the utility owners complete all the work in consecutive days or over multiple mobilizations?

A: As noted in the Item No. 22, Notices to Owner have been issued and the City's Resident Engineer has initiated coordination with the utility owners. The utility adjustments are not assigned to a specific phase or stage. The Contractor shall coordinate the timing and sequencing of this work with the Resident Engineer and the respective utility owners in accordance with Section 5.38.

The City does not guarantee that the utility work will begin concurrently, occur on consecutive days, or be completed in a single mobilization.

Item No. 28:

Q: The Traffic Handling Plans provide Typical cross sections showing the outside lane closures. Each of these cross sections shows the sidewalk on both sides of the road being reconstructed in the "Outside Lane Closure" Phase. Will the contractor be allowed to reconstruct the sidewalk on each side of the road at the same time during the Outside Lane Closure phases?

A: In accordance with Specification Sections 10.03 and 10.15, the Contractor must maintain pedestrian routes for all work within the public right-of-way. The Contractor shall provide signage and pedestrian re-routing options prior to closures for the City's authorization. The Contractor will not be allowed to close the pedestrian routes on both sides of Geer Rd at the same time.

Item No. 29:

Q: The pre-bid conference was recently held and Addendum No. 1 has already resulted in the replacement of fifteen (15) grading plan sheets to include existing contour information that was not included in the original Contract Documents. The revised grading sheets contain information that is material to the evaluation of grading, roadway excavation, profile adjustments, quantity verification, subcontractor pricing, and overall project risk.

Given the size and complexity of this project, with an estimated construction value of approximately \$26 million, bidders require sufficient time to evaluate the revised grading information, reassess quantities, review the impacts of the revised plans on construction means and methods, and obtain updated quotations from subcontractors and suppliers. For reference, Caltrans contract 10-1K6204 (roundabout) with an EE of \$4.8 advertised on 6/1 with a final bid date of 7/16 (6.5 weeks). The Geer Road project advertised on 6/23, is a very large and complex project and only allows 5 weeks for bidding.

The addition of existing contour information was issued in response to bidder questions regarding the ability to accurately evaluate quantities from the original plan set. As such, the revised plans constitute a significant modification to the Contract Documents rather than a minor clarification. In the interest of obtaining the most accurate and competitive bids and ensuring that all bidders have adequate time to fully evaluate the original and recently revised Contract Documents, please extend the bid date by a minimum of fourteen (14) calendar days.

Providing additional time will allow bidders to properly assess the impacts of the revised plans, incorporate any subsequent addenda, and submit bids based on a complete understanding of the work. Failure to provide adequate time for review of material plan revisions may result in increased contingency pricing and reduced bid competitiveness, which is not in the best interest of either the City or the bidding community.

A: The request to extend the bid opening date has been reviewed and is denied.

The information provided in Addendum No. 1 is intended to supplement the Contract Documents and does not change the scope of work or constitute a material revision requiring an extension of the bidding period. Bidders shall prepare their bids based on the Contract Documents, including all issued addenda. The bid opening date remains unchanged.

End of Addendum No. 2

CITY OF TURLOCK

Project No. 23-052 Geer Road Pavement Rehabilitation Phases 1, 2, and 3

BID SCHEDULE

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
General						
1.		POTHOLE EXISTING UTILITIES	1	LS	\$_____	\$_____
2.		TRAFFIC CONTROL SYSTEM	1	LS	\$_____	\$_____
3.		PORTABLE CHANGEABLE MESSAGE SIGN	1	LS	\$_____	\$_____
4.		CONSTRUCTION FUNDING SIGNS	16	EA	\$_____	\$_____
5.		JOB SITE MANAGEMENT	1	LS	\$_____	\$_____
6.		LEAD AND HAZARDOUS MATERIALS COMPLIANCE PLAN	1	LS	\$_____	\$_____
7.		PREPARE STORM WATER POLLUTION PREVENTION PLAN	1	LS	\$_____	\$_____
8.		EROSION AND DUST CONTROL BMP'S	1	LS	\$_____	\$_____
9.		VIDEO SEWER AND STORM DRAIN	1	LS	\$_____	\$_____
10.		CONSTRUCTION STAKING	1	LS	\$_____	\$_____
11.		CLEARING AND GRUBBING	1	LS	\$_____	\$_____
12.		TRAINING	17000	HOURLY	\$ <u>0.8</u>	\$ <u>13,600</u>
13.		MONUMENT PRESERVATION	1	EA	\$_____	\$_____
14.		PLANTING PROTECTION DURING CONSTRUCTION	1	LS	\$_____	\$_____
Phase 1						
15.		REMOVE TREE	9	EA	\$_____	\$_____
16.		REMOVE FENCE	220	LF	\$_____	\$_____
17.		REMOVE GATE	4	EA	\$_____	\$_____
18.		REMOVE CONCRETE HEADWALL	1	EA	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
19.		REMOVE STORM DRAIN PIPE	9	LF	\$_____	\$_____
20.		REMOVE DRAINAGE INLET	4	EA	\$_____	\$_____
21.		REMOVE ROADSIDE SIGN (ONE-POST)	3	EA	\$_____	\$_____
22.		REMOVE CONCRETE (CURB)	5230	LF	\$_____	\$_____
23.		REMOVE CONCRETE (CURB AND GUTTER)	2800	LF	\$_____	\$_____
24.		REMOVE CONCRETE (FLATWORK)	1800	SY	\$_____	\$_____
25.		COLD PLANING AC PAVEMENT	28400	SQYD	\$_____	\$_____
26.	(F)	ROADWAY EXCAVATION	2590	CY	\$_____	\$_____
27.		UNSUITABLE MATERIAL	240	CY	\$_____	\$_____
28.		DECOMPOSED GRANITE	260	SF	\$_____	\$_____
29.		AGGREGATE BASE CLASS 2	150	CY	\$_____	\$_____
30.		FULL DEPTH RECLAMATION CEMENT	18210	SQYD	\$_____	\$_____
31.		CEMENT (FULL DEPTH RECLAMATION-CEMENT)	535	TON	\$_____	\$_____
32.		MIX DESIGN	1	LS	\$_____	\$_____
33.		HOT MIX ASPHALT (TYPE A)	10080	TON	\$_____	\$_____
34.		SHALLOW UTILITY ALTERNATIVE PAVEMENT SECTION	8500	SF	\$_____	\$_____
35.		MINOR CONCRETE (CURB AND GUTTER)	2750	LF	\$_____	\$_____
36.		MINOR CONCRETE (RETAINING CURB)	190	LF	\$_____	\$_____
37.		MINOR CONCRETE (VERTICAL CURB)	2970	LF	\$_____	\$_____
38.		MINOR CONCRETE (LANDSCAPING MEDIAN CURB)	2130	LF	\$_____	\$_____
39.		MINOR CONCRETE (CURB RAMP)	2820	SF	\$_____	\$_____
40.		MINOR CONCRETE (SIDEWALK)	15450	SF	\$_____	\$_____
41.		MINOR CONCRETE (RESIDENTIAL DRIVEWAY)	1430	SF	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
42.		MINOR CONCRETE (ALLEY/COMMERCIAL DRIVEWAY)	2410	SF	\$_____	\$_____
43.		MINOR CONCRETE (TEXTURED PAVEMENT)	2700	SF	\$_____	\$_____
44.		DETECTABLE WARNING SURFACE (TRUNCATED DOMES)	510	SF	\$_____	\$_____
45.		18" REINFORCED CONCRETE PIPE	59	LF	\$_____	\$_____
46.		INSTALL DRAINAGE INLET (SD-3)	4	EA	\$_____	\$_____
47.		ADJUST DRAINAGE INLET TO GRADE	7	EA	\$_____	\$_____
48.		ADJUST MANHOLE COVER TO GRADE (UTILITY)	15	EA	\$_____	\$_____
49.		ADJUST STORM DRAIN MANHOLE COVER TO GRADE	21	EA	\$_____	\$_____
50.		ADJUST UTILITY COVER TO GRADE	94	EA	\$_____	\$_____
51.		ADJUST UTILITY INTO TRAFFIC RATED BOXES	2	EA	\$_____	\$_____
52.		RESET POST (LICENSE PLATE READER)	1	EA	\$_____	\$_____
53.		INSTALL WOOD FENCE	90	LF	\$_____	\$_____
54.		INSTALL WOOD GATE	2	EA	\$_____	\$_____
55.		CHAIN LINK FENCE (TYPE CL-4)	110	LF	\$_____	\$_____
56.		CHAIN LINK GATE (TYPE CL-4)	3	EA	\$_____	\$_____
57.		ROADSIDE SIGN (ONE-POST)	51	EA	\$_____	\$_____
58.		RELOCATE ROADSIDE SIGN (ONE-POST)	6	EA	\$_____	\$_____
59.		PAINT CURB (2 COAT)	640	LF	\$_____	\$_____
60.		THERMOPLASTIC TRAFFIC STRIPE	21540	LF	\$_____	\$_____
61.		THERMOPLASTIC PAVEMENT MARKINGS	10170	SF	\$_____	\$_____
62.		THERMOPLASTIC PAVEMENT MARKING (GREEN METHYL METHACRYLATE)	390	SF	\$_____	\$_____
63.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/ GOLDEN STATE BLVD)	1	LS	\$_____	\$_____
64.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/CANAL DR)	1	LS	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
65.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/HAWKEYE DR)	1	LS	\$_____	\$_____
66.		RECTANGULAR RAPID FLASHING BEACON SYSTEM (RRFB) (GEER RD/STARR AVE)	1	LS	\$_____	\$_____
67.		RECTANGULAR RAPID FLASHING BEACON SYSTEM (RRFB) (GEER RD/20TH CENTURY BLVD)	1	LS	\$_____	\$_____
68.		MODIFY STREET LIGHTING SYSTEM (GEER ROAD BETWEEN GOLDEN STATE BLVD AND CANAL DR)	1	LS	\$_____	\$_____
Phase 2						
69.		REMOVE BOLLARD	4	EA	\$_____	\$_____
70.		REMOVE TREE	27	EA	\$_____	\$_____
71.		REMOVE FENCE	120	LF	\$_____	\$_____
72.		REMOVE DRAINAGE INLET	1	EA	\$_____	\$_____
73.		REMOVE UTILITY BOX	2	EA	\$_____	\$_____
74.		REMOVE BACKFLOW PREVENTER	1	EA	\$_____	\$_____
75.		REMOVE ROADSIDE SIGN (ONE-POST)	4	EA	\$_____	\$_____
76.		REMOVE CONCRETE (CURB)	8760	LF	\$_____	\$_____
77.		REMOVE CONCRETE (CURB AND GUTTER)	4900	LF	\$_____	\$_____
78.		REMOVE CONCRETE (FLATWORK)	4620	SY	\$_____	\$_____
79.		COLD PLANING AC PAVEMENT	42130	SQYD	\$_____	\$_____
80.	(F)	ROADWAY EXCAVATION	3355	CY	\$_____	\$_____
81.		UNSUITABLE MATERIAL	195	CY	\$_____	\$_____
82.		AGGREGATE BASE CLASS 2	230	CY	\$_____	\$_____
83.		FULL DEPTH RECLAMATION CEMENT	34050	SQYD	\$_____	\$_____
84.		CEMENT (FULL DEPTH RECLAMATION-CEMENT)	1000	TON	\$_____	\$_____
85.		MIX DESIGN	1	LS	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
86.		HOT MIX ASPHALT (TYPE A)	13140	TON	\$_____	\$_____
87.		SHALLOW UTILITY ALTERNATIVE PAVEMENT SECTION	12000	SF	\$_____	\$_____
88.		MINOR CONCRETE (CURB AND GUTTER)	4800	LF	\$_____	\$_____
89.		MINOR CONCRETE (RETAINING CURB)	70	LF	\$_____	\$_____
90.		MINOR CONCRETE (VERTICAL CURB)	5310	LF	\$_____	\$_____
91.		MINOR CONCRETE (LANDSCAPING MEDIAN CURB)	3580	LF	\$_____	\$_____
92.		MINOR CONCRETE (VALLEY GUTTER)	140	LF	\$_____	\$_____
93.		MINOR CONCRETE (CURB RAMP)	2730	SF	\$_____	\$_____
94.		MINOR CONCRETE (SIDEWALK)	33750	SF	\$_____	\$_____
95.		MINOR CONCRETE (RESIDENTIAL DRIVEWAY)	150	SF	\$_____	\$_____
96.		MINOR CONCRETE (ALLEY/COMMERCIAL DRIVEWAY)	6290	SF	\$_____	\$_____
97.		MINOR CONCRETE (TEXTURED PAVEMENT)	5040	SF	\$_____	\$_____
98.		MINOR CONCRETE (BUS TURNOUT)	1260	SF	\$_____	\$_____
99.		MINOR CONCRETE (MAILBOX PAD)	20	SF	\$_____	\$_____
100.		DETECTABLE WARNING SURFACE (TRUNCATED DOMES)	580	SF	\$_____	\$_____
101.		18" REINFORCED CONCRETE PIPE	10	LF	\$_____	\$_____
102.		INSTALL DRAINAGE INLET (SD-3)	1	EA	\$_____	\$_____
103.		ADJUST DRAINAGE INLET TO GRADE	12	EA	\$_____	\$_____
104.		ADJUST MANHOLE COVER TO GRADE (UTILITY)	21	EA	\$_____	\$_____
105.		ADJUST STORM DRAIN MANHOLE COVER TO GRADE	20	EA	\$_____	\$_____
106.		ADJUST UTILITY COVER TO GRADE	132	EA	\$_____	\$_____
107.		RELOCATE MAILBOX	1	EA	\$_____	\$_____
108.		VINYL FENCE	110	LF	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
109.		ROADSIDE SIGN (ONE-POST)	43	EA	\$_____	\$_____
110.		RELOCATE ROADSIDE SIGN (ONE-POST)	8	EA	\$_____	\$_____
111.		RESET ROADSIDE SIGN (ONE-POST)	5	EA	\$_____	\$_____
112.		RESET BUS SHELTER	4	EA	\$_____	\$_____
113.		RESET TRASH RECEPTACLE	3	EA	\$_____	\$_____
114.		PAINT CURB (2 COAT)	850	LF	\$_____	\$_____
115.		THERMOPLASTIC TRAFFIC STRIPE	38000	LF	\$_____	\$_____
116.		THERMOPLASTIC PAVEMENT MARKINGS	9360	SF	\$_____	\$_____
117.		THERMOPLASTIC PAVEMENT MARKING (GREEN METHYL METHACRYLATE)	2240	SF	\$_____	\$_____
118.		CHECK AND TEST SCHOOL EXISTING IRRIGATION SYSTEM	1	LS	\$_____	\$_____
119.		MODIFY EXISTING SCHOOL IRRIGATION SYSTEM FOR NEW PLANTING	1	LS	\$_____	\$_____
120.		QUICK COUPLING VALVE ASSEMBLY	1	EA	\$_____	\$_____
121.		BALL VALVE ASSEMBLY	1	EA	\$_____	\$_____
122.		REMOTE CONTROL VALVE ASSEMBLY	2	EA	\$_____	\$_____
123.		IRRIGATION MAINLINE	56	LF	\$_____	\$_____
124.		LATERAL LINE	868	LF	\$_____	\$_____
125.		DEEP WATER BUBBLER ASSEMBLY	44	EA	\$_____	\$_____
126.		CONTROL WIRE AND CONDUIT	1	LS	\$_____	\$_____
127.		TREES, 36" BOX	22	EA	\$_____	\$_____
128.		LINEAR ROOT BARRIER	230	LF	\$_____	\$_____
129.		DARK BROWN RUBBER BARK MULCH - 3" THICK	83	CY	\$_____	\$_____
130.		SOIL AMENDMENT AND FERTILIZER	8400	SF	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
131.		LANDSCAPE MAINTENANCE AND ESTABLISHMENT PERIOD, 365 DAYS	1	LS	\$_____	\$_____
132.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/NORTH AVE)	1	LS	\$_____	\$_____
133.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/PEDRAS AVE)	1	LS	\$_____	\$_____
134.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/TUOLUMNE RD)	1	LS	\$_____	\$_____
135.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/MINNESOTA AVE)	1	LS	\$_____	\$_____
Phase 3						
136.		REMOVE STORM DRAIN PIPE	13	LF	\$_____	\$_____
137.		REMOVE DRAINAGE INLET	1	EA	\$_____	\$_____
138.		REMOVE ROADSIDE SIGN (ONE-POST)	9	EA	\$_____	\$_____
139.		REMOVE CONCRETE (CURB)	3520	LF	\$_____	\$_____
140.		REMOVE CONCRETE (CURB AND GUTTER)	1060	LF	\$_____	\$_____
141.		REMOVE CONCRETE (FLATWORK)	870	SY	\$_____	\$_____
142.		COLD PLANING AC PAVEMENT	46640	SQYD	\$_____	\$_____
143.	(F)	SHOULDER BACKING	10	CY	\$_____	\$_____
144.	(F)	ROADWAY EXCAVATION	3710	CY	\$_____	\$_____
145.		UNSUITABLE MATERIAL	210	CY	\$_____	\$_____
146.		AGGREGATE BASE CLASS 2	3	CY	\$_____	\$_____
147.		FULL DEPTH RECLAMATION CEMENT	9750	SQYD	\$_____	\$_____
148.		CEMENT (FULL DEPTH RECLAMATION-CEMENT)	290	TON	\$_____	\$_____
149.		MIX DESIGN	1	LS	\$_____	\$_____
150.		HOT MIX ASPHALT (TYPE A)	17080	TON	\$_____	\$_____
151.		SHALLOW UTILITY ALTERNATIVE PAVEMENT SECTION	2000	SF	\$_____	\$_____
152.		MINOR CONCRETE (CURB AND GUTTER)	1080	LF	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
153.		MINOR CONCRETE (RETAINING CURB)	60	LF	\$_____	\$_____
154.		MINOR CONCRETE (VERTICAL CURB)	4470	LF	\$_____	\$_____
155.		MINOR CONCRETE (MEDIAN THRU DRAIN)	380	LF	\$_____	\$_____
156.		MINOR CONCRETE (LANDSCAPING MEDIAN CURB)	5540	LF	\$_____	\$_____
157.		MINOR CONCRETE (CURB RAMP)	1580	SF	\$_____	\$_____
158.		MINOR CONCRETE (SIDEWALK)	5490	SF	\$_____	\$_____
159.		MINOR CONCRETE (ALLEY/COMMERCIAL DRIVEWAY)	1420	SF	\$_____	\$_____
160.		MINOR CONCRETE (TEXTURED PAVEMENT)	4780	SF	\$_____	\$_____
161.		DETECTABLE WARNING SURFACE (TRUNCATED DOMES)	710	SF	\$_____	\$_____
162.		18" REINFORCED CONCRETE PIPE	27	LF	\$_____	\$_____
163.		INSTALL DRAINAGE INLET (SD-3)	1	EA	\$_____	\$_____
164.		ADJUST DRAINAGE INLET TO GRADE	5	EA	\$_____	\$_____
165.		ADJUST MANHOLE COVER TO GRADE (UTILITY)	8	EA	\$_____	\$_____
166.		ADJUST STORM DRAIN MANHOLE COVER TO GRADE	15	EA	\$_____	\$_____
167.		ADJUST UTILITY COVER TO GRADE	67	EA	\$_____	\$_____
168.		ROADSIDE SIGN (ONE-POST)	25	EA	\$_____	\$_____
169.		RELOCATE ROADSIDE SIGN (ONE-POST)	2	EA	\$_____	\$_____
170.		RESET ROADSIDE SIGN (ONE-POST)	3	EA	\$_____	\$_____
171.		PAINT CURB (2 COAT)	480	LF	\$_____	\$_____
172.		THERMOPLASTIC TRAFFIC STRIPE	39600	LF	\$_____	\$_____
173.		THERMOPLASTIC PAVEMENT MARKINGS	12040	SF	\$_____	\$_____
174.		THERMOPLASTIC PAVEMENT MARKING (GREEN METHYL METHACRYLATE)	3330	SF	\$_____	\$_____
175.		IRRIGATION CONTROLLER, 8 STATION WITH PEDESTAL ENCLOSURE	3	EA	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
176.		REDUCED PRESSURE BACKFLOW ASSEMBLY WITH ENCLOSURE	2	EA	\$_____	\$_____
177.		WATER METER, 1"	2	EA	\$_____	\$_____
178.		MASTER VALVE ASSEMBLY	3	EA	\$_____	\$_____
179.		FLOW SENSOR ASSEMBLY	3	EA	\$_____	\$_____
180.		QUICK COUPLING VALVE ASSEMBLY	9	EA	\$_____	\$_____
181.		BALL VALVE ASSEMBLY	6	EA	\$_____	\$_____
182.		REMOTE CONTROL VALVE ASSEMBLY	6	EA	\$_____	\$_____
183.		IRRIGATION MAINLINE	1740	LF	\$_____	\$_____
184.		LATERAL LINE	1672	LF	\$_____	\$_____
185.		IRRIGATION SLEEVE	1045	LF	\$_____	\$_____
186.		SPLICE BOX	6	EA	\$_____	\$_____
187.		DEEP WATER BUBBLER ASSEMBLY	130	EA	\$_____	\$_____
188.		CONTROL WIRE AND CONDUIT	1	LS	\$_____	\$_____
189.		TREES, 36" BOX	46	EA	\$_____	\$_____
190.		TREES, 24" BOX	21	EA	\$_____	\$_____
191.		LINEAR ROOT BARRIER	1580	LF	\$_____	\$_____
192.		DARK BROWN RUBBER BARK MULCH - 3" THICK	200	CY	\$_____	\$_____
193.		IMPORTED TOP SOIL - 12" DEEP	800	CY	\$_____	\$_____
194.		SOIL AMENDMENT AND FERTILIZER	21580	SF	\$_____	\$_____
195.		MAINTENANCE AND ESTABLISHMENT PERIOD, 365 DAYS	1	LS	\$_____	\$_____
196.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/MONTE VISTA AVE)	1	LS	\$_____	\$_____
197.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/CHRISTOFFERSON PKWY)	1	LS	\$_____	\$_____
198.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/SPRINGER DR)	1	LS	\$_____	\$_____

Item	Final Pay Item (F)	Description	Quantity	Unit	Unit Price	Total
199.		MODIFYING TRAFFIC SIGNAL SYSTEM (GEER RD/TAYLOR RD)	1	LS	\$_____	\$_____
200.		RECTANGULAR RAPID FLASHING BEACON SYSTEM (GEER RD/CALAVERAS WAY)	1	LS	\$_____	\$_____
201.		ELECTRICAL SERVICE FOR IRRIGATION (GEER RD/CALEVERAS WAY)	1	LS	\$_____	\$_____
202.		ELECTRICAL SERVICE FOR IRRIGATION (GEER RD NEAR CHRISTOFFERSON PKWY)	1	LS	\$_____	\$_____
203.		ELECTRICAL SERVICE FOR IRRIGATION (GEER RD NEAR SPRINGER DR)	1	LS	\$_____	\$_____
Phases 1, 2, and 3						
204.		MOBILIZATION (10%)	1	LS	\$_____	\$_____
TOTAL BID						\$_____

(F) denotes final pay item per Section 9-1.02C of the State Standard Specifications.

BIDDER'S BOND

KNOW ALL MEN BY THESE PRESENTS:

That we _____ as
BIDDER, and _____ as
SURETY a corporation duly organized under the laws of the State of _____
and duly licensed to become sole Surety on bonds required and authorized by the State of California,
as SURETY, are held and firmly bound unto the City of Turlock, hereinafter called the City, in the
penal sum of TEN PERCENT (10%) OF THE TOTAL AMOUNT OF THE BID of the Bidder above
named, submitted by said Bidder to the City, for the work described below, for the payment of which
sum in lawful money of the United States, well and truly to be made, we bind ourselves, our heirs,
executors, administrators and successors, jointly and severally, firmly by these presents. In no case
shall the liability of the Surety hereunder exceed the sum _____
Dollars (\$ _____).

THE CONDITION OF THIS OBLIGATION IS SUCH THAT, whereas the bidder has submitted the
above-mentioned bid to the City for certain construction specifically described as follows for which
bids are to be opened at Municipal Services Department, City Hall, 156 S. Broadway Suite 150,
Turlock, California, on

_____, _____, 20____, at_____.
(day) (date) (time)
for

Project No. 23-052 Geer Road Pavement Rehabilitation Phases 1, 2, and 3

NOW, THEREFORE, if the aforesaid Bidder is awarded the contract and, within the time manner
required under the specifications after the prescribed forms are presented to him for signature, enters
into a written contract in the prescribed form in accordance with the bid, and files the two bonds with
the City, one to guarantee faithful performance and the other to guarantee payment for labor and
materials as required by law, then obligation shall be null and void; otherwise, it shall be and remain
in full force and virtue.

In the event suit is brought upon this bond by the Obligee and judgment is recovered, the Surety shall
pay all costs incurred by the Obligee in such a suit, including a reasonable attorney's fee to be fixed
by the court.

"General Decision Number: CA20260018 07/14/2026

State: California

Construction Types: Building, Heavy and Highway

Counties: California Counties of
Alameda, Calaveras, Contra Costa,
Fresno, Kings, Madera, Mariposa, Merced,
Monterey, San Benito, San Francisco, San
Joaquin, San Mateo, Santa Clara, Santa
Cruz, Stanislaus and Tuolumne

Building Construction Projects

Dredging Projects-Includes Dredging Projects (does not include hopper dredge work)

Heavy Construction Projects (excludes water well drilling)

Highway Construction Projects

Modification Number	Publication Date
4	01/30/2026
5	05/18/2026
6	07/14/2026

ASBE0016-004 05/01/2025

	Rates	Fringes
ASBESTOS REMOVAL WORKER/HAZARDOUS MATERIAL HANDLER: INCLUDES PREPARATION, WETTING, STRIPPING, REMOVAL, SCRAPPING, VACUUMING, BAGGING AND DISPOSING OF ALL INSULATION MATERIALS FROM MECHANICAL SYSTEMS, WHETHER THEY CONTAIN ASBESTOS OR NOT (AREA 1: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN JOAQUIN, SANTA CRUZ, STANISLAUS, & TOULMNE COUNTIES).....\$ 34.56		11.40
ASBESTOS REMOVAL WORKER/HAZARDOUS MATERIAL HANDLER: INCLUDES PREPARATION, WETTING, STRIPPING, REMOVAL, SCRAPPING, VACUUMING, BAGGING AND DISPOSING OF ALL INSULATION MATERIALS FROM MECHANICAL SYSTEMS, WHETHER THEY CONTAIN ASBESTOS OR NOT (AREA 2: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, &		

SANTA CLARA COUNTIES).....	\$ 44.73	12.75

ASBE0016-008 01/01/2024		
	Rates	Fringes
ASBESTOS WORKERS/INSULATOR: INCLUDES THE APPLICATION OF ALL INSULATING MATERIALS, PROTECTIVE COVERINGS, COATINGS, AND FINISHES TO ALL TYPES OF MECHANICAL SYSTEMS (AREA 1: ALAMEDA, CONTRA COSTA, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN MATEO, SANTA CLARA, & SANTA CRUZ).....	\$ 84.76	25.07
ASBESTOS WORKERS/INSULATOR: INCLUDES THE APPLICATION OF ALL INSULATING MATERIALS, PROTECTIVE COVERINGS, COATINGS, AND FINISHES TO ALL TYPES OF MECHANICAL SYSTEMS (AREA 2: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS, & TUOLUMNE).....	\$ 64.56	25.07

BOIL0549-001 01/01/2021		
	Rates	Fringes
BOILERMAKER (AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO & SANTA CLARA COUNTIES).....	\$ 49.62	41.27
BOILERMAKER (AREA 2: REMAINING COUNTIES).....	\$ 45.60	38.99

BRCA0003-001 08/01/2024		
	Rates	Fringes
MARBLE FINISHER.....	\$ 42.06	19.80

BRCA0003-003 08/01/2024		
	Rates	Fringes
MARBLE MASON.....	\$ 61.72	30.31

BRCA0003-005 05/01/2024		
	Rates	Fringes
BRICKLAYER (1) FRESNO, KINGS, MADERA, MARIPOSA, MERCED.....	\$ 51.17	25.80
BRICKLAYER (7) SAN FRANCISCO, SAN MATEO.....	\$ 57.02	28.50
BRICKLAYER (9) CALAVERAS, SAN JOAQUIN, STANISLAUS, TOULUMNE.....	\$ 52.76	25.01
BRICKLAYER (16) MONTEREY, SANTA CRUZ.....	\$ 54.18	27.82
BRICKLAYER (8) ALAMEDA, CONTRA COSTA, SAN BENITO, SANTA CLARA).....	\$ 56.94	26.28

BRCA0003-008 07/01/2024		

	Rates	Fringes
TERRAZZO FINISHER.....	\$ 44.93	20.98
TERRAZZO WORKER/SETTER.....	\$ 60.58	29.79

BRCA0003-011 04/01/2024

	Rates	Fringes
TILE FINISHER (AREA 1: ALAMEDA, CONTRA COSTA, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN MATEO, SANTA CLARA, SANTA CRUZ).....	\$ 37.75	19.28
TILE FINISHER (AREA 2: CALAVERAS, SAN JOAQUIN, STANISLAUS, TUOLUMNE).....	\$ 34.76	19.22
TILE FINISHER (AREA 3: FRESNO, KINGS, MADERA, MARIPOSA, MERCED).....	\$ 32.68	18.32
TILE LAYER (AREA 1: ALAMEDA, CONTRA COSTA, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN MATEO, SANTA CLARA, SANTA CRUZ).....	\$ 59.92	22.62
TILE LAYER (AREA 2: CALAVERAS, SAN JOAQUIN, STANISLAUS, TUOLUMNE).....	\$ 55.17	22.52
TILE LAYER (AREA 3: FRESNO, KINGS, MADERA, MARIPOSA, MERCED).....	\$ 50.28	22.05

CARP0022-001 07/01/2023

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (SAN FRANCISCO COUNTY).....	\$ 60.39	33.52
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (SAN FRANCISCO COUNTY).....	\$ 60.54	33.52
CARPENTERS: JOURNEYMAN CARPENTER (SAN FRANCISCO COUNTY).....	\$ 60.39	33.52
CARPENTERS: MILLWRIGHT (SAN FRANCISCO COUNTY).....	\$ 60.49	35.11

CARP0034-001 07/01/2021

	Rates	Fringes
DIVER: ASSISTANT TENDER, ROV TENDER/TECHNICIAN. DEPTH PAY (SURFACE DIVING): 50 TO 100 FT, \$2.00 PER FOOT; 101 TO 150 FT, \$3.00 PER FOOT; 151 TO 220 FT, \$4.00 PER FOOT; 221 FT. AND DEEPER, \$5.00 PER FOOT. (SATURATION DIVING: THE STANDBY RATE SHALL APPLY UNTIL SATURATION STARTS. THE SATURATION DIVING RATE APPLIES WHEN DIVERS ARE UNDER PRESSURE CONTINUOUSLY UNTIL WORK TASK AND DECOMPRESSION ARE COMPLETE. THE DIVER RATE SHALL BE PAID FOR ALL SATURATION HOURS.) (DIVING IN ENCLOSURES: WHERE IT IS NECESSARY FOR DIVERS TO ENTER PIPES OR TUNNELS, OR OTHER ENCLOSURES WHERE THERE IS NO VERTICAL		

ASCENT, THE FOLLOWING PREMIUM SHALL BE PAID:
 DISTANCE TRAVELED FROM ENTRANCE 26 FEET TO 300
 FEET: \$1.00 PER FOOT. WHEN IT IS NECESSARY FOR A
 DIVER TO ENTER ANY PIPE, TUNNEL OR OTHER ENCLOSURE
 LESS THAN 48"" IN HEIGHT, THE PREMIUM WILL BE \$1.00
 PER FOOT.) (WORK IN COMBINATION OF
 CLASSIFICATIONS: EMPLOYEES WORKING IN ANY
 COMBINATION OF CLASSIFICATIONS WITHIN THE DIVING
 CREW (EXCEPT DIVE SUPERVISOR) IN A SHIFT ARE PAID
 IN THE CLASSIFICATION WITH THE HIGHEST RATE FOR
 THAT SHIFT.).....\$ 54.10 34.69
 DIVER: DIVER STANDBY. DEPTH PAY (SURFACE DIVING):
 50 TO 100 FT, \$2.00 PER FOOT; 101 TO 150 FT, \$3.00
 PER FOOT; 151 TO 220 FT, \$4.00 PER FOOT; 221 FT.
 AND DEEPER, \$5.00 PER FOOT. (SATURATION DIVING:
 THE STANDBY RATE SHALL APPLY UNTIL SATURATION
 STARTS. THE SATURATION DIVING RATE APPLIES WHEN
 DIVERS ARE UNDER PRESSURE CONTINUOUSLY UNTIL WORK
 TASK AND DECOMPRESSION ARE COMPLETE. THE DIVER RATE
 SHALL BE PAID FOR ALL SATURATION HOURS.) (DIVING IN
 ENCLOSURES: WHERE IT IS NECESSARY FOR DIVERS TO
 ENTER PIPES OR TUNNELS, OR OTHER ENCLOSURES WHERE
 THERE IS NO VERTICAL ASCENT, THE FOLLOWING PREMIUM
 SHALL BE PAID: DISTANCE TRAVELED FROM ENTRANCE 26
 FEET TO 300 FEET: \$1.00 PER FOOT. WHEN IT IS
 NECESSARY FOR A DIVER TO ENTER ANY PIPE, TUNNEL OR
 OTHER ENCLOSURE LESS THAN 48"" IN HEIGHT, THE
 PREMIUM WILL BE \$1.00 PER FOOT.) (WORK IN
 COMBINATION OF CLASSIFICATIONS: EMPLOYEES WORKING
 IN ANY COMBINATION OF CLASSIFICATIONS WITHIN THE
 DIVING CREW (EXCEPT DIVE SUPERVISOR) IN A SHIFT ARE
 PAID IN THE CLASSIFICATION WITH THE HIGHEST RATE
 FOR THAT SHIFT.).....\$ 60.51 34.69
 DIVER: DIVER TENDER. DEPTH PAY (SURFACE DIVING):
 50 TO 100 FT, \$2.00 PER FOOT; 101 TO 150 FT, \$3.00
 PER FOOT; 151 TO 220 FT, \$4.00 PER FOOT; 221 FT.
 AND DEEPER, \$5.00 PER FOOT. (SATURATION DIVING:
 THE STANDBY RATE SHALL APPLY UNTIL SATURATION
 STARTS. THE SATURATION DIVING RATE APPLIES WHEN
 DIVERS ARE UNDER PRESSURE CONTINUOUSLY UNTIL WORK
 TASK AND DECOMPRESSION ARE COMPLETE. THE DIVER RATE
 SHALL BE PAID FOR ALL SATURATION HOURS.) (DIVING IN
 ENCLOSURES: WHERE IT IS NECESSARY FOR DIVERS TO
 ENTER PIPES OR TUNNELS, OR OTHER ENCLOSURES WHERE
 THERE IS NO VERTICAL ASCENT, THE FOLLOWING PREMIUM
 SHALL BE PAID: DISTANCE TRAVELED FROM ENTRANCE 26
 FEET TO 300 FEET: \$1.00 PER FOOT. WHEN IT IS
 NECESSARY FOR A DIVER TO ENTER ANY PIPE, TUNNEL OR
 OTHER ENCLOSURE LESS THAN 48"" IN HEIGHT, THE

PREMIUM WILL BE \$1.00 PER FOOT.) (WORK IN COMBINATION OF CLASSIFICATIONS: EMPLOYEES WORKING IN ANY COMBINATION OF CLASSIFICATIONS WITHIN THE DIVING CREW (EXCEPT DIVE SUPERVISOR) IN A SHIFT ARE PAID IN THE CLASSIFICATION WITH THE HIGHEST RATE FOR THAT SHIFT.).....\$ 59.51	34.69
DIVER: DIVER WET. DEPTH PAY (SURFACE DIVING): 50 TO 100 FT, \$2.00 PER FOOT; 101 TO 150 FT, \$3.00 PER FOOT; 151 TO 220 FT, \$4.00 PER FOOT; 221 FT. AND DEEPER, \$5.00 PER FOOT. (SATURATION DIVING: THE STANDBY RATE SHALL APPLY UNTIL SATURATION STARTS. THE SATURATION DIVING RATE APPLIES WHEN DIVERS ARE UNDER PRESSURE CONTINUOUSLY UNTIL WORK TASK AND DECOMPRESSION ARE COMPLETE. THE DIVER RATE SHALL BE PAID FOR ALL SATURATION HOURS.) (DIVING IN ENCLOSURES: WHERE IT IS NECESSARY FOR DIVERS TO ENTER PIPES OR TUNNELS, OR OTHER ENCLOSURES WHERE THERE IS NO VERTICAL ASCENT, THE FOLLOWING PREMIUM SHALL BE PAID: DISTANCE TRAVELED FROM ENTRANCE 26 FEET TO 300 FEET: \$1.00 PER FOOT. WHEN IT IS NECESSARY FOR A DIVER TO ENTER ANY PIPE, TUNNEL OR OTHER ENCLOSURE LESS THAN 48"" IN HEIGHT, THE PREMIUM WILL BE \$1.00 PER FOOT.) (WORK IN COMBINATION OF CLASSIFICATIONS: EMPLOYEES WORKING IN ANY COMBINATION OF CLASSIFICATIONS WITHIN THE DIVING CREW (EXCEPT DIVE SUPERVISOR) IN A SHIFT ARE PAID IN THE CLASSIFICATION WITH THE HIGHEST RATE FOR THAT SHIFT.).....\$ 103.62	
	34.69
DIVER: MANIFOLD OPERATOR (MIXED GAS). DEPTH PAY (SURFACE DIVING): 50 TO 100 FT, \$2.00 PER FOOT; 101 TO 150 FT, \$3.00 PER FOOT; 151 TO 220 FT, \$4.00 PER FOOT; 221 FT. AND DEEPER, \$5.00 PER FOOT. (SATURATION DIVING: THE STANDBY RATE SHALL APPLY UNTIL SATURATION STARTS. THE SATURATION DIVING RATE APPLIES WHEN DIVERS ARE UNDER PRESSURE CONTINUOUSLY UNTIL WORK TASK AND DECOMPRESSION ARE COMPLETE. THE DIVER RATE SHALL BE PAID FOR ALL SATURATION HOURS.) (DIVING IN ENCLOSURES: WHERE IT IS NECESSARY FOR DIVERS TO ENTER PIPES OR TUNNELS, OR OTHER ENCLOSURES WHERE THERE IS NO VERTICAL ASCENT, THE FOLLOWING PREMIUM SHALL BE PAID: DISTANCE TRAVELED FROM ENTRANCE 26 FEET TO 300 FEET: \$1.00 PER FOOT. WHEN IT IS NECESSARY FOR A DIVER TO ENTER ANY PIPE, TUNNEL OR OTHER ENCLOSURE LESS THAN 48"" IN HEIGHT, THE PREMIUM WILL BE \$1.00 PER FOOT.) (WORK IN COMBINATION OF CLASSIFICATIONS: EMPLOYEES WORKING IN ANY COMBINATION OF CLASSIFICATIONS WITHIN THE DIVING CREW (EXCEPT DIVE SUPERVISOR) IN A SHIFT ARE PAID	

IN THE CLASSIFICATION WITH THE HIGHEST RATE FOR THAT SHIFT.).....\$ 64.51	34.69
DIVER: MANIFOLD OPERATOR (STANDBY). DEPTH PAY (SURFACE DIVING): 50 TO 100 FT, \$2.00 PER FOOT; 101 TO 150 FT, \$3.00 PER FOOT; 151 TO 220 FT, \$4.00 PER FOOT; 221 FT. AND DEEPER, \$5.00 PER FOOT. (SATURATION DIVING: THE STANDBY RATE SHALL APPLY UNTIL SATURATION STARTS. THE SATURATION DIVING RATE APPLIES WHEN DIVERS ARE UNDER PRESSURE CONTINUOUSLY UNTIL WORK TASK AND DECOMPRESSION ARE COMPLETE. THE DIVER RATE SHALL BE PAID FOR ALL SATURATION HOURS.) (DIVING IN ENCLOSURES: WHERE IT IS NECESSARY FOR DIVERS TO ENTER PIPES OR TUNNELS, OR OTHER ENCLOSURES WHERE THERE IS NO VERTICAL ASCENT, THE FOLLOWING PREMIUM SHALL BE PAID: DISTANCE TRAVELED FROM ENTRANCE 26 FEET TO 300 FEET: \$1.00 PER FOOT. WHEN IT IS NECESSARY FOR A DIVER TO ENTER ANY PIPE, TUNNEL OR OTHER ENCLOSURE LESS THAN 48" IN HEIGHT, THE PREMIUM WILL BE \$1.00 PER FOOT.) (WORK IN COMBINATION OF CLASSIFICATIONS: EMPLOYEES WORKING IN ANY COMBINATION OF CLASSIFICATIONS WITHIN THE DIVING CREW (EXCEPT DIVE SUPERVISOR) IN A SHIFT ARE PAID IN THE CLASSIFICATION WITH THE HIGHEST RATE FOR THAT SHIFT.).....\$ 59.51	
	34.69

CARP0034-003 07/01/2021

	Rates	Fringes
PILEDIVER.....\$ 54.10		34.69

CARP0035-007 07/01/2020

	Rates	Fringes
MODULAR FURNITURE INSTALLER: INSTALLER (AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, SANTA CLARA COUNTIES).....\$ 28.76		22.53
MODULAR FURNITURE INSTALLER: INSTALLER (AREA 2: MONTEREY, SAN BENITO, SANTA CRUZ COUNTIES).....\$ 26.11		22.53
MODULAR FURNITURE INSTALLER: INSTALLER (AREA 3: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS, TUOLUMNE COUNTIES).....\$ 25.16		22.53
MODULAR FURNITURE INSTALLER: LEAD INSTALLER (AREA 2: MONTEREY, SAN BENITO, SANTA CRUZ COUNTIES).....\$ 29.08		23.03
MODULAR FURNITURE INSTALLER: LEAD INSTALLER (AREA 3: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS, TUOLUMNE COUNTIES).\$ 27.96		23.03
MODULAR FURNITURE INSTALLER: LEAD INSTALLER (AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO,		

SANTA CLARA COUNTIES).....\$ 32.21	23.03
MODULAR FURNITURE INSTALLER: MASTER INSTALLER (AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, SANTA CLARA COUNTIES).....\$ 36.43	23.03
MODULAR FURNITURE INSTALLER: MASTER INSTALLER (AREA 2: MONTEREY, SAN BENITO, SANTA CRUZ COUNTIES).....\$ 32.71	23.03
MODULAR FURNITURE INSTALLER: MASTER INSTALLER (AREA 3: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS, TUOLUMNE COUNTIES).....\$ 31.38	23.03

CARP0035-008 08/01/2020

	Rates	Fringes
DRYWALL INSTALLERS/LATHERS (AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, SANTA CLARA COUNTIES).....\$ 52.65	31.26	
DRYWALL INSTALLERS/LATHERS (AREA 2: MONTEREY, SAN BENITO, SANTA CRUZ COUNTIES).....\$ 46.77	31.26	
DRYWALL INSTALLERS/LATHERS (AREA 3: SAN JOAQUIN)....\$ 47.27	31.26	
DRYWALL INSTALLERS/LATHERS (AREA 4: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, STANISLAUS, TUOLUMNE COUNTIES).....\$ 45.92	31.26	
DRYWALL STOCKER/SCRAPPER (AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, SANTA CLARA COUNTIES).....\$ 26.33	18.22	
DRYWALL STOCKER/SCRAPPER (AREA 2: MONTEREY, SAN BENITO, SANTA CRUZ COUNTIES).....\$ 23.39	18.22	
DRYWALL STOCKER/SCRAPPER (AREA 3: SAN JOAQUIN).....\$ 23.64	18.22	
DRYWALL STOCKER/SCRAPPER (AREA 4: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, STANISLAUS, TUOLUMNE COUNTIES).....\$ 22.97	18.22	

CARP0152-001 07/01/2020

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (CONTRA COSTA COUNTY).....\$ 52.65	30.82	
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (CONTRA COSTA COUNTY).....\$ 52.80	30.82	
CARPENTERS: JOURNEYMAN CARPENTER (CONTRA COSTA COUNTY).....\$ 52.65	30.82	
CARPENTERS: MILLWRIGHT (CONTRA COSTA COUNTY).....\$ 52.75	32.41	

CARP0152-002 07/01/2020

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (SAN JOAQUIN COUNTY).....\$ 52.65	30.82	

CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (SAN JOAQUIN COUNTY).....	\$ 46.92	30.82
CARPENTERS: JOURNEYMAN CARPENTER (SAN JOAQUIN COUNTY).....	\$ 46.77	30.82
CARPENTERS: MILLWRIGHT (SAN JOAQUIN COUNTY).....	\$ 49.27	32.41

CARP0152-004 07/01/2020

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (CALAVERAS, MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES).....	\$ 52.65	30.82
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER CALAVERAS, MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES.....	\$ 45.57	30.82
CARPENTERS: JOURNEYMAN CARPENTER (CALAVERAS, MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES).\$	45.42	30.82
CARPENTERS: MILLWRIGHT (CALAVERAS, MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES).....	\$ 47.92	32.41

CARP0217-001 07/01/2023

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (SAN MATEO COUNTY).....	\$ 60.39	33.52
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (SAN MATEO COUNTY).....	\$ 60.54	33.52
CARPENTERS: JOURNEYMAN CARPENTER (SAN MATEO COUNTY).\$	60.39	33.52
CARPENTERS: MILLWRIGHT (SAN MATEO COUNTY).....	\$ 60.49	35.11

CARP0405-001 07/01/2021

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (SANTA CLARA COUNTY).....	\$ 54.85	31.49
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (SANTA CLARA COUNTY).....	\$ 55.00	31.49
CARPENTERS: JOURNEYMAN CARPENTER (SANTA CLARA COUNTY).....	\$ 54.85	31.49
CARPENTERS: MILLWRIGHT (SANTA CLARA COUNTY).....	\$ 54.95	33.08

CARP0405-002 07/01/2021

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (SAN		

BENITO COUNTY).....	\$ 54.85	31.49
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (SAN BENITO COUNTY).....	\$ 49.12	31.49
CARPENTERS: JOURNEYMAN CARPENTER (SAN BENITO COUNTY).....	\$ 48.97	31.49
CARPENTERS: MILLWRIGHT (SAN BENITO COUNTY).....	\$ 51.47	33.08

CARP0505-001 07/01/2021

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (SANTA CRUZ COUNTY).....	\$ 54.85	31.49
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (SANTA CRUZ COUNTY).....	\$ 49.12	31.49
CARPENTERS: JOURNEYMAN CARPENTER (SANTA CRUZ COUNTY).....	\$ 48.97	31.49
CARPENTERS: MILLWRIGHT (SANTA CRUZ COUNTY).....	\$ 51.47	33.08

CARP0605-001 07/01/2021

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (MONTEREY COUNTY).....	\$ 54.85	31.49
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (MONTEREY COUNTY).....	\$ 49.12	31.49
CARPENTERS: JOURNEYMAN CARPENTER (MONTEREY COUNTY)..	\$ 48.97	31.49
CARPENTERS: MILLWRIGHT (MONTEREY COUNTY).....	\$ 51.47	33.08

CARP0701-001 07/01/2021

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (FRESNO AND MADERA COUNTIES).....	\$ 54.85	31.49
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING ERECTOR, SAW FILER (FRESNO AND MADERA COUNTIES)...	\$ 47.77	31.49
CARPENTERS: JOURNEYMAN CARPENTER (FRESNO AND MADERA COUNTIES).....	\$ 47.62	31.49
CARPENTERS: MILLWRIGHT (FRESNO AND MADERA COUNTIES).\$	50.12	33.08

CARP0713-001 07/01/2021

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (ALAMEDA COUNTY).....	\$ 54.85	31.49
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER		

SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING		
ERECTOR, SAW FILER (ALAMEDA COUNTY).....	\$ 55.00	31.49
CARPENTERS: JOURNEYMAN CARPENTER (ALAMEDA COUNTY)...	\$ 54.85	31.49
CARPENTERS: MILLWRIGHT (ALAMEDA COUNTY).....	\$ 54.95	33.08

CARP1109-001 07/01/2021

	Rates	Fringes
CARPENTERS: BRIDGE BUILDER/HIGHWAY CARPENTER (KINGS COUNTY).....	\$ 54.85	31.49
CARPENTERS: HARDWOOD FLOORLAYER, SHINGLER, POWER SAW OPERATOR, STEEL SCAFFOLD & STEEL SHORING		
ERECTOR, SAW FILER KINGS COUNTY.....	\$ 47.77	31.49
CARPENTERS: JOURNEYMAN CARPENTER (KINGS COUNTY).....	\$ 47.62	31.49
CARPENTERS: MILLWRIGHT (KINGS COUNTY).....	\$ 50.12	33.08

ELEC0006-004 12/01/2025

	Rates	Fringes
SOUND & COMMUNICATIONS: INSTALLER. (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (SAN FRANCISCO COUNTY).....	\$ 58.83	31.51
SOUND & COMMUNICATIONS: TECHNICIAN (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF		

CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING
FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS
(INCLUDING WIRE AND CABLE PULLING) AND WHEN
PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS
OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM
SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING
INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK,
INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS
HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE
LOWEST FLOOR LEVEL HAVING BUILDING ACCESS);
EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE:
FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS
(INCLUDING WIRE AND CABLE PULLING), ON PROJECTS
WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING
CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE
ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE
PERFORMED BY THE INSIDE ELECTRICIAN.) (SAN
FRANCISCO COUNTY) (SAN FRANCISCO COUNTY)\$ 67.65 31.78

ELEC0006-007 06/01/2024
Rates Fringes
ELECTRICIAN (SAN FRANCISCO COUNTY).....\$ 91.25 48.05

ELEC0100-002 09/01/2025
Rates Fringes
ELECTRICIAN (FRESNO, KINGS, AND MADERA COUNTIES)....\$ 50.00 30.15

ELEC0100-005 12/01/2024
Rates Fringes
COMMUNICATIONS SYSTEM: INSTALLER (SCOPE OF WORK:
INCLUDES THE INSTALLATION TESTING, SERVICE AND
MAINTENANCE, OF THE FOLLOWING SYSTEMS WHICH UTILIZE
THE TRANSMISSION AND/OR TRANSFERENCE OF VOICE,
SOUND, VISION AND DIGITAL FOR COMMERCIAL,
EDUCATION, SECURITY AND ENTERTAINMENT PURPOSES FOR
THE FOLLOWING: TV MONITORING AND SURVEILLANCE,
BACKGROUND-FOREGROUND MUSIC, INTERCOM AND TELEPHONE
INTERCONNECT, INVENTORY CONTROL SYSTEMS, MICROWAVE
TRANSMISSION, MULTI-MEDIA, MULTIPLEX, NURSE CALL
SYSTEM, RADIO PAGE, SCHOOL INTERCOM AND SOUND,
BURGLAR ALARMS, AND LOW VOLTAGE MASTER CLOCK
SYSTEMS. A. SOUND AND VOICE
TRANSMISSION/TRANSFERENCE SYSTEMS BACKGROUND
FOREGROUND MUSIC, INTERCOM AND TELEPHONE
INTERCONNECT SYSTEMS, TELEPHONE SYSTEMS NURSE CALL
SYSTEMS, RADIO PAGE SYSTEMS, SCHOOL INTERCOM AND

SOUND SYSTEMS, BURGLAR ALARM SYSTEMS, LOW VOLTAGE, MASTER CLOCK SYSTEMS, MULTI-MEDIA/MULTIPLEX SYSTEMS, SOUND AND MUSICAL ENTERTAINMENT SYSTEMS, RF SYSTEMS, ANTENNAS AND WAVE GUIDE. B. FIRE ALARM SYSTEMS INSTALLATION, WIRE PULLING AND TESTING. C. TELEVISION AND VIDEO SYSTEMS TELEVISION MONITORING AND SURVEILLANCE SYSTEMS VIDEO SECURITY SYSTEMS, VIDEO ENTERTAINMENT SYSTEMS, VIDEO EDUCATIONAL SYSTEMS, MICROWAVE TRANSMISSION SYSTEMS, CATV AND CCTV. D. SECURITY SYSTEMS PERIMETER SECURITY SYSTEMS VIBRATION SENSOR SYSTEMS CARD ACCESS SYSTEMS ACCESS CONTROL SYSTEMS, SONAR/INFRARED MONITORING EQUIPMENT. E. COMMUNICATIONS SYSTEMS THAT TRANSMIT OR RECEIVE INFORMATION AND/OR CONTROL SYSTEMS THAT ARE INTRINSIC TO THE ABOVE LISTED SYSTEMS SCADA (SUPERVISORY CONTROL AND DATA ACQUISITION) PCM (PULSE CODE MODULATION) INVENTORY CONTROL SYSTEMS, DIGITAL DATA SYSTEMS BROADBAND AND BASEBAND AND CARRIERS POINT OF SALE SYSTEMS, VSAT DATA SYSTEMS DATA COMMUNICATION SYSTEMS RF AND REMOTE CONTROL SYSTEMS, FIBER OPTIC DATA SYSTEMS. WORK EXCLUDED RACEWAY SYSTEMS ARE NOT COVERED (EXCLUDING LADDER-RACK FOR THE PURPOSE OF THE ABOVE LISTED SYSTEMS). CHASES AND/OR NIPPLES (NOT TO EXCEED 10 FEET) MAY BE INSTALLED ON OPEN WIRING SYSTEMS. ENERGY MANAGEMENT SYSTEMS. SCADA (SUPERVISORY CONTROL AND DATA ACQUISITION) WHEN NOT INTRINSIC TO THE ABOVE LISTED SYSTEMS (IN THE SCOPE). FIRE ALARM SYSTEMS WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) SHALL BE PERFORMED AT THE ELECTRICIAN WAGE RATE, WHEN EITHER OF THE FOLLOWING TWO (2) CONDITIONS APPLY: 1. THE PROJECT INVOLVES NEW OR MAJOR REMODEL BUILDING TRADES CONSTRUCTION. 2. THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT.) (FRESNO, KINGS, MADERA)\$ 45.28 28.01

COMMUNICATIONS SYSTEM: TECHNICIAN (SCOPE OF WORK: INCLUDES THE INSTALLATION TESTING, SERVICE AND MAINTENANCE, OF THE FOLLOWING SYSTEMS WHICH UTILIZE THE TRANSMISSION AND/OR TRANSFERENCE OF VOICE, SOUND, VISION AND DIGITAL FOR COMMERCIAL, EDUCATION, SECURITY AND ENTERTAINMENT PURPOSES FOR THE FOLLOWING: TV MONITORING AND SURVEILLANCE, BACKGROUND-FOREGROUND MUSIC, INTERCOM AND TELEPHONE INTERCONNECT, INVENTORY CONTROL SYSTEMS, MICROWAVE TRANSMISSION, MULTI-MEDIA, MULTIPLEX, NURSE CALL SYSTEM, RADIO PAGE, SCHOOL INTERCOM AND SOUND, BURGLAR ALARMS, AND LOW VOLTAGE MASTER CLOCK SYSTEMS. A. SOUND AND VOICE

TRANSMISSION/TRANSFERENCE SYSTEMS BACKGROUND
FOREGROUND MUSIC, INTERCOM AND TELEPHONE
INTERCONNECT SYSTEMS, TELEPHONE SYSTEMS NURSE CALL
SYSTEMS, RADIO PAGE SYSTEMS, SCHOOL INTERCOM AND
SOUND SYSTEMS, BURGLAR ALARM SYSTEMS, LOW VOLTAGE,
MASTER CLOCK SYSTEMS, MULTI-MEDIA/MULTIPLEX
SYSTEMS, SOUND AND MUSICAL ENTERTAINMENT SYSTEMS,
RF SYSTEMS, ANTENNAS AND WAVE GUIDE. B. FIRE ALARM
SYSTEMS INSTALLATION, WIRE PULLING AND TESTING. C.
TELEVISION AND VIDEO SYSTEMS TELEVISION MONITORING
AND SURVEILLANCE SYSTEMS VIDEO SECURITY SYSTEMS,
VIDEO ENTERTAINMENT SYSTEMS, VIDEO EDUCATIONAL
SYSTEMS, MICROWAVE TRANSMISSION SYSTEMS, CATV AND
CCTV. D. SECURITY SYSTEMS PERIMETER SECURITY
SYSTEMS VIBRATION SENSOR SYSTEMS CARD ACCESS
SYSTEMS ACCESS CONTROL SYSTEMS, SONAR/INFRARED
MONITORING EQUIPMENT. E. COMMUNICATIONS SYSTEMS
THAT TRANSMIT OR RECEIVE INFORMATION AND/OR CONTROL
SYSTEMS THAT ARE INTRINSIC TO THE ABOVE LISTED
SYSTEMS SCADA (SUPERVISORY CONTROL AND DATA
ACQUISITION) PCM (PULSE CODE MODULATION) INVENTORY
CONTROL SYSTEMS, DIGITAL DATA SYSTEMS BROADBAND
AND BASEBAND AND CARRIERS POINT OF SALE SYSTEMS,
VSAT DATA SYSTEMS DATA COMMUNICATION SYSTEMS RF
AND REMOTE CONTROL SYSTEMS, FIBER OPTIC DATA
SYSTEMS. WORK EXCLUDED RACEWAY SYSTEMS ARE NOT
COVERED (EXCLUDING LADDER-RACK FOR THE PURPOSE OF
THE ABOVE LISTED SYSTEMS). CHASES AND/OR NIPPLES
(NOT TO EXCEED 10 FEET) MAY BE INSTALLED ON OPEN
WIRING SYSTEMS. ENERGY MANAGEMENT SYSTEMS. SCADA
(SUPERVISORY CONTROL AND DATA ACQUISITION) WHEN NOT
INTRINSIC TO THE ABOVE LISTED SYSTEMS (IN THE
SCOPE). FIRE ALARM SYSTEMS WHEN INSTALLED IN
RACEWAYS (INCLUDING WIRE AND CABLE PULLING) SHALL
BE PERFORMED AT THE ELECTRICIAN WAGE RATE, WHEN
EITHER OF THE FOLLOWING TWO (2) CONDITIONS APPLY:
1. THE PROJECT INVOLVES NEW OR MAJOR REMODEL
BUILDING TRADES CONSTRUCTION. 2. THE CONDUCTORS
FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN
CONDUIT.) (FRESNO, KINGS, MADERA)\$ 52.07

28.21

ELEC0234-001 12/30/2025

ELECTRICIAN ZONE A : ALL OF SANTA CRUZ, MONTEREY,
AND SAN BENITO COUNTIES WITHIN 25 AIR MILES OF
HIGHWAY 1 AND DOLAN ROAD IN MOSS LANDING, AND AN
AREA EXTENDING 5 MILES EAST AND WEST OF HIGHWAY 101
SOUTH TO THE SAN LUIS OBISPO COUNTY LINE (MONTEREY,

Rates

Fringes

SAN BENITO AND SANTA CRUZ COUNTIES).....\$ 70.41	33.76
ELECTRICIAN ZONE B: ANY AREA OUTSIDE OF ZONE A	
(MONTEREY, SAN BENITO AND SANTA CRUZ COUNTIES).....\$ 77.45	33.97

ELEC0234-003 12/01/2021

	Rates	Fringes
SOUND & COMMUNICATIONS: INSTALLER (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES)\$ 47.93		24.09
SOUND & COMMUNICATIONS: TECHNICIAN (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN		

RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON
PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL
BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR
THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT,
SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.)
(MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES)\$ 55.12 24.30

ELEC0302-001 03/01/2025

	Rates	Fringes
CABLE SPLICER (CONTRA COSTA COUNTY).....	\$ 74.54	36.09
ELECTRICIAN (CONTRA COSTA COUNTY).....	\$ 66.26	35.84

ELEC0302-003 12/01/2025

	Rates	Fringes
SOUND & COMMUNICATIONS: INSTALLER (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (CONTRA COSTA COUNTY)	\$ 53.08	30.84
SOUND & COMMUNICATIONS: TECHNICIAN (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN		

PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS
OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM
SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING
INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK,
INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS
HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE
LOWEST FLOOR LEVEL HAVING BUILDING ACCESS);
EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE:
FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS
(INCLUDING WIRE AND CABLE PULLING), ON PROJECTS
WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING
CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE
ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE
PERFORMED BY THE INSIDE ELECTRICIAN.) (CONTRA
COSTA COUNTY)\$ 61.04 31.08

ELEC0332-001 06/01/2025 Rates Fringes

CABLE SPLICER (FOOTNOTES: WORK UNDER COMPRESSED
AIR OR WHERE GAS MASKS ARE REQUIRED, ORWORK ON
LADDERS, SCAFFOLDS, STACKS, ""BOSUN'S CHAIRS,"" OR
OTHER STRUCTURES AND WHERE THE WORKERS ARE NOT
PROTECTED BY PERMANENT GUARD RAILS AT A DISTANCE OF
40 TO 60 FT. FROM THE GROUND OR SUPPORTING
STRUCTURES: TO BE PAID ONE AND ONE-HALF TIMES THE
STRAIGHT-TIME RATE OF PAY. WORK ON STRUCTURES OF
60 FT. OR OVER (AS DESCRIBED ABOVE): TO BE PAID
TWICE THE STRAIGHT-TIME RATE OF PAY.) (SANTA CLARA
COUNTY).....\$ 104.68 49.46

ELECTRICIAN (FOOTNOTES: WORK UNDER COMPRESSED AIR
OR WHERE GAS MASKS ARE REQUIRED, ORWORK ON LADDERS,
SCAFFOLDS, STACKS, ""BOSUN'S CHAIRS,"" OR OTHER
STRUCTURES AND WHERE THE WORKERS ARE NOT PROTECTED
BY PERMANENT GUARD RAILS AT A DISTANCE OF 40 TO 60
FT. FROM THE GROUND OR SUPPORTING STRUCTURES: TO BE
PAID ONE AND ONE-HALF TIMES THE STRAIGHT-TIME RATE
OF PAY. WORK ON STRUCTURES OF 60 FT. OR OVER (AS
DESCRIBED ABOVE): TO BE PAID TWICE THE
STRAIGHT-TIME RATE OF PAY.) (SANTA CLARA COUNTY)...\$ 91.03 49.05

ELEC0332-003 12/01/2025 Rates Fringes

SOUND & COMMUNICATIONS: INSTALLER (SCOPE OF WORK:
INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO
TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL
OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH
INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION

OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (SANTA CLARA COUNTY).....	\$ 58.33	31.00
SOUND & COMMUNICATIONS: TECHNICIAN (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (SANTA CLARA COUNTY).....	\$ 67.08	31.26

ELEC0595-001 06/01/2025

	Rates	Fringes
CABLE SPLICER (ALAMEDA COUNTY).....	\$ 87.40	49.41
ELECTRICIAN (ALAMEDA COUNTY).....	\$ 76.00	49.07

ELEC0595-002 06/01/2024

	Rates	Fringes
CABLE SPLICER (CALAVERAS AND SAN JOAQUIN COUNTIES).. ELECTRICIAN: ALL OTHER WORK (CALAVERAS AND SAN JOAQUIN COUNTIES).....	\$ 59.34 \$ 49.45	32.26 31.96
ELECTRICIAN: TUNNEL WORK (CALAVERAS AND SAN JOAQUIN COUNTIES).....	\$ 51.92	32.04

ELEC0595-006 12/01/2025

	Rates	Fringes
SOUND & COMMUNICATIONS: INSTALLER (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (ALAMEDA COUNTY).....	\$ 58.33	31.00
SOUND & COMMUNICATIONS: TECHNICIAN (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING		

INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK,
INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS
HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE
LOWEST FLOOR LEVEL HAVING BUILDING ACCESS);
EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE:
FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS
(INCLUDING WIRE AND CABLE PULLING), ON PROJECTS
WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING
CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE
ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE
PERFORMED BY THE INSIDE ELECTRICIAN.) (ALAMEDA
COUNTY).....\$ 67.08 31.26

ELEC0595-008 12/01/2024

	Rates	Fringes
COMMUNICATIONS SYSTEM: INSTALLER (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (CALAVERAS AND SAN JOAQUIN COUNTIES)\$ 45.28		28.01
COMMUNICATIONS SYSTEM: TECHNICIAN (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN		

PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS
OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM
SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING
INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK,
INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS
HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE
LOWEST FLOOR LEVEL HAVING BUILDING ACCESS);
EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE:
FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS
(INCLUDING WIRE AND CABLE PULLING), ON PROJECTS
WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING
CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE
ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE
PERFORMED BY THE INSIDE ELECTRICIAN.) (CALAVERAS
AND SAN JOAQUIN COUNTIES)\$ 52.07 28.21

ELEC0617-001 06/01/2025 Rates Fringes
ELECTRICIAN (SAN MATEO COUNTY).....\$ 86.00 51.07

ELEC0617-003 12/01/2025 Rates Fringes
SOUND & COMMUNICATIONS: INSTALLER (SCOPE OF WORK:
INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO
TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL
OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH
INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION
OR EXCLUSION OF TERMINATIONS AND TESTINGS OF
CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING
FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS
(INCLUDING WIRE AND CABLE PULLING) AND WHEN
PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS
OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM
SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING
INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK,
INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS
HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE
LOWEST FLOOR LEVEL HAVING BUILDING ACCESS);
EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE:
FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS
(INCLUDING WIRE AND CABLE PULLING), ON PROJECTS
WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING
CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE
ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE
PERFORMED BY THE INSIDE ELECTRICIAN.) (SAN MATEO
COUNTY).....\$ 58.33 31.00
SOUND & COMMUNICATIONS: TECHNICIAN (SCOPE OF WORK:

INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (SAN MATEO COUNTY).....	\$ 67.08	31.26
---	----------	-------

ELEC0684-001 12/01/2024		
	Rates	Fringes
ELECTRICIAN (MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES) CABLE SPLICER = 110% OF JOURNEYMAN ELECTRICIAN.....	\$ 48.50	30.09

ELEC0684-004 12/01/2024		
	Rates	Fringes
COMMUNICATIONS SYSTEM: INSTALLER (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75'		

ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES).....\$ 45.28	28.01
COMMUNICATIONS SYSTEM: TECHNICIAN (SCOPE OF WORK: INCLUDING ANY DATA SYSTEM WHOSE ONLY FUNCTION IS TO TRANSMIT OR RECEIVE INFORMATION; EXCLUDING ALL OTHER DATA SYSTEMS OR MULTIPLE SYSTEMS WHICH INCLUDE CONTROL FUNCTION OR POWER SUPPLY; INCLUSION OR EXCLUSION OF TERMINATIONS AND TESTINGS OF CONDUCTORS DETERMINED BY THEIR FUNCTION; EXCLUDING FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING) AND WHEN PERFORMED ON NEW OR MAJOR REMODEL BUILDING PROJECTS OR JOBS FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN CONDUIT; EXCLUDING INSTALLATION OF RACEWAY SYSTEMS, LINE VOLTAGE WORK, INDUSTRIAL WORK, LIFE-SAFETY SYSTEMS (ALL BUILDINGS HAVING FLOORS LOCATED MORE THAN 75' ABOVE THE LOWEST FLOOR LEVEL HAVING BUILDING ACCESS); EXCLUDING ENERGY MANAGEMENT SYSTEMS.) (FOOTNOTE: FIRE ALARM WORK WHEN INSTALLED IN RACEWAYS (INCLUDING WIRE AND CABLE PULLING), ON PROJECTS WHICH INVOLVE NEW OR MAJOR REMODEL BUILDING CONSTRUCTION, FOR WHICH THE CONDUCTORS FOR THE FIRE ALARM SYSTEM ARE INSTALLED IN THE CONDUIT, SHALL BE PERFORMED BY THE INSIDE ELECTRICIAN.) (MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES).....\$ 52.07	28.21

ELEC1245-001 01/01/2025

Rates

Fringes

LINE CONSTRUCTION: (1) LINEMAN; CABLE SPLICER (HOLIDAYS: NEW YEAR'S DAY, M.L. KING DAY, MEMORIAL DAY, INDEPENDENCE DAY, LABOR DAY, VETERANS DAY, THANKSGIVING DAY AND DAY AFTER THANKSGIVING, CHRISTMAS DAY).....\$ 70.16	24.71
LINE CONSTRUCTION: (2) EQUIPMENT SPECIALIST (OPERATES CRAWLER TRACTORS, COMMERCIAL MOTOR VEHICLES, BACKHOES, TRENCHERS, CRANES (50 TONS AND BELOW), OVERHEAD & UNDERGROUND DISTRIBUTION LINE EQUIPMENT) (HOLIDAYS: NEW YEAR'S DAY, M.L. KING	

DAY, MEMORIAL DAY, INDEPENDENCE DAY, LABOR DAY, VETERANS DAY, THANKSGIVING DAY AND DAY AFTER THANKSGIVING, CHRISTMAS DAY).....	\$ 53.30	22.26
LINE CONSTRUCTION: (3) GROUNDMAN (HOLIDAYS: NEW YEAR'S DAY, M.L. KING DAY, MEMORIAL DAY, INDEPENDENCE DAY, LABOR DAY, VETERANS DAY, THANKSGIVING DAY AND DAY AFTER THANKSGIVING, CHRISTMAS DAY).....		
	\$ 40.76	21.76

ELEV0008-001 01/01/2025

Rates

Fringes

ELEVATOR MECHANIC (FOOTNOTE: ADD TO FRINGE BENEFITS A+B: A. PAID VACATION: EMPLOYER CONTRIBUTES 8% OF REGULAR HOURLY RATE AS VACATION PAY CREDIT FOR EMPLOYEES WITH MORE THAN 5 YEARS OF SERVICE, AND 6% FOR 6 MONTHS TO 5 YEARS OF SERVICE. B. PAID HOLIDAYS: NEW YEAR'S DAY, MEMORIAL DAY, INDEPENDENCE DAY, LABOR DAY, VETERANS' DAY, THANKSGIVING DAY, FRIDAY AFTER THANKSGIVING, AND CHRISTMAS DAY.).....	\$ 84.05	38.44
--	----------	-------

ENGI0003-001 06/29/2020

Rates

Fringes

OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 1 (LIFTING DEVICES)- DERRICK BARGE PEDESTAL MOUNTED OVER 100 TONS; CLAMSHELL OVER 7 CU. YDS.; SELF-PROPELLED BOOM-TYHPE LIFTING DEVICE OVER 100 TONS; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED OVER 100 TONS.....	\$ 52.64	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 1 (OILER)- DERRICK BARGE PEDESTAL MOUNTED OVER 100 TONS; CLAMSHELL OVER 7 CU. YDS.; SELF-PROPELLED BOOM-TYHPE LIFTING DEVICE OVER 100 TONS; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED OVER 100 TONS.....	\$ 43.38	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 1 (TRUCK CRANE OILER)- DERRICK BARGE PEDESTAL MOUNTED OVER 100 TONS; CLAMSHELL OVER 7 CU. YDS.; SELF-PROPELLED BOOM-TYHPE LIFTING DEVICE OVER 100 TONS; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED OVER 100 TONS.....	\$ 45.66	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 2 (LIFTING DEVICES)- DERRICK BARGE PEDESTAL MOUNTED 45 TONS TO AND INCLUDING 100 TONS; CLAMSHELL UP TO AND INCLUDING 7 CU. YDS.; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE OVER 45 TONS; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED, OVER 45 TONS UP TO		

AND INCLUDING 100 TONS; FUNDEX F-12 HYDRAULIC PILE RIG.....	\$ 50.82	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 2 (OILER)- DERRICK BARGE PEDESTAL MOUNTED 45 TONS TO AND INCLUDING 100 TONS; CLAMSHELL UP TO AND INCLUDING 7 CU. YDS.; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE OVER 45 TONS; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED, OVER 45 TONS UP TO AND INCLUDING 100 TONS; FUNDEX F-12 HYDRAULIC PILE RIG.....		
	\$ 43.11	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 2 (TRUCK CRANE OILER)- DERRICK BARGE PEDESTAL MOUNTED 45 TONS TO AND INCLUDING 100 TONS; CLAMSHELL UP TO AND INCLUDING 7 CU. YDS.; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE OVER 45 TONS; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED, OVER 45 TONS UP TO AND INCLUDING 100 TONS; FUNDEX F-12 HYDRAULIC PILE RIG.....		
	\$ 45.41	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 3 (LIFTING DEVICES)- DERRICK BARGE PEDESTAL MOUNTED UNDER 45 TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE 45 TONS AND UNDER; SKID/SCOW PILEDRIVER, ANY TONNAGE; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED 45 TONS AND UNDER.....		
	\$ 49.14	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 3 (OILER)- DERRICK BARGE PEDESTAL MOUNTED UNDER 45 TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE 45 TONS AND UNDER; SKID/SCOW PILEDRIVER, ANY TONNAGE; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED 45 TONS AND UNDER.....		
	\$ 42.89	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 3 (TRUCK CRANE OILER)- DERRICK BARGE PEDESTAL MOUNTED UNDER 45 TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE 45 TONS AND UNDER; SKID/SCOW PILEDRIVER, ANY TONNAGE; TRUCK CRANE OR CRAWLER, LAND OR BARGE MOUNTED 45 TONS AND UNDER.....		
	\$ 45.12	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 4 (LIFTING DEVICES)- ASSISTANT OPERATOR IN LIEU OF ASSISTANT TO ENGINEER; FORKLIFT, 10 TONS AND OVER; HEAVY-DUTY REPAIR PERSON/WELDER.....		
	\$ 47.37	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 5 (LIFTING DEVICES)- DECK ENGINEER.....		
	\$ 44.73	31.15
OPERATOR: POWER EQUIPMENT, PILEDIVING: GROUP 6 (LIFTING DEVICES)- DECKHAND; FIRE TENDER.....		
	\$ 42.50	31.15

ENGI0003-001 06/30/2025

Rates

Fringes

OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS

- AREA 1: GROUP 1 (CRANES)- CLAMSHELL AND DRAGLINE OVER 7 CU. YDS.; CRANE, OVER 100 TONS; DERRICK, OVER 100 TONS; DERRICK BARGE PEDESTAL-MOUNTED, OVER 100 TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, OVER 100 TONS. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 68.59 OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 1 (OILER)- CLAMSHELL AND DRAGLINE OVER 7 CU. YDS.; CRANE, OVER 100 TONS; DERRICK, OVER 100 TONS; DERRICK BARGE PEDESTAL-MOUNTED, OVER 100 TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, OVER 100 TONS. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 43.79 OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 1 (TRUCK CRANE OILER)- CLAMSHELL AND DRAGLINE OVER 7 CU. YDS.; CRANE, OVER 100 TONS; DERRICK, OVER 100 TONS; DERRICK BARGE PEDESTAL-MOUNTED, OVER 100 TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, OVER 100 TONS. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE	32.53 31.15
---	---------------------------

(EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....	\$ 46.08	31.15
OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 2 (CRANES)- CLAMSHELL AND DRAGLINE OVER 1 CU. YD. UP TO AND INCLUDING 7 CU. YDS.; CRANE, OVER 45 TONS UP TO AND INCLUDING 100 TONS; DERRICK BARGE, 100 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, OVER 45 TONS; TOWER CRANE. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....		
	\$ 66.08	32.53
OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 2 (OILER)- CLAMSHELL AND DRAGLINE OVER 1 CU. YD. UP TO AND INCLUDING 7 CU. YDS.; CRANE, OVER 45 TONS UP TO AND INCLUDING 100 TONS; DERRICK BARGE, 100 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, OVER 45 TONS; TOWER CRANE. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....		
	\$ 42.83	31.15
OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 2 (TRUCK CRANE OILER)- CLAMSHELL AND DRAGLINE OVER 1 CU. YD. UP TO AND INCLUDING 7 CU. YDS.; CRANE, OVER 45 TONS UP TO AND INCLUDING 100 TONS; DERRICK BARGE, 100 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, OVER 45		

TONS; TOWER CRANE. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 45.07 OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 3 (CRANES) CLAMSHELL AND DRAGLINE UP TO AND INCLUDING 1 CU. YD.; CRANES 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE 45 TONS AND UNDER. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 64.34 OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 3 (HYDRAULIC) CLAMSHELL AND DRAGLINE UP TO AND INCLUDING 1 CU. YD.; CRANES 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE 45 TONS AND UNDER. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 59.98 OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS	31.15 32.53 32.53
---	--

- AREA 1: GROUP 3 (OILER) CLAMSHELL AND DRAGLINE UP TO AND INCLUDING 1 CU. YD.; CRANES 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE 45 TONS AND UNDER. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 42.55 OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 3 (TRUCK CRANE OILER) CLAMSHELL AND DRAGLINE UP TO AND INCLUDING 1 CU. YD.; CRANES 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE 45 TONS AND UNDER. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 44.83 OPERATOR: POWER EQUIPMENT- CRANES AND ATTACHMENTS - AREA 1: GROUP 4 (CRANES)- BOOM TRUCK OR DUAL PURPOSE A-FRAME TRUCK, NON-ROTATING OVER 15 TONS; TRUCK-MOUNTED ROTATING TELESCOPIC BOOM TYPE LIFTING DEVICE, MANITEX OR SIMILAR (BOOM TRUCK) OVER 15 TONS. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO	31.15 31.15
--	---------------------------

(EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 61.30	32.53
OPERATOR: POWER EQUIPMENT, AREA 1: GROUP 2- HIGHLINE CABLEWAY; HYDRAULIC EXCAVATOR, 3.5 CU. YDS. UP TO 7 CU. YDS.; LICENSED CONSTRUCTION WORK BOAT OPERATOR, ON SITE; POWER BLADE OPERATOR (FINISH); POWER SHOVELS, OVER 1 CU. YD. UP TO AN DINCLUDING 7 CU. YDS. M.R.C. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 65.43	
32.53	
OPERATOR: POWER EQUIPMENT, AREA 1: GROUP 3- ASPHALT MILLING MACHINE; CABLE BACKHOE; COMBINATION BACKHOE AND LOADER OVER 3/4 CU. YDS.; CONTINUOUS FLIGHT TIE BACK MACHINE ASSISTNAT TO ENGINEER OR MECHANIC; CRANE MOUNTED CONTINUOUS FLIGHT TIE BACK MACHINE, TONNAGE TO APPLY; CRANE MOUNTED DRILL ATTACHMENT, TONNAGE TO APPLY; DOZER, SLOPE BRD; GRADALL; HYDRAULIC EXCAVATOR, UP TO 3.5 CU. YDS.; LOADER 4 CU. YDS. AND OVER; LONG REACH EXCAVATOR; MULTIPLE ENGINE SCRAPER (WHEN USED AS PUSH PULL); POWER SHOVELS, UP TO AND INCLUDING 1 CU. YD.; PRE-STRESS WIRE WRAPPING MACHINE; SIDE BOOM CAT, 572 OR LARGER; TRACK LOADER 4 CU. YDS. AND OVER; WHEEL EXCAVATOR (UP TO AND INCLUDING 750 CU. YDS. PER HOUR) (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 63.95	
32.53	

OPERATOR: POWER EQUIPMENT, AREA 1: GROUP 4-
 ASPHALT PLANT ENGINEER/BOX PERSON; CHICAGO BOOM;
 COMBINATION BACKHOE AND LOADER UP TO AND INCLUDING
 .75 CU. YD.; CONCRETE BATCH PLANT (WET OR DRY);
 DOZER AND/OR PUSH CAT; PULL-TYPE ELEVATING LOADER;
 GRADESETTER, GRADE CHECKER (GPS, MECHANICAL OR
 OTHERWISE); GROOVING AND GRINDING MACHINE; HEADING
 SHIELD OPERATOR; HEAVY-DUTY DRILLING EQUIPMENT,
 HUGHS, LDH, WATSON 3000 OR SIMILAR; HEAVY-DUTY
 REPAIRPERSON AND/OR WELDER; LIME SPREADER; LOADER
 UNDER 4 CU. YDS.; LUBRICATION AND SERVICE ENGINEER
 (MOBILE AND GREASE RACK); MECHANICAL FINISHERS OR
 SPREADER MACHINE (ASPHALT, BARBER-GREENE AND
 SIMILAR); MILLER FORMLESS M-9000 SLOPE PAVER OR
 SIMILAR; PORTABLE CRUSHING AND SCREENING PLANTS;
 POWER BLADE SUPPORT; ROLLER OPERATOR, ASPHALT;
 RUBBER-TIRED SCRAPER, SELF-LOADING (PADDLE-WHEELS,
 ETC.); RUBBER-TIRED EARTHMOVING EQUIPMENT
 (SCRAPERS); SLIP FORM PAVER (CONCRETE); SMALL
 TRACTOR WITH DRAG; SOIL STABILIZER (P&H OR EQUAL);
 SPIDER PLOW AND SPIDER PULLER; TUBEX PILE RIG;
 UNLICENSED CONSTRUCTION WORK BOAT OPERATOR, ON
 SITE; TIMBER SKIDDER; TRACK LOADER UP TO 4 YDS.;
 TRACTOR-DRAWN SCRAPER; TRACTOR, COMPRESSOR DRILL
 COMBINATION; WELDER; WOODS-MIXER (AND OTHER SIMILAR
 PUGMILL EQUIPMENT. (AREA 1: LISTED WAGE RATES. AREA
 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA
 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT
 EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN
 PART), KINGS, MADERA (EXCEPT EASTERN PART),
 MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY
 (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN
 FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA,
 SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN
 PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART),
 FRESNO (EASTERN PART), MADERA (EASTERN PART),
 MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN
 PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 62.57

32.53

OPERATOR: POWER EQUIPMENT, AREA 1: GROUP 5-
 CAST-IN-PLACE PIPE LAYING MACHINE; COMBINATION
 SLUSHER AND MOTOR OPERATOR; CONCRETE CONVEYOR OR
 CONCRETE PUMP, TRUCK OR EQUIPMENT MOUNTED; CONCRETE
 CONVEYOR, BUILDING SITE; CONCRETE PUMP OR PUMPCRETE
 GUN; DRILLING EQUIPMENT, WATSON 2000, TEXOMA 700 OR
 SIMILAR; DRILLING AND BORING MACHINERY, HORIZONTAL
 (NOT TO APPLY TO WATERLINES, WAGON DRILLS, OR
 JACKHAMMERS); CONCRETE MIXER/ALL; PERSON AND/OR
 MATERIAL HOIST; MECHANICAL FINISHERS (CONCRETE
 (CLARY, JOHNSON, BIDWELL BRIDGE DECK, OR SIMILAR

TYPES); MECHANICAL BURM, CURB, AND/OR CURB AND
 GUTTER MACHINE, CONCRETE OR ASPHALT); MINE OR SHAFT
 HOIST; PORTABLE CRUSHER; POWER JUMBO OPERATOR
 (SETTING SLIP-FORMS, ETC., IN TUNNELS); SCREED
 (AUTOMATIC OR MANUAL); SELF-PROPELLED COMPACTOR
 WITH DOZER; TRACTOR WITH BOOM D6 OR SMALLER;
 TRENCHING MACHINE, MAXIMUM DIGGING CAPACITY OVER 5
 FT. DEPTH; VERMEER T-600B ROCK CUTTER OR SIMILAR.
 (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN
 ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.)
 (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART),
 CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS,
 MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT
 EASTERN PART), MERCED, MONTEREY (EXCEPT
 SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN
 JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ,
 STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART)
 COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO
 (EASTERN PART), MADERA (EASTERN PART), MARIPOSA
 (EASTERN PART), MONTEREY (SOUTHWESTERN PART),
 TUOLUMNE (EASTERN PART) COUNTIES).....\$ 61.30

32.53

OPERATOR: POWER EQUIPMENT, AREA 1: GROUP 6-
 ARMOR-COATER (OR SIMILAR); BALLAST JACK TAMPER;
 BOOM-TYPE BACKFILLING MACHINE; ASSISTANT PLANT
 ENGINEER; BRIDGE AND/OR GANTRY CRANE; CHEMICAL
 GROUTING MACHINE, TRUCK-MOUNTED; CHIP SPREADING
 MACHINE OPERATOR; CONCRETE SAW (SELF-PROPELLED UNIT
 ON STREETS, HIGHWAYS, AIRPORTS, AND CANALS); DECK
 ENGINEER; DRILLING EQUIPMENT TEXOMA 600, HUGHS 200
 SERIES OR SIMILAR UP TO AND INCLUDING 30 FT.
 M.R.C.; DRILL DOCTOR; HELICOPTER RADIO OPERATOR;
 HYDRO-HAMMER OR SIMILAR; LINE MASTER; SKIDSTEER
 LOADER, BOBCAT LARGER THAN 743 SERIES OR SIMILAR
 (WITH ATTACHMENTS); LOCOMOTIVE; LULL HI-LIFT OR
 SIMILAR; OILER, TRUCK MOUNTED; PAVEMENT BREAKER,
 TRUCK-MOUNTED, WITH COMPRESSOR COMBINATION; PAVING
 FABRIC INSTALLATION AND/OR LAYING MACHINE; PIPE
 BENDING MACHINE (PIPELINES ONLY); PIPE WRAPPING
 MACHINE (TRACTOR PROPELLED AND SUPPORTED); SCREED
 (EXCEPT ASPHALTIC CONCRETE PAVING); SELF-PROPELLED
 PIPELINE WRAPPING MACHINE; TRACTOR; SELF-LOADING
 CHIPPER; CONCRETE BARRIER MOVING MACHINE. (AREA 1:
 LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL
 \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1:
 ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA
 COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA
 (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN
 PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART),
 SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO,

SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE
(EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS
(EASTERN PART), FRESNO (EASTERN PART), MADERA
(EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY
(SOUTHWESTERN PART), TUOLUMNE (EASTERN PART)
COUNTIES).....\$ 59.98

32.53

OPERATOR; POWER EQUIPMENT, AREA 1: GROUP 7-
BALLAST REGULATOR; BOOM TRUCK OR DUAL-PURPOSE
A-FRAME TRUCK, NON-ROTATING-UNDER 15 TONS; CARY IFT
OR SIMILAR; COMBINATION SLURRY MIER AND/OR CLEANER;
DRILLING EQUIPMENT, 20 FT AND UNDER M.R.C.;
FIRETENDER (HOT PLANT); GROUTING MACHINE OPERATOR;
HIGHLINE CABLEWAY SIGNALPERSON; STATIONARY BELT
LOADER (KOLMAN OR SIMILAR); LIFT SLAB MACHINE
(VAGTBORG AND SIMILAR TYPES); MAGINNES INTERNAL
FULL SLAB VIBRATOR; MATERIAL HOIST (1 DRUM);
MECHANICAL TRENCH SHIELD; PAVEMENT BREAKER WITH OR
WITHOUT COMPRESSOR COMBINATION); PIPE CLEANING
MACHINE (TRACTOR PROPELLED AND SUPPORTED); POST
DRIVER; ROLLER (EXCEPT ASPHALT); CHIP SEAL;
SELF-PROPELLED AUTOMATICALLY APPLIED CONCRETE
CURING MACHINE (ON STREETS, HIGHWAYS, AIRPORTS, AND
CANALS); SELF-PROPELLED COMPACTOR (WITHOUT DOZER);
SIGNALPERSON; SLIP-FORM PUMPS (LIFTING DEVICE FOR
CONCRETE FORMS); TIE SPACE; TOWER MOBILE; TRENCHING
MACHINE, MAXIMUM DIGGING CAPACITY UP TO AND
INCLUDING 5 FT. DEPTH; TRUCK-TYPE LOADER. (AREA 1:
LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL
\$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1:
ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA
COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA
(EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN
PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART),
SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO,
SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE
(EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS
(EASTERN PART), FRESNO (EASTERN PART), MADERA
(EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY
(SOUTHWESTERN PART), TUOLUMNE (EASTERN PART)
COUNTIES).....\$ 58.84

32.53

OPERATOR; POWER EQUIPMENT, AREA 1: GROUP 8- BIT
SHARPENER; BOILER TENDER; BOX OPERATOR;
BRAKEPERSON; COMBINATION MIXER AND COMPRESSOR
(SHOTCRETE/GUNITE); COMPRESSOR OPERATOR; DECKHAND;
FIRE TENDER; FORKLIFT (UNDER 20 FT); GENERATOR;
GUNITE/SHOTCRETE EQUIPMENT OPERATOR; HYDRAULIC
MONITOR; KEN SEAL MACHINE (OR SIMILAR);
MIXERMOBILE; OILER; PUMPOPERATOR; REFRIGERATOR
PLANT; RESERVOIR-DEBRIS TUG (SELF-PROPELLED

FLOATING); ROSS CARRIER (CONSTRUCTION SITE);
ROTOMIST OPERATOR; SELF-PROPELLED TAPE MACHINE;
SHUTTLECAR; SELF-PROPELLED POWER SWEEPER OPERATOR
(INCLUDES VACUUM SWEEPER); SLUSHER OPERATOR;
SURFACE HEATER; SWITCHPERSON; TAR POT FIRETENDER;
TUGGER HOIST, SINGLE DRUM; VACUUM COOLING PLANT;
WELDING MACHINE (POWERED OTHER THAN BY ELECTRICITY.

(AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN
ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.)
(AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART),
CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS,
MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT
EASTERN PART), MERCED, MONTEREY (EXCEPT
SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN
JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ,
STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART)
COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO
(EASTERN PART), MADERA (EASTERN PART), MARIPOSA
(EASTERN PART), MONTEREY (SOUTHWESTERN PART),
TUOLUMNE (EASTERN PART) COUNTIES).....\$ 57.70

32.53

OPERATOR: POWER EQUIPMENT, AREA 1: GROUP 8-A -
ELEVATOR OPERATOR; SKIDSTEER LOADER-BOBCAT 743
SERIES OR SMALLER, AND SIMILAR (WITHOUT
ATTACHMENTS); MINI EXCAVATOR UNDER 25 H.P.
(BACKHOE-TRENCHER); TUB GRINDER WOOD CHIPPER. (AREA
1: LISTED WAGE RATES. AREA 2: RECEIVES AN
ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.)

(AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART),
CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS,
MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT
EASTERN PART), MERCED, MONTEREY (EXCEPT
SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN
JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ,
STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART)
COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO
(EASTERN PART), MADERA (EASTERN PART), MARIPOSA
(EASTERN PART), MONTEREY (SOUTHWESTERN PART),
TUOLUMNE (EASTERN PART) COUNTIES).....\$ 55.49

32.53

OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 1
(CRANES)- CRANE OVER 100 TONS; DERRICK OVER 100
TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE OVER
100 TONS.....\$ 68.81

32.53

OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 1
(OILER)- CRANE OVER 100 TONS; DERRICK OVER 100
TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE OVER
100 TONS.....\$ 43.72

31.15

OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 1
(TRUCK CRANE OILER)- CRANE OVER 100 TONS; DERRICK
OVER 100 TONS; SELF-PROPELLED BOOM-TYPE LIFTING

DEVICE OVER 100 TONS.....	\$ 45.95	31.15
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 2 (CRANES)- CRANE OVER 45 TONS TO 100 TONS; DERRICK UNDER 100 TONS; SELF-PROPELLED BOOM-TYPE LIFTING		
DEVICE OVER 45 TONS TO 100 TONS; TOWER CRANE.....	\$ 67.04	32.53
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 2 (OILER)- CRANE OVER 45 TONS TO 100 TONS; DERRICK UNDER 100 TONS; SELF-PROPELLED BOOM-TYPE LIFTING		
DEVICE OVER 45 TONS TO 100 TONS; TOWER CRANE.....	\$ 43.45	31.15
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 2 (TRUCK CRANE OILER)- CRANE OVER 45 TONS TO 100 TONS; DERRICK UNDER 100 TONS; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE OVER 45 TONS TO 100 TONS;		
TOWER CRANE.....	\$ 45.73	31.15
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 3 (CRANES)- CRANE, 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, 45 TONS AND UNDER.....		
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 3 (HYDRAULIC)- CRANE, 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, 45 TONS AND UNDER.....	\$ 65.56	32.53
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 3 (OILER)- CRANE, 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, 45 TONS AND UNDER.....		
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 3 (TRUCK CRANE OILER)- CRANE, 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, 45 TONS AND UNDER.....	\$ 45.07	31.15
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 3 (OILER)- CRANE, 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, 45 TONS AND UNDER.....		
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 3 (TRUCK CRANE OILER)- CRANE, 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, 45 TONS AND UNDER.....	\$ 43.23	31.15
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 3 (TRUCK CRANE OILER)- CRANE, 45 TONS AND UNDER; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE, 45 TONS AND UNDER.....		
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 4 (CRANES)- CHICAGO BOOM; FORKLIFT, 10 TONS AND OVER; HEAVY-DUTY REPAIR PERSON/WELDER.....	\$ 45.46	31.15
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 4 (CRANES)- CHICAGO BOOM; FORKLIFT, 10 TONS AND OVER; HEAVY-DUTY REPAIR PERSON/WELDER.....		
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 5 (CRANES)- BOOM CAT.....	\$ 63.54	32.53
OPERATOR: POWER EQUIPMENT, STEEL ERECTION: GROUP 5 (CRANES)- BOOM CAT.....		
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- SHAFTS, STOPES, RAISES: AREA 1, GROUP 1- HEADING SHIELD OPERATOR; HEAVY-DUTY REPAIRPERSON; MUCKING MACHINE (RUBBER TIRED, RAIL OR TRACK TYPE); RAISED BORE OPERATOR (TUNNELS); TUNNEL MOLE BORE OPERATOR. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA	\$ 62.24	32.53

(EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 63.06	32.53
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- SHAFTS, STOPES, RAISES: AREA 1, GROUP 1-A- TUNNEL BORE MACHINE OPERATOR 20' DIAMETER OR MORE. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 65.53	
32.53	
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- SHAFTS, STOPES, RAISES: AREA 1, GROUP 2- COMBINATION SLUSHER AND MOTOR OPERATOR; CONCRETE PUMP OR PUMPCRETE GUN; POWER JUMBO OPERATOR. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 61.80	
32.53	
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- SHAFTS, STOPES, RAISES: AREA 1, GROUP 3- DRILL DOCTOR; MINE OR SHAFT HOIST. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY	

(SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 60.47	32.53
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- SHAFTS, STOPES, RAISES: AREA 1, GROUP 4- COMBINATION SLURRY MIXER CLEANER; GROUTING MACHINE OPERATOR; MOTORMAN. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 59.33	
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- SHAFTS, STOPES, RAISES: AREA 1, GROUP 5- BIT SHARPENER; BRAKEMAN; COMBINATION MIXER AND COMPRESSOR (GUNITE); COMPRESSOR OPERATOR; OILER; PUMP OPERATOR; SLUSHER OPERATOR. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 58.19	32.53
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- UNDERGROUND: AREA 1, GROUP 1- HEADING SHIELD OPERATOR; HEAVY-DUTY REPAIRPERSON; MUCKING MACHINE (RUBBER TIRED, RAIL OR TRACK TYPE); RAISED BORE OPERATOR (TUNNELS); TUNNEL MOLE BORE OPERATOR. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ,	

STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 62.96	32.53
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- UNDERGROUND: AREA 1, GROUP 1-A- TUNNEL BORE MACHINE OPERATOR 20' DIAMETER OR MORE. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 65.43	
	32.53
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- UNDERGROUND: AREA 1, GROUP 2- COMBINATION SLUSHER AND MOTOR OPERATOR; CONCRETE PUMP OR PUMPCRETE GUN; POWER JUMBO OPERATOR. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 61.70	
	32.53
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- UNDERGROUND: AREA 1, GROUP 3- DRILL DOCTOR; MINE OR SHAFT HOIST. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN	

PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 60.37	32.53
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- UNDERGROUND: AREA 1, GROUP 4- COMBINATION SLURRY MIXER CLEANER; GROUTING MACHINE OPERATOR; MOTORMAN. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 59.23	
OPERATOR: POWER EQUIPMENT, TUNNEL AND UNDERGROUND WORK- UNDERGROUND: AREA 1, GROUP 5- BIT SHARPENER; BRAKEMAN; COMBINATION MIXER AND COMPRESSOR (GUNITE); COMPRESSOR OPERATOR; OILER; PUMP OPERATOR; SLUSHER OPERATOR. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN PART), FRESNO (EASTERN PART), MADERA (EASTERN PART), MARIPOSA (EASTERN PART), MONTEREY (SOUTHWESTERN PART), TUOLUMNE (EASTERN PART) COUNTIES).....\$ 58.09	32.53
OPERATOR: POWER EQUIPMENT, AREA 1: GROUP 1- OPERATOR OF HELICOPTER (WHEN USED IN ERECTION WORK); HYDRAULIC EXCAVATOR, 7 CU. YDS. AND OVER; POWER SHOVELS, OVER 7 CU. YDS. (AREA 1: LISTED WAGE RATES. AREA 2: RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.) (AREA 1: ALAMEDA, CALAVERAS (EXCEPT EASTERN PART), CONTRA COSTA, FRESNO (EXCEPT EASTERN PART), KINGS, MADERA (EXCEPT EASTERN PART), MARIPOSA (EXCEPT EASTERN PART), MERCED, MONTEREY (EXCEPT SOUTHWESTERN PART), SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA	

CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE (EXCEPT
EASTERN PART) COUNTIES. AREA 2: CALAVERAS (EASTERN
PART), FRESNO (EASTERN PART), MADERA (EASTERN
PART), MARIPOSA (EASTERN PART), MONTEREY
(SOUTHWESTERN PART), TUOLUMNE (EASTERN PART)
COUNTIES).....\$ 66.96 32.53

ENGI0003-008 08/01/2024

	Rates	Fringes
DREDGING: CLAMSHELL & DIPPER DREDGING; HYDRAULIC SUCTION DREDGING- (1) LEVERMAN. AREA 1: ALAMEDA, CONTRA COSTA, KINGS, MERCED, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, AND STANISLAUS COUNTIES. CALAVERAS COUNTY-EXCEPT EASTERN PART. FRESNO COUNTY-EXCEPT EASTERN PART. MADERA COUNTY-EXCEPT EASTERN PART. MARIPOSA COUNTY-EXCEPT EASTERN PART. MONTERREY COUNTY-EXCEPT SOUTHWESTERN PART. TUOLUMNE COUNTY-EXCEPT EASTERN PART.....\$ 60.61		39.55
DREDGING: CLAMSHELL & DIPPER DREDGING; HYDRAULIC SUCTION DREDGING- (1) LEVERMAN. AREA 2: CALAVERAS COUNTY-EASTERN PART; FRESNO COUNTY-EASTERN PART; MADERA COUNTY-EASTERN PART; MARIPOSA COUNTY-EASTERN PART; MONTERREY COUNTY-SOUTHWESTERN PART; TUOLUMNE COUNTY-EASTERN PART.....\$ 62.61		39.55
DREDGING: CLAMSHELL & DIPPER DREDGING; HYDRAULIC SUCTION DREDGING- (2) DREDGE DOZER; HEAVY DUTY REPAIRMAN. AREA 2: CALAVERAS COUNTY-EASTERN PART; FRESNO COUNTY-EASTERN PART; MADERA COUNTY-EASTERN PART; MARIPOSA COUNTY-EASTERN PART; MONTERREY COUNTY-SOUTHWESTERN PART; TUOLUMNE COUNTY-EASTERN PART.....\$ 57.65		39.55
DREDGING: CLAMSHELL & DIPPER DREDGING; HYDRAULIC SUCTION DREDGING- (2) DREDGE DOZER; HEAVY DUTY REPAIRMAN. AREA 1: ALAMEDA, CONTRA COSTA, KINGS, MERCED, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, AND STANISLAUS COUNTIES. CALAVERAS COUNTY-EXCEPT EASTERN PART. FRESNO COUNTY-EXCEPT EASTERN PART. MADERA COUNTY-EXCEPT EASTERN PART. MARIPOSA COUNTY-EXCEPT EASTERN PART. MONTERREY COUNTY-EXCEPT SOUTHWESTERN PART. TUOLUMNE COUNTY-EXCEPT EASTERN PART.....\$ 55.65		39.55
DREDGING: CLAMSHELL & DIPPER DREDGING; HYDRAULIC SUCTION DREDGING- (3) BOOSTER PUMP OPERATOR; DECK ENGINEER; DECK MATE; DREDGE TENDER; WINCH OPERATOR. AREA 1: ALAMEDA, CONTRA COSTA, KINGS, MERCED, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, AND STANISLAUS COUNTIES.		

CALAVERAS COUNTY-EXCEPT EASTERN PART. FRESNO COUNTY-EXCEPT EASTERN PART. MADERA COUNTY-EXCEPT EASTERN PART. MARIPOSA COUNTY-EXCEPT EASTERN PART. MONTERREY COUNTY-EXCEPT SOUTHWESTERN PART. TUOLUMNE COUNTY-EXCEPT EASTERN PART.....	\$ 54.53	39.55
DREDGING: CLAMSHELL & DIPPER DREDGING; HYDRAULIC SUCTION DREDGING- (3) BOOSTER PUMP OPERATOR; DECK ENGINEER; DECK MATE; DREDGE TENDER; WINCH OPERATOR. AREA 2: CALAVERAS COUNTY-EASTERN PART; FRESNO COUNTY-EASTERN PART; MADERA COUNTY-EASTERN PART; MARIPOSA COUNTY-EASTERN PART; MONTERREY COUNTY-SOUTHWESTERN PART; TUOLUMNE COUNTY-EASTERN PART.....		
	\$ 56.53	39.55
DREDGING: CLAMSHELL & DIPPER DREDGING; HYDRAULIC SUCTION DREDGING- (4) BARGEMAN; DECKHAND; FIREMAN; LEVEEHAND; OILER. AREA 1: ALAMEDA, CONTRA COSTA, KINGS, MERCED, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, AND STANISLAUS COUNTIES. CALAVERAS COUNTY-EXCEPT EASTERN PART. FRESNO COUNTY-EXCEPT EASTERN PART. MADERA COUNTY-EXCEPT EASTERN PART. MARIPOSA COUNTY-EXCEPT EASTERN PART. MONTERREY COUNTY-EXCEPT SOUTHWESTERN PART. TUOLUMNE COUNTY-EXCEPT EASTERN PART.....		
	\$ 51.23	39.55
DREDGING: CLAMSHELL & DIPPER DREDGING; HYDRAULIC SUCTION DREDGING- (4) BARGEMAN; DECKHAND; FIREMAN; LEVEEHAND; OILER. AREA 2: CALAVERAS COUNTY-EASTERN PART; FRESNO COUNTY-EASTERN PART; MADERA COUNTY-EASTERN PART; MARIPOSA COUNTY-EASTERN PART; MONTERREY COUNTY-SOUTHWESTERN PART; TUOLUMNE COUNTY-EASTERN PART.....		
	\$ 53.23	39.55

ENGI0003-019 06/30/2025

Rates

Fringes

OPERATOR: POWER EQUIPMENT, LANDSCAPE WORK ONLY: GROUP 1- LANDSCAPE FINISH GRADE OPERATOR: ALL FINISH GRADE WORK REGARDLESS OF EQUIPMENT USED, AND ALL EQUIPMENT WITH A RATING MORE THAN 65 HP. (AREA 1: ALAMEDA, CONTRA COSTA, KINGS, MERCED, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, AND STANISLAUS COUNTIES. CALAVERAS COUNTY-EXCEPT EASTERN PART. FRESNO COUNTY-EXCEPT EASTERN PART. MADERA COUNTY-EXCEPT EASTERN PART. MARIPOSA-EXCEPT EASTERN PART. MONTERREY COUNTY-EXCEPT SOUTHWESTERN PART. TUOLUMNE COUNTY-EXCEPT EASTERN PART.).....	\$ 55.85	28.56
OPERATOR: POWER EQUIPMENT, LANDSCAPE WORK ONLY: GROUP 1- LANDSCAPE FINISH GRADE OPERATOR: ALL		

FINISH GRADE WORK REGARDLESS OF EQUIPMENT USED, AND ALL EQUIPMENT WITH A RATING MORE THAN 65 HP. (AREA 2: CALAVERAS COUNTY-EASTERN PART. FRESNO COUNTY-EASTERN PART. MADERA COUNTY-EASTERN PART. MARIPOSA COUNTY-EASTERN PART. MONTEREY COUNTY-SOUTHWESTERN PART. TUOLUMNE COUNTY-EASTERN PART.).....\$ 57.85	28.56
OPERATOR: POWER EQUIPMENT, LANDSCAPE WORK ONLY: GROUP 2- LANDSCAPE OPERATOR UP TO 65 HP: ALL EQUIPMENT WITH A MANUFACTURER'S RATING OF 65 HP OR LESS EXCEPT EQUIPMENT COVERED BY GROUP 1 OR GROUP 3. THE FOLLOWING EQUIPMENT SHALL BE INCLUDED EXCEPT WHEN USED FOR FINISH WORK AS LONG AS MANUFACTURER'S RATING IS 65 HP OR LESS: A-FRAME AND WINCH TRUCK, BACKHOE, FORKLIFT, HYDRAGRAPHIC SEEDER MACHINE, ROLLER, RUBBER-TIRED AND TRACK EARTHMOVING EQUIPMENT, SKIPLOADER, STRAW BLOWERS, AND TRENCHER 31 HP UP TO 65 HP. (AREA 1: ALAMEDA, CONTRA COSTA, KINGS, MERCED, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, AND STANISLAUS COUNTIES. CALAVARAS COUNTY-EXCEPT EASTERN PART. FRESNO COUNTY-EXCEPT EASTERN PART. MADERA COUNTY-EXCEPT EASTERN PART. MARIPOSAL-EXCEPT EASTERN PART. MONTEREY COUNTY-EXCEPT SOUTHWESTERN PART. TUOLUMNE COUNTY-EXCEPT EASTERN PART.).....\$ 52.25	
	28.56
OPERATOR: POWER EQUIPMENT, LANDSCAPE WORK ONLY: GROUP 2- LANDSCAPE OPERATOR UP TO 65 HP: ALL EQUIPMENT WITH A MANUFACTURER'S RATING OF 65 HP OR LESS EXCEPT EQUIPMENT COVERED BY GROUP 1 OR GROUP 3. THE FOLLOWING EQUIPMENT SHALL BE INCLUDED EXCEPT WHEN USED FOR FINISH WORK AS LONG AS MANUFACTURER'S RATING IS 65 HP OR LESS: A-FRAME AND WINCH TRUCK, BACKHOE, FORKLIFT, HYDRAGRAPHIC SEEDER MACHINE, ROLLER, RUBBER-TIRED AND TRACK EARTHMOVING EQUIPMENT, SKIPLOADER, STRAW BLOWERS, AND TRENCHER 31 HP UP TO 65 HP. (AREA 2: CALAVERAS COUNTY-EASTERN PART. FRESNO COUNTY-EASTERN PART. MADERA COUNTY-EASTERN PART. MARIPOSA COUNTY-EASTERN PART. MONTEREY COUNTY-SOUTHWESTERN PART. TUOLUMNE COUNTY-EASTERN PART.).....\$ 54.25	
	28.56
OPERATOR: POWER EQUIPMENT, LANDSCAPE WORK ONLY: GROUP 3- LANDSCAPE UTILITY OPERATOR: SMALL RUBBER-TIRED TRACTOR, TRENCHER UNDER 31 HP. (AREA 1: ALAMEDA, CONTRA COSTA, KINGS, MERCED, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, AND STANISLAUS COUNTIES. CALAVARAS COUNTY-EXCEPT EASTERN PART. FRESNO COUNTY-EXCEPT EASTERN PART. MADERA COUNTY-EXCEPT EASTERN PART. MARIPOSAL-EXCEPT EASTERN PART.	

MONTEREY COUNTY-EXCEPT SOUTHWESTERN PART. TUOLUMNE COUNTY-EXCEPT EASTERN PART.).....\$ 47.64	28.56
OPERATOR: POWER EQUIPMENT, LANDSCAPE WORK ONLY:	
GROUP 3- LANDSCAPE UTILITY OPERATOR: SMALL RUBBER-TIRED TRACTOR, TRENCHER UNDER 31 HP. (AREA 2: CALAVERAS COUNTY-EASTERN PART. FRESNO COUNTY-EASTERN PART. MADERA COUNTY-EASTERN PART. MARIPOSA COUNTY-EASTERN PART. MONTEREY COUNTY-SOUTHWESTERN PART. TUOLUMNE COUNTY-EASTERN PART.).....\$ 49.64	
	28.56

IRON0377-001 01/01/2025

Rates

Fringes

IRONWORKERS: FENCE ERECTOR (ALAMEDA, CONTRA COSTA, SAN MATEO, SANTA CLARA COUNTIES). PREMIUM PAY: \$6.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: CHINA LAKE NAVAL TEST STATION, CHOCOLATE MOUNTAINS NAVAL RESERVE-NILAND, EDWARDS AFB, FORT IRWIN MILITARY STATION, FORT IRWIN TRAINING CENTER-GOLDSTONE, SAN CLEMENTE ISLAND, SAN NICHOLAS ISLAND, SUSANVILLE FEDERAL PRISON, 29 PALMS-MARINE CORPS, U.S. MARINE BASE-BARSTOW, U.S. NAVAL AIR FACILITY-SEALY, VENDENBERG AFB. \$4.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: ARMY DEENSE LANGUAGE INSTITUTE-MONTEREY, FALLON AIR BASE, NAVAL POST GRADUATE SCHOOL-MONTEREY, YERMO MARINE CORPS LOGISTICS CENTER. \$2.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: PORT HUENEME, PORT MUGU, U.S. COAST GUARD STATION-TWO ROCK.....\$ 45.78	26.51
IRONWORKERS: ORNAMENTAL, REINFORCING AND STRUCTURAL (ALAMEDA, CONTRA COSTA, SAN MATEO, SANTA CLARA COUNTIES) PREMIUM PAY: \$6.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: CHINA LAKE NAVAL TEST STATION, CHOCOLATE MOUNTAINS NAVAL RESERVE-NILAND, EDWARDS AFB, FORT IRWIN MILITARY STATION, FORT IRWIN TRAINING CENTER-GOLDSTONE, SAN CLEMENTE ISLAND, SAN NICHOLAS ISLAND, SUSANVILLE FEDERAL PRISON, 29 PALMS-MARINE CORPS, U.S. MARINE BASE-BARSTOW, U.S. NAVAL AIR FACILITY-SEALY, VENDENBERG AFB. \$4.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: ARMY DEENSE LANGUAGE INSTITUTE-MONTEREY, FALLON AIR BASE, NAVAL POST GRADUATE SCHOOL-MONTEREY, YERMO MARINE CORPS LOGISTICS CENTER. \$2.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: PORT HUENEME, PORT MUGU, U.S. COAST GUARD STATION-TWO ROCK.....\$ 55.33	35.15

IRON0377-003 01/01/2025

Rates

Fringes

IRONWORKERS: FENCE ERECTOR (SAN FRANCISCO CITY AND COUNTY) PREMIUM PAY: \$6.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: CHINA LAKE NAVAL TEST STATION, CHOCOLATE MOUNTAINS NAVAL RESERVE-NILAND, EDWARDS AFB, FORT IRWIN MILITARY STATION, FORT IRWIN TRAINING CENTER-GOLDSTONE, SAN CLEMENTE ISLAND, SAN NICHOLAS ISLAND, SUSANVILLE FEDERAL PRISON, 29 PALMS-MARINE CORPS, U.S. MARINE BASE-BARSTOW, U.S. NAVAL AIR FACILITY-SEALY, VENDENBERG AFB. \$4.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: ARMY DEENSE LANGUAGE INSTITUTE-MONTEREY, FALLON AIR BASE, NAVAL POST GRADUATE SCHOOL-MONTEREY, YERMO MARINE CORPS LOGISTICS CENTER. \$2.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: PORT HUENEME, PORT MUGU, U.S. COAST GUARD STATION-TWO ROCK.....\$ 45.78

IRONWORKERS: ORNAMENTAL, REINFORCING AND STRUCTURAL (SAN FRANCISCO CITY AND COUNTY) PREMIUM PAY: \$6.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: CHINA LAKE NAVAL TEST STATION, CHOCOLATE MOUNTAINS NAVAL RESERVE-NILAND, EDWARDS AFB, FORT IRWIN MILITARY STATION, FORT IRWIN TRAINING CENTER-GOLDSTONE, SAN CLEMENTE ISLAND, SAN NICHOLAS ISLAND, SUSANVILLE FEDERAL PRISON, 29 PALMS-MARINE CORPS, U.S. MARINE BASE-BARSTOW, U.S. NAVAL AIR FACILITY-SEALY, VENDENBERG AFB. \$4.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: ARMY DEENSE LANGUAGE INSTITUTE-MONTEREY, FALLON AIR BASE, NAVAL POST GRADUATE SCHOOL-MONTEREY, YERMO MARINE CORPS LOGISTICS CENTER. \$2.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: PORT HUENEME, PORT MUGU, U.S. COAST GUARD STATION-TWO ROCK.....\$ 55.83

26.51

35.15

IRON0433-005 01/01/2025

Rates

Fringes

IRONWORKER: FENCE ERECTOR (REMAINING COUNTIES) PREMIUM PAY: \$6.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: CHINA LAKE NAVAL TEST STATION, CHOCOLATE MOUNTAINS NAVAL RESERVE-NILAND, EDWARDS AFB, FORT IRWIN MILITARY STATION, FORT IRWIN TRAINING CENTER-GOLDSTONE, SAN CLEMENTE ISLAND, SAN NICHOLAS ISLAND, SUSANVILLE FEDERAL PRISON, 29 PALMS-MARINE CORPS, U.S. MARINE BASE-BARSTOW, U.S. NAVAL AIR FACILITY-SEALY, VENDENBERG AFB. \$4.00 ADDITIONAL PER HOUR AT THE FOLLOWING LOCATIONS: ARMY DEENSE LANGUAGE INSTITUTE-MONTEREY, FALLON AIR

BASE, NAVAL POST GRADUATE SCHOOL-MONTEREY, YERMO
MARINE CORPS LOGISTICS CENTER. \$2.00 ADDITIONAL PER
HOUR AT THE FOLLOWING LOCATIONS: PORT HUENEME, PORT
MUGU, U.S. COAST GUARD STATION-TWO ROCK.....\$ 45.78 26.51
IRONWORKER: ORNAMENTAL, REINFORCING AND STRUCTURAL
(REMAINING COUNTIES) PREMIUM PAY: \$6.00 ADDITIONAL
PER HOUR AT THE FOLLOWING LOCATIONS: CHINA LAKE
NAVAL TEST STATION, CHOCOLATE MOUNTAINS NAVAL
RESERVE-NILAND, EDWARDS AFB, FORT IRWIN MILITARY
STATION, FORT IRWIN TRAINING CENTER-GOLDSTONE, SAN
CLEMENTE ISLAND, SAN NICHOLAS ISLAND, SUSANVILLE
FEDERAL PRISON, 29 PALMS-MARINE CORPS, U.S. MARINE
BASE-BARSTOW, U.S. NAVAL AIR FACILITY-SEALY,
VENDENBERG AFB. \$4.00 ADDITIONAL PER HOUR AT THE
FOLLOWING LOCATIONS: ARMY DEENSE LANGUAGE
INSTITUTE-MONTEREY, FALLON AIR BASE, NAVAL POST
GRADUATE SCHOOL-MONTEREY, YERMO MARINE CORPS
LOGISTICS CENTER. \$2.00 ADDITIONAL PER HOUR AT THE
FOLLOWING LOCATIONS: PORT HUENEME, PORT MUGU, U.S.
COAST GUARD STATION-TWO ROCK.....\$ 50.70 35.15

LAB00067-006 06/30/2025

	Rates	Fringes
LABORER: ASBESTOS/MOLD/LEAD LABORER. ASBESTOS REMOVAL-SCOPE OF WORK: SITE MOBILIZATION; INITIAL SITE CLEAN-UP; SITE PREPARATION; REMOVAL OF ASBESTOS-CONTAINING MATERIALS FROM WALLS AND CEILINGS; OR FROM PIPES, BOILERS, AND MECHANICAL SYSTEMS ONLY IF THEY ARE BEING SCRAPPED; ENCAPSULATION, ENCLOSURE AND DISPOSAL OF ASBESTOS-CONTAINING MATERIALS BY HAND OR WITH EQUIPMENT OR MACHINERY; SCAFFOLDING; FABRICATION OF TEMPORARY WOODEN BARRIERS; AND ASSEMBLY OF DECONTAMINATION STATIONS. (AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, AND SANTA CLARA COUNTIES).....\$ 39.15		30.03
LABORER: ASBESTOS/MOLD/LEAD LABORER. ASBESTOS REMOVAL-SCOPE OF WORK: SITE MOBILIZATION; INITIAL SITE CLEAN-UP; SITE PREPARATION; REMOVAL OF ASBESTOS-CONTAINING MATERIALS FROM WALLS AND CEILINGS; OR FROM PIPES, BOILERS, AND MECHANICAL SYSTEMS ONLY IF THEY ARE BEING SCRAPPED; ENCAPSULATION, ENCLOSURE AND DISPOSAL OF ASBESTOS-CONTAINING MATERIALS BY HAND OR WITH EQUIPMENT OR MACHINERY; SCAFFOLDING; FABRICATION OF TEMPORARY WOODEN BARRIERS; AND ASSEMBLY OF DECONTAMINATION STATIONS. (AREA 2: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, MONTEREY,		

SAN BENITO, SAN JOAQUIN, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 38.15	30.03

LAB00073-002 07/01/2023		
	Rates	Fringes
LABORER, TRAFFIC CONTROL/LANE CLOSURE: ESCORT DRIVER, FLAG PERSON (CALAVERAS AND SAN JOAQUIN COUNTIES).....	\$ 36.26	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON I- LAYOUT OF TRAFFIC CONTROL, CRASH CUSHIONS, CONSTRUCTION AREA AND ROADSIDE SIGNAGE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....	\$ 36.56	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON II- INSTALLATION AND REMOVAL OF TEMPORARY/PERMANENT SIGNS, MARKERS, DELINEATORS AND CRASH CUSHIONS. (CALAVERAS AND SAN JOAQUIN COUNTIES).....	\$ 34.06	27.30

LAB00073-003 07/01/2023		
	Rates	Fringes
LABORER: MASON TENDER-BRICK (SAN JOAQUIN COUNTY)....	\$ 36.29	25.55

LAB00073-005 06/26/2023		
	Rates	Fringes
TUNNEL AND SHAFT LABORERS: GROUP 1- DIAMOND DRILLER; GROUND MEN; GUNITE AND SHOTCRETE NOZZLEMEN..	\$ 45.89	27.72
TUNNEL AND SHAFT LABORERS: GROUP 2- RODMEN; SHAFT WORK & RAISE (BELOW ACTUAL OR EXCAVATED GROUND LEVEL).....	\$ 45.66	27.72
TUNNEL AND SHAFT LABORERS: GROUP 3- BIT GRINDER; BLASTER, DRILLER, POWDERMEN, HEADING; CHERRY PICKERMEN - WHERE CAR IS LIFTED; CONCRETE FINISHER IN TUNNEL; CONCRETE SCREEDMAN; GROUT PUMPMAN AND POTMAN; GUNITE & SHOTCRETE GUNMAN & POTMAN; HEADERMEN; HIGH PRESSURE NOZZLEMAN; MINER - TUNNEL, INCLUDING TOP AND BOTTOM MAN ON SHAFT AND RAISE WORK; NIPPER; NOZZLEMAN ON SLICK LINE; SANDBLASTER - POTMAN, ROBOTIC SHOTCRETE PLACER, SEGMENT ERECTOR, TUNNEL MUCK HAULER, STEEL FORM RAISER AND SETTER; TIMBERMAN, RETIMBERMAN (WOOD OR STEEL OR SUBSTITUTE MATERIALS THEREFORE); TUGGER (FOR TUNNEL LABORER WORK); CABLE TENDER; CHUCK TENDER; POWDERMAN - PRIMER HOUSE.....	\$ 45.41	27.72
TUNNEL AND SHAFT LABORERS: GROUP 4- VIBRATOR OPERATOR, PAVEMENT BREAKER; BULL GANG - MUCKERS, TRACKMEN; CONCRETE CREW - INCLUDES RODDING AND		

SPREADING, DUMPMEN (ANY METHOD).....	\$ 44.96	27.72
TUNNEL AND SHAFT LABORERS: GROUP 5- GROUT CREW; REBOUNDMAN; SWAMPER/ BRAKEMAN.....	\$ 44.42	27.72
TUNNEL AND SHAFT LABORERS: SHOTCRETE SPECIALIST.....	\$ 46.41	27.72

LABO0073-007 06/30/2025

	Rates	Fringes
LABORER (CONSTRUCTION CRAFT LABORERS) GROUP 1-F- WIRE WINDING MACHINE IN CONNECTION WITH GUNITING OR SHOT CRETE. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED.(CALAVERAS AND SAN JOAQUIN COUNTIES).....	\$ 30.37	29.89
LABORER, CONSTRUCTION CRAFT LABORERS: CONSTRUCTION SPECIALIST GROUP- ASPHALT IRONER AND RAKER; CHAINSAW; LASER BEAM IN CONNECTION WITH LABORERS' WORK; CAST-IN- PLACE MANHOLE FORM SETTER; PRESSURE PIPELAYER; DAVIS TRENCHER - 300 OR SIMILAR TYPE (AND ALL SMALL TRENCHERS); BLASTER; DIAMOND DRILLER; MULTIPLE UNIT DRILL; HYDRAULIC DRILL. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK		

COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 38.85

29.89

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-
ASPHALT SPREADER BOXES (ALL TYPES); BARKO, WACKER
AND SIMILAR TYPE TAMPERS; BUGGYMOBILE; CAULKER,
BANDER, PIPEWRAPPER, CONDUIT LAYER, PLASTIC
PIPELAYER; CERTIFIED HAZARDOUS WASTE WORKER
INCLUDING LEADE ABATEMENT; COMPACTORS OF ALL TYPES;
CONCRETE AND MAGNESITE MIXER, 1/2 YD. AND UNDER;
CONCRETE PAN WORK; CONCRETE SANDER; CONCRETE SAW;
CRIBBER AND/OR SHORING; CUT GRANITE CURB SETTER;
DRI-PAK-IT MACHINE; FALLER, LOGLOADER AND BUCKER;
FORM RAISER, SLIP FORMS; GREEN CUTTER; HEADERBOARD,
HUBSETTER, ALIGNER, BY ANY METHOD; HIGH PRESSURE
BLOW PIPE (1-1/2" OR OVER, 100 LBS. PRESSURE/OVER);
HYDRO SEEDER AND SIMILAR TYPE; JACKHAMMER OPERATOR;
JACKING OF PIPE OVER 12 INCHES; JACKSON AND SIMILAR
TYPE COMPACTOR; KETTLE TENDER, POT AND WORKER
APPLYING ASPHALT, LAY-KOLD, CREOSOTE, LIME, CAUSTIC
AND SIMILAR TYPE MATERIALS (APPLYING MEANS
APPLYING, DIPPING OR HANDLING OF SUCH MATERIALS);
LAGGING, SHEETING, WHALING, BRACING, TRENCHJACKING,
LAGGING HAMMER; MAGNESITE, EPOXYRESIN, FIBERGLASS,
MASTIC WORKER (WET OR DRY); NO JOINT PIPE AND
STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS;
PAVEMENT BREAKER AND SPADER, INCLUDING TOOL
GRINDER; PERMA CURB; PIPELAYER (INCLUDING GRADE
CHECKING IN CONNECTION WITH PIPELAYING);
PRECAST-MANHOLE SETTER; PRESSURE PIPE TESTER; POST
HOLE DIGGER, AIR, GAS AND ELECTRIC; POWER BROOM
SWEEPER; POWER TAMPERS OF ALL TYPES (EXCEPT AS
SHOWN IN GROUP 2); RAM SET GUN AND STUD GUN; RIPRAP
STONEPAVER AND ROCK-SLINGER, INCLUDING PLACING OF
SACKED CONCRETE AND/OR SAND (WET OR DRY) AND
GABIONS AND SIMILAR TYPE; ROTARY SCARIFIER OR
MULTIPLE HEAD CONCRETE CHIPPING SCARIFIER; ROTO AND
DITCH WITCH; ROTOTILLER; SANDBLASTER, POT, GUN,
NOZZLE OPERATORS; SIGNALLING AND RIGGING; TANK
CLEANER; TREE CLIMBER; TURBO BLASTER; VIBRASCREED,
BULL FLOAT IN CONNECTION WITH LABORERS' WORK;
VIBRATOR; HAZARDOUS WASTE WORKER (LEAD REMOVAL);
ASBESTOS AND MOLD REMOVAL WORKER. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,

SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CALAVERAS AND SAN JOAQUIN COUNTIES)\$ 38.15 29.89

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-A- JOY DRILL MODEL TWM-2A; GARDNER-DENVER MODEL DH143 AND SIMILAR TYPE DRILLS; TRACK DRILLER; JACK LEG DRILLER; WAGON DRILLER; MECHANICAL DRILLERS, ALL TYPES REGARDLESS OF TYPE OR METHOD OF POWER; MECHANICAL PIPE LAYERS, ALL TYPES REGARDLESS OF TYPE OR METHOD OF POWER; BLASTER AND POWDER; ALL WORK OF LOADING, PLACING AND BLASTING OF ALL POWDER AND EXPLOSIVES OF WHATEVER TYPE REGARDLESS OF METHOD USED FOR SUCH LOADING AND PLACING; HIGH SCALERS (INCLUDING DRILLING OF SAME); TREE TOPPER; BIT GRINDER. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CALAVERAS AND SAN JOAQUIN COUNTIES)\$ 38.37 29.89

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-C-

BURNING AND WELDING IN CONNECTION WITH LABORERS' WORK; SYNTHETIC THERMOPLASTICS AND SIMILAR TYPE WELDING. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 38.20

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-E- WORK ON AND/OR IN BELL HOLE FOOTINGS AND SHAFTS THEREOF, AND WORK ON AND IN DEEP FOOTINGS. (A DEEP FOOTING IS A HOLE 15 FEET OR MORE IN DEPTH.) IN THE EVENT THE DEPTH OF THE FOOTING IS UNKNOWN AT THE COMMENCEMENT OF EXCAVATION, AND THE FINAL DEPTH EXCEEDS 15 FEET, THE DEEP FOOTING WAGE RATE WOULD APPLY TO ALL EMPLOYEES FOR EACH AND EVERY DAY WORKED ON OR IN THE EXCAVATION OF THE FOOTING FROM THE DATE OF INCEPTION. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER

29.89

WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CALAVERAS AND SAN JOAQUIN COUNTIES).....	\$ 38.70	29.89
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 2- ASPHALT SHOVELER; CEMENT DUMPER AND HANDLING DRY CEMENT OR GYPSUM; CHOKE-SETTER AND RIGGER (CLEARING WORK); CONCRETE BUCKET DUMPER AND CHUTE; CONCRETE CHIPPING AND GRINDING; CONCRETE LABORER (WET OR DRY); DRILLER TENDER, CHUCK TENDER, NIPPER; GUINEA CHASER (STAKE), GROUT CREW; HIGH PRESSURE NOZZLE, ADDUCTOR; HYDRAULIC MONITOR (OVER 100 LBS. PRESSURE); LOADING AND UNLOADING, CARRYING AND HAULING OF ALL RODS AND MATERIALS FOR USE IN REINFORCING CONCRETE CONSTRUCTION; PITTSBURGH CHIPPER AND SIMILAR TYPE BRUSH SHREDDERS; SLOPER; SINGLE FOOT, HAND-HELD, PNEUMATIC TAMPER; ALL PNEUMATIC, AIR, GAS AND ELECTRIC TOOLS NOT LISTED IN GROUPS 1 THROUGH 1-F; JACKING OF PIPE - UNDER 12 INCHES. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CALAVERAS AND SAN JOAQUIN COUNTIES).....		
	\$ 38.00	29.89
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 3- CONSTRUCTION LABORERS, INCLUDING BRIDGE AND GENERAL LABORER; DUMP, LOAD SPOTTER; FLAG PERSON; FIRE WATCHER; FENCE ERECTOR; GUARDRAIL ERECTOR; GARDENER, HORTICULTURAL AND LANDSCAPE LABORER; JETTING; LIMBER, BRUSH LOADER AND PILER; PAVEMENT MARKER (BUTTON SETTER); MAINTENANCE, REPAIR TRACK AND ROAD BEDS; STREETCAR AND RAILROAD CONSTRUCTION TRACK LABORER; TEMPORARY AIR AND WATER LINES, VICTAULIC OR SIMILAR; TOOL ROOM ATTENDANT (JOBSITE ONLY). FOOTNOTES: LABORERS WORKING OFF OR WITH OR		

FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 37.90

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 4-FINAL CLEAN-UP WORK OF DEBRIS, GROUNDS AND BUILDING INCLUDING BUT NOT LIMITED TO: STREET CLEANER; CLEANING AND WASHING WINDOWS; BRICK CLEANER (JOBSITE ONLY); MATERIAL CLEANER (JOBSITE ONLY). THE CLASSIFICATION ""MATERIAL CLEANER"" IS TO BE UTILIZED UNDER THE FOLLOWING CONDITIONS: A: AT DEMOLITION SITE FOR THE SALVAGE OF THE MATERIAL. B: AT THE CONCLUSION OF A JOB WHERE THE MATERIAL IS TO BE SALVAGED AND STOCKED TO BE REUSED ON ANOTHER JOB. C: FOR THE CLEANING OF SALVAGE MATERIAL AT THE JOBSITE OR TEMPORARY JOBSITE YARD. THE MATERIAL CLEANER CLASSIFICATION SHOULD NOT BE USED IN THE PERFORMANCE OF ""FORM STRIPPING, CLEANING AND OILING AND MOVING TO THE NEXT POINT OF ERECTION"". FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT

29.89

SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 31.59 29.89

LABORER, GUNITE: GROUP 1- STRUCTURAL NOZZLEMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 39.11 29.89

LABORER, GUNITE: GROUP 2- NOZZLEMAN, GUNMAN, POTMAN, GROUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 38.61 29.89

LABORER, GUNITE: GROUP 3- REBOUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 38.02 29.89

LABORER, GUNITE: GROUP 4- GUINTE LABORER. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 37.90 29.89

LABORER, WRECKING: GROUP 1- SKILLED WRECKER (REMOVING AND SALVAGING OF SASH, WINDOWS, AND MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 38.15 29.89

LABORER, WRECKING: GROUP 2- SEMI-SKILLED WRECKER (SALVAGING OF OTHER BUILDING MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 38.00 29.89

LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (1) New Construction. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 37.90 29.89

LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (2) Establishment Warranty Period. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM

BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 31.59	29.89
---	-------

LAB00073-009 07/01/2023

	Rates	Fringes
LABORER, PLASTER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (CALAVERAS AND SAN JOAQUIN COUNTIES).....\$ 39.77		28.54

LAB00261-003 07/01/2023

	Rates	Fringes
LABORER, TRAFFIC CONTROL/LANE CLOSURE: ESCORT DRIVER, FLAG PERSON (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 37.26		27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON I- LAYOUT OF TRAFFIC CONTROL, CRASH CUSHIONS, CONSTRUCTION AREA AND ROADSIDE SIGNAGE. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 37.56		27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON II- INSTALLATION AND REMOVAL OF TEMPORARY/PERMANENT SIGNS, MARKERS, DELINEATORS AND CRASH CUSHIONS. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 35.06		27.30

LAB00261-005 06/26/2023

	Rates	Fringes
TUNNEL AND SHAFT LABORERS: GROUP 1- DIAMOND DRILLER; GROUND MEN; GUNITE AND SHOTCRETE NOZZLEMEN (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 45.89		27.72
TUNNEL AND SHAFT LABORERS: GROUP 2- RODMEN; SHAFT WORK & RAISE (BELOW ACTUAL OR EXCAVATED GROUND LEVEL) (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 45.66		27.72
TUNNEL AND SHAFT LABORERS: GROUP 3- BIT GRINDER; BLASTER, DRILLER, POWDERMEN, HEADING; CHERRY PICKERMEN - WHERE CAR IS LIFTED; CONCRETE FINISHER IN TUNNEL; CONCRETE SCREEDMAN; GROUT PUMPMAN AND POTMAN; GUNITE & SHOTCRETE GUNMAN & POTMAN; HEADERMEN; HIGH PRESSURE NOZZLEMAN; MINER - TUNNEL, INCLUDING TOP AND BOTTOM MAN ON SHAFT AND RAISE WORK; NIPPER; NOZZLEMAN ON SLICK LINE; SANDBLASTER - POTMAN, ROBOTIC SHOTCRETE PLACER, SEGMENT ERECTOR, TUNNEL MUCK HAULER, STEEL FORM RAISER AND SETTER; TIMBERMAN, RETIMBERMAN (WOOD OR STEEL OR SUBSTITUTE MATERIALS THEREFORE); TUGGER (FOR TUNNEL LABORER WORK); CABLE TENDER; CHUCK TENDER;		

POWDERMAN - PRIMER HOUSE (SAN FRANCISCO AND SAN MATEO COUNTIES).....	\$ 45.41	27.72
TUNNEL AND SHAFT LABORERS: GROUP 4- VIBRATOR OPERATOR, PAVEMENT BREAKER; BULL GANG - MUCKERS, TRACKMEN; CONCRETE CREW - INCLUDES RODDING AND SPREADING, DUMPMEN (ANY METHOD) (SAN FRANCISCO AND SAN MATEO COUNTIES).....	\$ 44.96	27.72
TUNNEL AND SHAFT LABORERS: GROUP 5- GROUT CREW; REBOUNDMAN; SWAMPER/ BRAKEMAN (SAN FRANCISCO AND SAN MATEO COUNTIES).....	\$ 44.42	27.72
TUNNEL AND SHAFT LABORERS: SHOTCRETE SPECIALIST (SAN FRANCISCO AND SAN MATEO COUNTIES).....	\$ 46.41	27.72

LAB00261-009 06/26/2023

Rates

Fringes

LABORER (CONSTRUCTION CRAFT LABORERS) GROUP 1-F- WIRE WINDING MACHINE IN CONNECTION WITH GUNITING OR SHOT CRETE. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SAN FRANCISCO AND SAN MATEO COUNTIES).....	\$ 31.37	23.20
LABORER, CONSTRUCTION CRAFT LABORERS: CONSTRUCTION SPECIALIST GROUP- ASPHALT IRONER AND RAKER; CHAINSAW; LASER BEAM IN CONNECTION WITH LABORERS' WORK; CAST-IN- PLACE MANHOLE FORM SETTER; PRESSURE PIPELAYER; DAVIS TRENCHER - 300 OR SIMILAR TYPE (AND ALL SMALL TRENCHERS); BLASTER; DIAMOND DRILLER; MULTIPLE UNIT DRILL; HYDRAULIC DRILL. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE		

\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SAN FRANCISCO AND SAN MATEO COUNTIES)....\$ 37.20

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1- ASPHALT SPREADER BOXES (ALL TYPES); BARKO, WACKER AND SIMILAR TYPE TAMPERS; BUGGYMOBILE; CAULKER, BANDER, PIPEWRAPPER, CONDUIT LAYER, PLASTIC PIPELAYER; CERTIFIED HAZARDOUS WASTE WORKER INCLUDING LEADE ABATEMENT; COMPACTORS OF ALL TYPES; CONCRETE AND MAGNESITE MIXER, 1/2 YD. AND UNDER; CONCRETE PAN WORK; CONCRETE SANDER; CONCRETE SAW; CRIBBER AND/OR SHORING; CUT GRANITE CURB SETTER; DRI-PAK-IT MACHINE; FALLER, LOGLOADER AND BUCKER; FORM RAISER, SLIP FORMS; GREEN CUTTER; HEADERBOARD, HUBSETTER, ALIGNER, BY ANY METHOD; HIGH PRESSURE BLOW PIPE (1-1/2" OR OVER, 100 LBS. PRESSURE/OVER); HYDRO SEEDER AND SIMILAR TYPE; JACKHAMMER OPERATOR; JACKING OF PIPE OVER 12 INCHES; JACKSON AND SIMILAR TYPE COMPACTOR; KETTLE TENDER, POT AND WORKER APPLYING ASPHALT, LAY-KOLD, CREOSOTE, LIME, CAUSTIC AND SIMILAR TYPE MATERIALS (APPLYING MEANS APPLYING, DIPPING OR HANDLING OF SUCH MATERIALS); LAGGING, SHEETING, WHALING, BRACING, TRENCHJACKING, LAGGING HAMMER; MAGNESITE, EPOXYRESIN, FIBERGLASS, MASTIC WORKER (WET OR DRY); NO JOINT PIPE AND STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS; PAVEMENT BREAKER AND SPADER, INCLUDING TOOL GRINDER; PERMA CURB; PIPELAYER (INCLUDING GRADE CHECKING IN CONNECTION WITH PIPELAYING); PRECAST-MANHOLE SETTER; PRESSURE PIPE TESTER; POST HOLE DIGGER, AIR, GAS AND ELECTRIC; POWER BROOM SWEEPER; POWER TAMPERS OF ALL TYPES (EXCEPT AS SHOWN IN GROUP 2); RAM SET GUN AND STUD GUN; RIPRAP STONEPAVER AND ROCK-SLINGER, INCLUDING PLACING OF SACKED CONCRETE AND/OR SAND (WET OR DRY) AND GABIONS AND SIMILAR TYPE; ROTARY SCARIFIER OR

MULTIPLE HEAD CONCRETE CHIPPING SCARIFIER; ROTO AND
DITCH WITCH; ROTOTILLER; SANDBLASTER, POT, GUN,
NOZZLE OPERATORS; SIGNALLING AND RIGGING; TANK
CLEANER; TREE CLIMBER; TURBO BLASTER; VIBRASCREED,
BULL FLOAT IN CONNECTION WITH LABORERS' WORK;
VIBRATOR; HAZARDOUS WASTE WORKER (LEAD REMOVAL);
ASBESTOS AND MOLD REMOVAL WORKER. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B:
SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE
GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY
WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW
SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK
INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND
ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE
\$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (SAN FRANCISCO AND SAN
MATEO COUNTIES).....\$ 36.50

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-A-
JOY DRILL MODEL TWM-2A; GARDNER-DENVER MODEL DH143
AND SIMILAR TYPE DRILLS; TRACK DRILLER; JACK LEG
DRILLER; WAGON DRILLER; MECHANICAL DRILLERS, ALL
TYPES REGARDLESS OF TYPE OR METHOD OF POWER;
MECHANICAL PIPE LAYERS, ALL TYPES REGARDLESS OF
TYPE OR METHOD OF POWER; BLASTER AND POWDER; ALL
WORK OF LOADING, PLACING AND BLASTING OF ALL POWDER
AND EXPLOSIVES OF WHATEVER TYPE REGARDLESS OF
METHOD USED FOR SUCH LOADING AND PLACING; HIGH
SCALERS (INCLUDING DRILLING OF SAME); TREE TOPPER;
BIT GRINDER. GROUP 1-B: SEWER CLEANERS SHALL
RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES.
""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR
COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER
SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE,
LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE
SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE
GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND
REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES
PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25
PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK

PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 36.72

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-C- BURNING AND WELDING IN CONNECTION WITH LABORERS' WORK; SYNTHETIC THERMOPLASTICS AND SIMILAR TYPE WELDING. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SAN FRANCISCO AND SAN MATEO COUNTIES)....\$ 36.55

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-E- WORK ON AND/OR IN BELL HOLE FOOTINGS AND SHAFTS THEREOF, AND WORK ON AND IN DEEP FOOTINGS. (A DEEP FOOTING IS A HOLE 15 FEET OR MORE IN DEPTH.) IN THE EVENT THE DEPTH OF THE FOOTING IS UNKNOWN AT THE COMMENCEMENT OF EXCAVATION, AND THE FINAL DEPTH EXCEEDS 15 FEET, THE DEEP FOOTING WAGE RATE WOULD APPLY TO ALL EMPLOYEES FOR EACH AND EVERY DAY WORKED ON OR IN THE EXCAVATION OF THE FOOTING FROM THE DATE OF INCEPTION. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00

PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 37.05	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 2- ASPHALT SHOVELER; CEMENT DUMPER AND HANDLING DRY CEMENT OR GYPSUM; CHOKE-SETTER AND RIGGER (CLEARING WORK); CONCRETE BUCKET DUMPER AND CHUTE; CONCRETE CHIPPING AND GRINDING; CONCRETE LABORER (WET OR DRY); DRILLER TENDER, CHUCK TENDER, NIPPER; GUINEA CHASER (STAKE), GROUT CREW; HIGH PRESSURE NOZZLE, ADDUCTOR; HYDRAULIC MONITOR (OVER 100 LBS. PRESSURE); LOADING AND UNLOADING, CARRYING AND HAULING OF ALL RODS AND MATERIALS FOR USE IN REINFORCING CONCRETE CONSTRUCTION; PITTSBURGH CHIPPER AND SIMILAR TYPE BRUSH SHREDDERS; SLOPER; SINGLE FOOT, HAND-HELD, PNEUMATIC TAMPER; ALL PNEUMATIC, AIR, GAS AND ELECTRIC TOOLS NOT LISTED IN GROUPS 1 THROUGH 1-F; JACKING OF PIPE - UNDER 12 INCHES. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SAN FRANCISCO AND SAN MATEO COUNTIES)....\$ 36.35	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 3- CONSTRUCTION LABORERS, INCLUDING BRIDGE AND GENERAL LABORER; DUMP, LOAD SPOTTER; FLAG PERSON; FIRE	

WATCHER; FENCE ERECTOR; GUARDRAIL ERECTOR;
GARDENER, HORTICULTURAL AND LANDSCAPE LABORER;
JETTING; LIMBER, BRUSH LOADER AND PILER; PAVEMENT
MARKER (BUTTON SETTER); MAINTENANCE, REPAIR TRACK
AND ROAD BEDS; STREETCAR AND RAILROAD CONSTRUCTION
TRACK LABORER; TEMPORARY AIR AND WATER LINES,
VICTAULIC OR SIMILAR; TOOL ROOM ATTENDANT (JOBSITE
ONLY). FOOTNOTES: LABORERS WORKING OFF OR WITH OR
FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (SAN FRANCISCO AND SAN MATEO COUNTIES)....\$ 36.25
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 4-
FINAL CLEAN-UP WORK OF DEBRIS, GROUNDS AND BUILDING
INCLUDING BUT NOT LIMITED TO: STREET CLEANER;
CLEANING AND WASHING WINDOWS; BRICK CLEANER
(JOBSITE ONLY); MATERIAL CLEANER (JOBSITE ONLY).
THE CLASSIFICATION ""MATERIAL CLEANER"" IS TO BE
UTILIZED UNDER THE FOLLOWING CONDITIONS: A: AT
DEMOLITION SITE FOR THE SALVAGE OF THE MATERIAL.
B: AT THE CONCLUSION OF A JOB WHERE THE MATERIAL IS
TO BE SALVAGED AND STOCKED TO BE REUSED ON ANOTHER
JOB. C: FOR THE CLEANING OF SALVAGE MATERIAL AT
THE JOBSITE OR TEMPORARY JOBSITE YARD. THE
MATERIAL CLEANER CLASSIFICATION SHOULD NOT BE USED
IN THE PERFORMANCE OF ""FORM STRIPPING, CLEANING
AND OILING AND MOVING TO THE NEXT POINT OF
ERECTION"". FOOTNOTES: LABORERS WORKING OFF OR
WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS,
BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE
APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS
SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE
RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO
HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN

27.30

SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE
RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL
RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00
PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (SAN FRANCISCO AND SAN
MATEO COUNTIES).....\$ 29.94 27.30
LABORER, GUNITE: GROUP 1- STRUCTURAL NOZZLEMAN.
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 37.46 27.30
LABORER, GUNITE: GROUP 2- NOZZLEMAN, GUNMAN,
POTMAN, GROUNDMAN. FOOTNOTES: LABORERS WORKING
OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING
SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE
THE APPLICABLE WAGE RATE. (SAN FRANCISCO AND SAN
MATEO COUNTIES).....\$ 36.96 27.30
LABORER, GUNITE: GROUP 3- REBOUNDMAN. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
HOUR ABOVE THE APPLICABLE WAGE RATE. (SAN
FRANCISCO AND SAN MATEO COUNTIES).....\$ 36.37 27.30
LABORER, GUNITE: GROUP 4- GUINTE LABORER.
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 36.25 27.30
LABORER, WRECKING: GROUP 1- SKILLED WRECKER
(REMOVING AND SALVAGING OF SASH, WINDOWS, AND
MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR
WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS,
BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE
APPLICABLE WAGE RATE. (SAN FRANCISCO AND SAN MATEO
COUNTIES).....\$ 36.50 27.30
LABORER, WRECKING: GROUP 2- SEMI-SKILLED WRECKER
(SALVAGING OF OTHER BUILDING MATERIALS).
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 36.35 27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE

LABORERS - (1) New Construction. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 36.25	27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (2) Establishment Warranty Period. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 29.94	27.30

LAB00261-011 07/01/2023

	Rates	Fringes
MASON TENDER, BRICK. FOOTNOTES: UNDERGROUND WORK SUCH AS SEWERS, MANHOLES, CATCH BASINS, SEWER PIPES, TELEPHONE CONDUITS, TUNNELS AND CUT TRENCHES: \$5.00 PER DAY ADDITIONAL. WORK IN LIVE SEWAGE: \$2.50 PER DAY ADDITIONAL. (SAN FRANCISCO AND SAN MATEO COUNTIES).....\$ 37.05		27.45

LAB00261-014 07/01/2023

	Rates	Fringes
PLASTER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (SAN FRANCISCO AND SAN MATEO COUNTIES)\$ 41.93		30.32

LAB00270-003 07/01/2023

	Rates	Fringes
LABORER, TRAFFIC CONTROL/LANE CLOSURE: ESCORT DRIVER, FLAG PERSON (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 36.26		27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: ESCORT DRIVER, FLAG PERSON (SANTA CALARA COUNTY).....\$ 37.26		27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON I- LAYOUT OF TRAFFIC CONTROL, CRASH CUSHIONS, CONSTRUCTION AREA AND ROADSIDE SIGNAGE. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 36.56		27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON I- LAYOUT OF TRAFFIC CONTROL, CRASH CUSHIONS, CONSTRUCTION AREA AND ROADSIDE SIGNAGE. (SANTA CALARA COUNTY).....\$ 37.56		27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON II- INSTALLATION AND REMOVAL OF TEMPORARY/PERMANENT SIGNS, MARKERS, DELINEATORS, AND CRASH CUSHIONS. (MONTEREY, SAN BENITO, AND		

SANTA CRUZ COUNTIES).....\$ 34.06	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON II- INSTALLATION AND REMOVAL OF TEMPORARY/PERMANENT SIGNS, MARKERS, DELINEATORS, AND CRASH CUSHIONS. (SANTA CALARA COUNTY).....\$ 35.06	27.30

LAB00270-004 06/26/2023

Rates	Fringes
TUNNEL AND SHAFT LABORERS: GROUP 1- DIAMOND DRILLER; GROUND MEN; GUNITE AND SHOTCRETE NOZZLEMEN. (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....\$ 45.89	27.72
TUNNEL AND SHAFT LABORERS: GROUP 2- RODMEN; SHAFT WORK & RAISE (BELOW ACTUAL OR EXCAVATED GROUND LEVEL). (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....\$ 45.66	27.72
TUNNEL AND SHAFT LABORERS: GROUP 3- BIT GRINDER; BLASTER, DRILLER, POWDERMEN, HEADING; CHERRY PICKERMEN - WHERE CAR IS LIFTED; CONCRETE FINISHER IN TUNNEL; CONCRETE SCREEDMAN; GROUT PUMPMAN AND POTMAN; GUNITE & SHOTCRETE GUNMAN & POTMAN; HEADERMEN; HIGH PRESSURE NOZZLEMAN; MINER - TUNNEL, INCLUDING TOP AND BOTTOM MAN ON SHAFT AND RAISE WORK; NIPPER; NOZZLEMAN ON SLICK LINE; SANDBLASTER - POTMAN, ROBOTIC SHOTCRETE PLACER, SEGMENT ERECTOR, TUNNEL MUCK HAULER, STEEL FORM RAISER AND SETTER; TIMBERMAN, RETIMBERMAN (WOOD OR STEEL OR SUBSTITUTE MATERIALS THEREFORE); TUGGER (FOR TUNNEL LABORER WORK); CABLE TENDER; CHUCK TENDER; POWDERMAN - PRIMER HOUSE. (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....\$ 45.41	27.72
TUNNEL AND SHAFT LABORERS: GROUP 4- VIBRATOR OPERATOR, PAVEMENT BREAKER; BULL GANG - MUCKERS, TRACKMEN; CONCRETE CREW - INCLUDES RODDING AND SPREADING, DUMPMEN (ANY METHOD). (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....\$ 44.96	27.72
TUNNEL AND SHAFT LABORERS: GROUP 5- GROUT CREW; REBOUNDMAN; SWAMPER/ BRAKEMAN. (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....\$ 44.42	27.72
TUNNEL AND SHAFT LABORERS: SHOTCRETE SPECIALIST. (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....\$ 46.41	27.72

LAB00270-005 07/01/2023

Rates	Fringes
LABORER: MASON TENDER-BRICK. (MONTEREY AND SAN BENITO COUNTIES).....\$ 36.29	25.55

LAB00270-007 06/26/2023

Rates

Fringes

LABORER (CONSTRUCTION CRAFT LABORERS) GROUP 1-F-
WIRE WINDING MACHINE IN CONNECTION WITH GUNITING OR
SHOT CRETE. FOOTNOTES: LABORERS WORKING OFF OR WITH
OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS
SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE
WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ
COUNTIES).....\$ 36.08

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: CONSTRUCTION
SPECIALIST GROUP- ASPHALT IRONER AND RAKER;
CHAINSAW; LASER BEAM IN CONNECTION WITH LABORERS'
WORK; CAST-IN- PLACE MANHOLE FORM SETTER; PRESSURE
PIPELAYER; DAVIS TRENCHER - 300 OR SIMILAR TYPE
(AND ALL SMALL TRENCHERS); BLASTER; DIAMOND
DRILLER; MULTIPLE UNIT DRILL; HYDRAULIC DRILL.
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED

HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ
COUNTIES).....\$ 36.20

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-
ASPHALT SPREADER BOXES (ALL TYPES); BARKO, WACKER
AND SIMILAR TYPE TAMPERS; BUGGYMOBILE; CAULKER,
BANDER, PIPEWRAPPER, CONDUIT LAYER, PLASTIC
PIPELAYER; CERTIFIED HAZARDOUS WASTE WORKER
INCLUDING LEADE ABATEMENT; COMPACTORS OF ALL TYPES;
CONCRETE AND MAGNESITE MIXER, 1/2 YD. AND UNDER;
CONCRETE PAN WORK; CONCRETE SANDER; CONCRETE SAW;
CRIBBER AND/OR SHORING; CUT GRANITE CURB SETTER;
DRI-PAK-IT MACHINE; FALLER, LOGLOADER AND BUCKER;
FORM RAISER, SLIP FORMS; GREEN CUTTER; HEADERBOARD,
HUBSETTER, ALIGNER, BY ANY METHOD; HIGH PRESSURE
BLOW PIPE (1-1/2" OR OVER, 100 LBS. PRESSURE/OVER);
HYDRO SEEDER AND SIMILAR TYPE; JACKHAMMER OPERATOR;
JACKING OF PIPE OVER 12 INCHES; JACKSON AND SIMILAR
TYPE COMPACTOR; KETTLE TENDER, POT AND WORKER
APPLYING ASPHALT, LAY-KOLD, CREOSOTE, LIME, CAUSTIC
AND SIMILAR TYPE MATERIALS (APPLYING MEANS
APPLYING, DIPPING OR HANDLING OF SUCH MATERIALS);
LAGGING, SHEETING, WHALING, BRACING, TRENCHJACKING,
LAGGING HAMMER; MAGNESITE, EPOXYRESIN, FIBERGLASS,
MASTIC WORKER (WET OR DRY); NO JOINT PIPE AND
STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS;
PAVEMENT BREAKER AND SPADER, INCLUDING TOOL
GRINDER; PERMA CURB; PIPELAYER (INCLUDING GRADE
CHECKING IN CONNECTION WITH PIPELAYING);
PRECAST-MANHOLE SETTER; PRESSURE PIPE TESTER; POST
HOLE DIGGER, AIR, GAS AND ELECTRIC; POWER BROOM
SWEEPER; POWER TAMPERS OF ALL TYPES (EXCEPT AS
SHOWN IN GROUP 2); RAM SET GUN AND STUD GUN; RIPRAP
STONEPAVER AND ROCK-SLINGER, INCLUDING PLACING OF
SACKED CONCRETE AND/OR SAND (WET OR DRY) AND
GABIONS AND SIMILAR TYPE; ROTARY SCARIFIER OR
MULTIPLE HEAD CONCRETE CHIPPING SCARIFIER; ROTO AND
DITCH WITCH; ROTOTILLER; SANDBLASTER, POT, GUN,
NOZZLE OPERATORS; SIGNALLING AND RIGGING; TANK
CLEANER; TREE CLIMBER; TURBO BLASTER; VIBRASCREED,
BULL FLOAT IN CONNECTION WITH LABORERS' WORK;
VIBRATOR; HAZARDOUS WASTE WORKER (LEAD REMOVAL);
ASBESTOS AND MOLD REMOVAL WORKER. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B:

SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.50

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-A- JOY DRILL MODEL TWM-2A; GARDNER-DENVER MODEL DH143 AND SIMILAR TYPE DRILLS; TRACK DRILLER; JACK LEG DRILLER; WAGON DRILLER; MECHANICAL DRILLERS, ALL TYPES REGARDLESS OF TYPE OR METHOD OF POWER; MECHANICAL PIPE LAYERS, ALL TYPES REGARDLESS OF TYPE OR METHOD OF POWER; BLASTER AND POWDER; ALL WORK OF LOADING, PLACING AND BLASTING OF ALL POWDER AND EXPLOSIVES OF WHATEVER TYPE REGARDLESS OF METHOD USED FOR SUCH LOADING AND PLACING; HIGH SCALERS (INCLUDING DRILLING OF SAME); TREE TOPPER; BIT GRINDER. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.72

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-C- BURNING AND WELDING IN CONNECTION WITH LABORERS' WORK; SYNTHETIC THERMOPLASTICS AND SIMILAR TYPE

WELDING. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.55

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-E- WORK ON AND/OR IN BELL HOLE FOOTINGS AND SHAFTS THEREOF, AND WORK ON AND IN DEEP FOOTINGS. (A DEEP FOOTING IS A HOLE 15 FEET OR MORE IN DEPTH.) IN THE EVENT THE DEPTH OF THE FOOTING IS UNKNOWN AT THE COMMENCEMENT OF EXCAVATION, AND THE FINAL DEPTH EXCEEDS 15 FEET, THE DEEP FOOTING WAGE RATE WOULD APPLY TO ALL EMPLOYEES FOR EACH AND EVERY DAY WORKED ON OR IN THE EXCAVATION OF THE FOOTING FROM THE DATE OF INCEPTION. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY

COVER HAS BEEN PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....	\$ 36.05	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 2- ASPHALT SHOVELER; CEMENT DUMPER AND HANDLING DRY CEMENT OR GYPSUM; CHOKE-SETTER AND RIGGER (CLEARING WORK); CONCRETE BUCKET DUMPER AND CHUTE; CONCRETE CHIPPING AND GRINDING; CONCRETE LABORER (WET OR DRY); DRILLER TENDER, CHUCK TENDER, NIPPER; GUINEA CHASER (STAKE), GROUT CREW; HIGH PRESSURE NOZZLE, ADDUCTOR; HYDRAULIC MONITOR (OVER 100 LBS. PRESSURE); LOADING AND UNLOADING, CARRYING AND HAULING OF ALL RODS AND MATERIALS FOR USE IN REINFORCING CONCRETE CONSTRUCTION; PITTSBURGH CHIPPER AND SIMILAR TYPE BRUSH SHREDDERS; SLOPER; SINGLE FOOT, HAND-HELD, PNEUMATIC TAMPER; ALL PNEUMATIC, AIR, GAS AND ELECTRIC TOOLS NOT LISTED IN GROUPS 1 THROUGH 1-F; JACKING OF PIPE - UNDER 12 INCHES. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....		
	\$ 35.35	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 3- CONSTRUCTION LABORERS, INCLUDING BRIDGE AND GENERAL LABORER; DUMP, LOAD SPOTTER; FLAG PERSON; FIRE WATCHER; FENCE ERECTOR; GUARDRAIL ERECTOR; GARDENER, HORTICULTURAL AND LANDSCAPE LABORER; JETTING; LIMBER, BRUSH LOADER AND PILER; PAVEMENT MARKER (BUTTON SETTER); MAINTENANCE, REPAIR TRACK AND ROAD BEDS; STREETCAR AND RAILROAD CONSTRUCTION TRACK LABORER; TEMPORARY AIR AND WATER LINES, VICTAULIC OR SIMILAR; TOOL ROOM ATTENDANT (JOBSITE ONLY). FOOTNOTES: LABORERS WORKING OFF OR WITH OR		

FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ
COUNTIES).....\$ 35.25 27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 4-
FINAL CLEAN-UP WORK OF DEBRIS, GROUNDS AND BUILDING
INCLUDING BUT NOT LIMITED TO: STREET CLEANER;
CLEANING AND WASHING WINDOWS; BRICK CLEANER
(JOBSITE ONLY); MATERIAL CLEANER (JOBSITE ONLY).
THE CLASSIFICATION ""MATERIAL CLEANER"" IS TO BE
UTILIZED UNDER THE FOLLOWING CONDITIONS: A: AT
DEMOLITION SITE FOR THE SALVAGE OF THE MATERIAL.
B: AT THE CONCLUSION OF A JOB WHERE THE MATERIAL IS
TO BE SALVAGED AND STOCKED TO BE REUSED ON ANOTHER
JOB. C: FOR THE CLEANING OF SALVAGE MATERIAL AT
THE JOBSITE OR TEMPORARY JOBSITE YARD. THE
MATERIAL CLEANER CLASSIFICATION SHOULD NOT BE USED
IN THE PERFORMANCE OF ""FORM STRIPPING, CLEANING
AND OILING AND MOVING TO THE NEXT POINT OF
ERECTION"". FOOTNOTES: LABORERS WORKING OFF OR
WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS,
BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE
APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS
SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE
RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO
HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN
SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE
RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL
RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00
PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR

ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 28.94 27.30

LABORER, GUNITE: GROUP 1- STRUCTURAL NOZZLEMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 36.46 27.30

LABORER, GUNITE: GROUP 2- NOZZLEMAN, GUNMAN, POTMAN, GROUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.96 27.30

LABORER, GUNITE: GROUP 3- REBOUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.37 27.30

LABORER, GUNITE: GROUP 4- GUINTE LABORER. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.25 27.30

LABORER, WRECKING: GROUP 1- SKILLED WRECKER (REMOVING AND SALVAGING OF SASH, WINDOWS, AND MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.50 27.30

LABORER, WRECKING: GROUP 2- SEMI-SKILLED WRECKER (SALVAGING OF OTHER BUILDING MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.35 27.30

LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (1) New Construction. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MONTEREY,

SAN BENITO, AND SANTA CRUZ COUNTIES).....\$ 35.25	27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE	
LABORERS - (2) Establishment Warranty Period.	
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM	
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL	
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE	
RATE. (MONTEREY, SAN BENITO, AND SANTA CRUZ	
COUNTIES).....\$ 28.94	27.30

LABO0270-010 06/26/2023		
	Rates	Fringes
LABORER (CONSTRUCTION CRAFT LABORERS) GROUP 1-F- WIRE WINDING MACHINE IN CONNECTION WITH GUNITING OR SHOT CRETE. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SANTA CLARA COUNTY).....\$ 37.08		27.30
LABORER, CONSTRUCTION CRAFT LABORERS: CONSTRUCTION SPECIALIST GROUP- ASPHALT IRONER AND RAKER; CHAINSAW; LASER BEAM IN CONNECTION WITH LABORERS' WORK; CAST-IN- PLACE MANHOLE FORM SETTER; PRESSURE PIPELAYER; DAVIS TRENCHER - 300 OR SIMILAR TYPE (AND ALL SMALL TRENCHERS); BLASTER; DIAMOND DRILLER; MULTIPLE UNIT DRILL; HYDRAULIC DRILL. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE		

DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (SANTA CLARA COUNTY).....\$ 37.20

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-
ASPHALT SPREADER BOXES (ALL TYPES); BARKO, WACKER
AND SIMILAR TYPE TAMPERS; BUGGYMOBILE; CAULKER,
BANDER, PIPEWRAPPER, CONDUIT LAYER, PLASTIC
PIPELAYER; CERTIFIED HAZARDOUS WASTE WORKER
INCLUDING LEADE ABATEMENT; COMPACTORS OF ALL TYPES;
CONCRETE AND MAGNESITE MIXER, 1/2 YD. AND UNDER;
CONCRETE PAN WORK; CONCRETE SANDER; CONCRETE SAW;
CRIBBER AND/OR SHORING; CUT GRANITE CURB SETTER;
DRI-PAK-IT MACHINE; FALLER, LOGLOADER AND BUCKER;
FORM RAISER, SLIP FORMS; GREEN CUTTER; HEADERBOARD,
HUBSETTER, ALIGNER, BY ANY METHOD; HIGH PRESSURE
BLOW PIPE (1-1/2" OR OVER, 100 LBS. PRESSURE/OVER);
HYDRO SEEDER AND SIMILAR TYPE; JACKHAMMER OPERATOR;
JACKING OF PIPE OVER 12 INCHES; JACKSON AND SIMILAR
TYPE COMPACTOR; KETTLE TENDER, POT AND WORKER
APPLYING ASPHALT, LAY-KOLD, CREOSOTE, LIME, CAUSTIC
AND SIMILAR TYPE MATERIALS (APPLYING MEANS
APPLYING, DIPPING OR HANDLING OF SUCH MATERIALS);
LAGGING, SHEETING, WHALING, BRACING, TRENCHJACKING,
LAGGING HAMMER; MAGNESITE, EPOXYRESIN, FIBERGLASS,
MASTIC WORKER (WET OR DRY); NO JOINT PIPE AND
STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS;
PAVEMENT BREAKER AND SPADER, INCLUDING TOOL
GRINDER; PERMA CURB; PIPELAYER (INCLUDING GRADE
CHECKING IN CONNECTION WITH PIPELAYING);
PRECAST-MANHOLE SETTER; PRESSURE PIPE TESTER; POST
HOLE DIGGER, AIR, GAS AND ELECTRIC; POWER BROOM
SWEEPER; POWER TAMPERS OF ALL TYPES (EXCEPT AS
SHOWN IN GROUP 2); RAM SET GUN AND STUD GUN; RIPRAP
STONEPAVER AND ROCK-SLINGER, INCLUDING PLACING OF
SACKED CONCRETE AND/OR SAND (WET OR DRY) AND
GABIONS AND SIMILAR TYPE; ROTARY SCARIFIER OR
MULTIPLE HEAD CONCRETE CHIPPING SCARIFIER; ROTO AND
DITCH WITCH; ROTOTILLER; SANDBLASTER, POT, GUN,
NOZZLE OPERATORS; SIGNALLING AND RIGGING; TANK
CLEANER; TREE CLIMBER; TURBO BLASTER; VIBRASCREED,

BULL FLOAT IN CONNECTION WITH LABORERS' WORK;
VIBRATOR; HAZARDOUS WASTE WORKER (LEAD REMOVAL);
ASBESTOS AND MOLD REMOVAL WORKER. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B:
SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE
GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY
WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW
SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK
INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND
ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE
\$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (SANTA CLARA COUNTY).....\$ 36.50

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-A-
JOY DRILL MODEL TWM-2A; GARDNER-DENVER MODEL DH143
AND SIMILAR TYPE DRILLS; TRACK DRILLER; JACK LEG
DRILLER; WAGON DRILLER; MECHANICAL DRILLERS, ALL
TYPES REGARDLESS OF TYPE OR METHOD OF POWER;
MECHANICAL PIPE LAYERS, ALL TYPES REGARDLESS OF
TYPE OR METHOD OF POWER; BLASTER AND POWDER; ALL
WORK OF LOADING, PLACING AND BLASTING OF ALL POWDER
AND EXPLOSIVES OF WHATEVER TYPE REGARDLESS OF
METHOD USED FOR SUCH LOADING AND PLACING; HIGH
SCALERS (INCLUDING DRILLING OF SAME); TREE TOPPER;
BIT GRINDER. GROUP 1-B: SEWER CLEANERS SHALL
RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES.
""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR
COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER
SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE,
LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE
SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE
GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND
REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES
PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25
PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK
PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY

COVER HAS BEEN PLACED. (SANTA CLARA COUNTY).....\$ 36.72

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-C-
BURNING AND WELDING IN CONNECTION WITH LABORERS'
WORK; SYNTHETIC THERMOPLASTICS AND SIMILAR TYPE
WELDING. FOOTNOTES: LABORERS WORKING OFF OR WITH
OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS
SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE
WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (SANTA CLARA COUNTY).....\$ 36.55

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-E-
WORK ON AND/OR IN BELL HOLE FOOTINGS AND SHAFTS
THEREOF, AND WORK ON AND IN DEEP FOOTINGS. (A DEEP
FOOTING IS A HOLE 15 FEET OR MORE IN DEPTH.) IN
THE EVENT THE DEPTH OF THE FOOTING IS UNKNOWN AT
THE COMMENCEMENT OF EXCAVATION, AND THE FINAL DEPTH
EXCEEDS 15 FEET, THE DEEP FOOTING WAGE RATE WOULD
APPLY TO ALL EMPLOYEES FOR EACH AND EVERY DAY
WORKED ON OR IN THE EXCAVATION OF THE FOOTING FROM
THE DATE OF INCEPTION. FOOTNOTES: LABORERS WORKING
OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING
SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE
THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER
CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1
WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO
HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN
SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE
RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL
RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00
PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL

NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (SANTA CLARA COUNTY).....\$ 37.05

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 2-
ASPHALT SHOVELER; CEMENT DUMPER AND HANDLING DRY
CEMENT OR GYPSUM; CHOKE-SETTER AND RIGGER (CLEARING
WORK); CONCRETE BUCKET DUMPER AND CHUTE; CONCRETE
CHIPPING AND GRINDING; CONCRETE LABORER (WET OR
DRY); DRILLER TENDER, CHUCK TENDER, NIPPER; GUINEA
CHASER (STAKE), GROUT CREW; HIGH PRESSURE NOZZLE,
ADDUCTOR; HYDRAULIC MONITOR (OVER 100 LBS.
PRESSURE); LOADING AND UNLOADING, CARRYING AND
HAULING OF ALL RODS AND MATERIALS FOR USE IN
REINFORCING CONCRETE CONSTRUCTION; PITTSBURGH
CHIPPER AND SIMILAR TYPE BRUSH SHREDDERS; SLOPER;
SINGLE FOOT, HAND-HELD, PNEUMATIC TAMPER; ALL
PNEUMATIC, AIR, GAS AND ELECTRIC TOOLS NOT LISTED
IN GROUPS 1 THROUGH 1-F; JACKING OF PIPE - UNDER 12
INCHES. FOOTNOTES: LABORERS WORKING OFF OR WITH
OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS
SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE
WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (SANTA CLARA COUNTY).....\$ 36.35

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 3-
CONSTRUCTION LABORERS, INCLUDING BRIDGE AND GENERAL
LABORER; DUMP, LOAD SPOTTER; FLAG PERSON; FIRE
WATCHER; FENCE ERECTOR; GUARDRAIL ERECTOR;
GARDENER, HORTICULTURAL AND LANDSCAPE LABORER;
JETTING; LIMBER, BRUSH LOADER AND PILER; PAVEMENT
MARKER (BUTTON SETTER); MAINTENANCE, REPAIR TRACK
AND ROAD BEDS; STREETCAR AND RAILROAD CONSTRUCTION
TRACK LABORER; TEMPORARY AIR AND WATER LINES,
VICTAULIC OR SIMILAR; TOOL ROOM ATTENDANT (JOBSITE

ONLY). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SANTA CLARA COUNTY).....\$ 36.25

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 4-FINAL CLEAN-UP WORK OF DEBRIS, GROUNDS AND BUILDING INCLUDING BUT NOT LIMITED TO: STREET CLEANER; CLEANING AND WASHING WINDOWS; BRICK CLEANER (JOBSITE ONLY); MATERIAL CLEANER (JOBSITE ONLY). THE CLASSIFICATION ""MATERIAL CLEANER"" IS TO BE UTILIZED UNDER THE FOLLOWING CONDITIONS: A: AT DEMOLITION SITE FOR THE SALVAGE OF THE MATERIAL. B: AT THE CONCLUSION OF A JOB WHERE THE MATERIAL IS TO BE SALVAGED AND STOCKED TO BE REUSED ON ANOTHER JOB. C: FOR THE CLEANING OF SALVAGE MATERIAL AT THE JOBSITE OR TEMPORARY JOBSITE YARD. THE MATERIAL CLEANER CLASSIFICATION SHOULD NOT BE USED IN THE PERFORMANCE OF ""FORM STRIPPING, CLEANING AND OILING AND MOVING TO THE NEXT POINT OF ERECTION"". FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR

ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (SANTA CLARA COUNTY).....\$ 29.94 27.30

LABORER, GUNITE: GROUP 1- STRUCTURAL NOZZLEMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SANTA CLARA COUNTY).....\$ 37.46 27.30

LABORER, GUNITE: GROUP 2- NOZZLEMAN, GUNMAN, POTMAN, GROUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SANTA CLARA COUNTY).....\$ 36.96 27.30

LABORER, GUNITE: GROUP 3- REBOUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SANTA CLARA COUNTY).....\$ 36.37 27.30

LABORER, GUNITE: GROUP 4- GUINTE LABORER. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SANTA CLARA COUNTY).....\$ 36.25 27.30

LABORER, WRECKING: GROUP 1- SKILLED WRECKER (REMOVING AND SALVAGING OF SASH, WINDOWS, AND MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SANTA CLARA COUNTY).....\$ 36.50 27.30

LABORER, WRECKING: GROUP 2- SEMI-SKILLED WRECKER (SALVAGING OF OTHER BUILDING MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SANTA CLARA COUNTY).....\$ 36.35 27.30

LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (1) New Construction. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (SANTA CLARA COUNTY).....\$ 36.25 27.30

LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (2) Establishment Warranty Period. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE

RATE. (SANTA CLARA COUNTY).....	\$ 29.94	27.30

LAB00270-011 07/01/2023		
	Rates	Fringes
LABORER, PLASTER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (MONTEREY, SAN BENITO, SANTA CRUZ, SANTA CLARA COUNTIES)	\$ 40.68	29.68

LAB00294-001 07/01/2023		
	Rates	Fringes
LABORER, BRICK: MASON TENDER-BRICK. (FRESNO, KINGS AND MADERA COUNTIES).....	\$ 36.29	25.55

LAB00294-002 07/01/2023		
	Rates	Fringes
LABORER, TRAFFIC CONTROL/LANE CLOSURE: ESCORT DRIVER, FLAG PERSON (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 36.26	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON I- LAYOUT OF TRAFFIC CONTROL, CRASH CUSHIONS, CONSTRUCTION AREA AND ROADSIDE SIGNAGE. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 36.56	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON II- INSTALLATION AND REMOVAL OF TEMPORARY/PERMANENT SIGNS, MARKERS, DELINEATORS AND CRASH CUSHIONS. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 34.06	27.30

LAB00294-005 06/26/2023		
	Rates	Fringes
TUNNEL AND SHAFT LABORERS: GROUP 1- DIAMOND DRILLER; GROUND MEN; GUNITE AND SHOTCRETE NOZZLEMEN. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 45.89	27.72
TUNNEL AND SHAFT LABORERS: GROUP 2- RODMEN; SHAFT WORK & RAISE (BELOW ACTUAL OR EXCAVATED GROUND LEVEL). (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 45.66	27.72
TUNNEL AND SHAFT LABORERS: GROUP 3- BIT GRINDER; BLASTER, DRILLER, POWDERMEN, HEADING; CHERRY PICKERMEN - WHERE CAR IS LIFTED; CONCRETE FINISHER IN TUNNEL; CONCRETE SCREEDMAN; GROUT PUMPMAN AND POTMAN; GUNITE & SHOTCRETE GUNMAN & POTMAN; HEADERMEN; HIGH PRESSURE NOZZLEMAN; MINER - TUNNEL, INCLUDING TOP AND BOTTOM MAN ON SHAFT AND RAISE WORK; NIPPER; NOZZLEMAN ON SLICK LINE; SANDBLASTER - POTMAN, ROBOTIC SHOTCRETE PLACER, SEGMENT		

ERECTOR, TUNNEL MUCK HAULER, STEEL FORM RAISER AND SETTER; TIMBERMAN, RETIMBERMAN (WOOD OR STEEL OR SUBSTITUTE MATERIALS THEREFORE); TUGGER (FOR TUNNEL LABORER WORK); CABLE TENDER; CHUCK TENDER; POWDERMAN - PRIMER HOUSE. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 45.41	27.72
TUNNEL AND SHAFT LABORERS: GROUP 4- VIBRATOR OPERATOR, PAVEMENT BREAKER; BULL GANG - MUCKERS, TRACKMEN; CONCRETE CREW - INCLUDES RODDING AND SPREADING, DUMPMEN (ANY METHOD). (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 44.96	27.72
TUNNEL AND SHAFT LABORERS: GROUP 5- GROUT CREW; REBOUNDMAN; SWAMPER/ BRAKEMAN. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 44.42	27.72
TUNNEL AND SHAFT LABORERS: SHOTCRETE SPECIALIST. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 46.41	27.72

LAB00294-008 06/26/2023

Rates

Fringes

LABORER (CONSTRUCTION CRAFT LABORERS) GROUP 1-F- WIRE WINDING MACHINE IN CONNECTION WITH GUNITING OR SHOT CRETE. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 36.08	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: CONSTRUCTION SPECIALIST GROUP- ASPHALT IRONER AND RAKER; CHAINSAW; LASER BEAM IN CONNECTION WITH LABORERS' WORK; CAST-IN- PLACE MANHOLE FORM SETTER; PRESSURE PIPELAYER; DAVIS TRENCHER - 300 OR SIMILAR TYPE (AND ALL SMALL TRENCHERS); BLASTER; DIAMOND DRILLER; MULTIPLE UNIT DRILL; HYDRAULIC DRILL.		

FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (FRESNO, KINGS, AND MADERA COUNTIES).....\$ 36.20

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-
ASPHALT SPREADER BOXES (ALL TYPES); BARKO, WACKER
AND SIMILAR TYPE TAMPERS; BUGGYMOBILE; CAULKER,
BANDER, PIPEWRAPPER, CONDUIT LAYER, PLASTIC
PIPELAYER; CERTIFIED HAZARDOUS WASTE WORKER
INCLUDING LEADE ABATEMENT; COMPACTORS OF ALL TYPES;
CONCRETE AND MAGNESITE MIXER, 1/2 YD. AND UNDER;
CONCRETE PAN WORK; CONCRETE SANDER; CONCRETE SAW;
CRIBBER AND/OR SHORING; CUT GRANITE CURB SETTER;
DRI-PAK-IT MACHINE; FALLER, LOGLOADER AND BUCKER;
FORM RAISER, SLIP FORMS; GREEN CUTTER; HEADERBOARD,
HUBSETTER, ALIGNER, BY ANY METHOD; HIGH PRESSURE
BLOW PIPE (1-1/2"" OR OVER, 100 LBS. PRESSURE/OVER);
HYDRO SEEDER AND SIMILAR TYPE; JACKHAMMER OPERATOR;
JACKING OF PIPE OVER 12 INCHES; JACKSON AND SIMILAR
TYPE COMPACTOR; KETTLE TENDER, POT AND WORKER
APPLYING ASPHALT, LAY-KOLD, CREOSOTE, LIME, CAUSTIC
AND SIMILAR TYPE MATERIALS (APPLYING MEANS
APPLYING, DIPPING OR HANDLING OF SUCH MATERIALS);
LAGGING, SHEETING, WHALING, BRACING, TRENCHJACKING,
LAGGING HAMMER; MAGNESITE, EPOXYRESIN, FIBERGLASS,
MASTIC WORKER (WET OR DRY); NO JOINT PIPE AND
STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS;
PAVEMENT BREAKER AND SPADER, INCLUDING TOOL
GRINDER; PERMA CURB; PIPELAYER (INCLUDING GRADE
CHECKING IN CONNECTION WITH PIPELAYING);
PRECAST-MANHOLE SETTER; PRESSURE PIPE TESTER; POST
HOLE DIGGER, AIR, GAS AND ELECTRIC; POWER BROOM
SWEEPER; POWER TAMPERS OF ALL TYPES (EXCEPT AS

SHOWN IN GROUP 2); RAM SET GUN AND STUD GUN; RIPRAP
STONEPAVER AND ROCK-SLINGER, INCLUDING PLACING OF
SACKED CONCRETE AND/OR SAND (WET OR DRY) AND
GABIONS AND SIMILAR TYPE; ROTARY SCARIFIER OR
MULTIPLE HEAD CONCRETE CHIPPING SCARIFIER; ROTO AND
DITCH WITCH; ROTOTILLER; SANDBLASTER, POT, GUN,
NOZZLE OPERATORS; SIGNALLING AND RIGGING; TANK
CLEANER; TREE CLIMBER; TURBO BLASTER; VIBRASCREED,
BULL FLOAT IN CONNECTION WITH LABORERS' WORK;
VIBRATOR; HAZARDOUS WASTE WORKER (LEAD REMOVAL);
ASBESTOS AND MOLD REMOVAL WORKER. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B:
SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE
GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY
WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW
SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK
INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND
ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE
\$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (FRESNO, KINGS, AND MADERA
COUNTIES).....\$ 35.50 27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-A-
JOY DRILL MODEL TWM-2A; GARDNER-DENVER MODEL DH143
AND SIMILAR TYPE DRILLS; TRACK DRILLER; JACK LEG
DRILLER; WAGON DRILLER; MECHANICAL DRILLERS, ALL
TYPES REGARDLESS OF TYPE OR METHOD OF POWER;
MECHANICAL PIPE LAYERS, ALL TYPES REGARDLESS OF
TYPE OR METHOD OF POWER; BLASTER AND POWDER; ALL
WORK OF LOADING, PLACING AND BLASTING OF ALL POWDER
AND EXPLOSIVES OF WHATEVER TYPE REGARDLESS OF
METHOD USED FOR SUCH LOADING AND PLACING; HIGH
SCALERS (INCLUDING DRILLING OF SAME); TREE TOPPER;
BIT GRINDER. GROUP 1-B: SEWER CLEANERS SHALL
RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES.
""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR
COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER
SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE,
LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE
SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE

GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 35.72	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-C- BURNING AND WELDING IN CONNECTION WITH LABORERS' WORK; SYNTHETIC THERMOPLASTICS AND SIMILAR TYPE WELDING. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (FRESNO, KINGS, AND MADERA COUNTIES).....		
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-E- WORK ON AND/OR IN BELL HOLE FOOTINGS AND SHAFTS THEREOF, AND WORK ON AND IN DEEP FOOTINGS. (A DEEP FOOTING IS A HOLE 15 FEET OR MORE IN DEPTH.) IN THE EVENT THE DEPTH OF THE FOOTING IS UNKNOWN AT THE COMMENCEMENT OF EXCAVATION, AND THE FINAL DEPTH EXCEEDS 15 FEET, THE DEEP FOOTING WAGE RATE WOULD APPLY TO ALL EMPLOYEES FOR EACH AND EVERY DAY WORKED ON OR IN THE EXCAVATION OF THE FOOTING FROM THE DATE OF INCEPTION. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO	\$ 35.55	27.30

HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (FRESNO, KINGS, AND MADERA COUNTIES).....\$ 36.05

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 2- ASPHALT SHOVELER; CEMENT DUMPER AND HANDLING DRY CEMENT OR GYPSUM; CHOKE-SETTER AND RIGGER (CLEARING WORK); CONCRETE BUCKET DUMPER AND CHUTE; CONCRETE CHIPPING AND GRINDING; CONCRETE LABORER (WET OR DRY); DRILLER TENDER, CHUCK TENDER, NIPPER; GUINEA CHASER (STAKE), GROUT CREW; HIGH PRESSURE NOZZLE, ADDUCTOR; HYDRAULIC MONITOR (OVER 100 LBS. PRESSURE); LOADING AND UNLOADING, CARRYING AND HAULING OF ALL RODS AND MATERIALS FOR USE IN REINFORCING CONCRETE CONSTRUCTION; PITTSBURGH CHIPPER AND SIMILAR TYPE BRUSH SHREDDERS; SLOPER; SINGLE FOOT, HAND-HELD, PNEUMATIC TAMPER; ALL PNEUMATIC, AIR, GAS AND ELECTRIC TOOLS NOT LISTED IN GROUPS 1 THROUGH 1-F; JACKING OF PIPE - UNDER 12 INCHES. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN

APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS
 SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE
 RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO
 HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN
 SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE
 RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL
 RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00
 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
 MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
 EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
 RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
 ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
 SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
 NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
 LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
 WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
 COVER HAS BEEN PLACED. (FRESNO, KINGS, AND MADERA
 COUNTIES).....\$ 28.94 27.30
 LABORER, GUNITE: GROUP 1- STRUCTURAL NOZZLEMAN.
 FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
 BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
 RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
 RATE. (FRESNO, KINGS, AND MADERA COUNTIES).....\$ 36.46 27.30
 LABORER, GUNITE: GROUP 2- NOZZLEMAN, GUNMAN,
 POTMAN, GROUNDMAN. FOOTNOTES: LABORERS WORKING
 OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING
 SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE
 THE APPLICABLE WAGE RATE. (FRESNO, KINGS, AND
 MADERA COUNTIES).....\$ 35.96 27.30
 LABORER, GUNITE: GROUP 3- REBOUNDMAN. FOOTNOTES:
 LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
 SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
 HOUR ABOVE THE APPLICABLE WAGE RATE. (FRESNO,
 KINGS, AND MADERA COUNTIES).....\$ 35.37 27.30
 LABORER, GUNITE: GROUP 4- GUINTE LABORER.
 FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
 BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
 RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
 RATE. (FRESNO, KINGS, AND MADERA COUNTIES).....\$ 35.25 27.30
 LABORER, WRECKING: GROUP 1- SKILLED WRECKER
 (REMOVING AND SALVAGING OF SASH, WINDOWS, AND
 MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR
 WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS,
 BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE
 APPLICABLE WAGE RATE. (FRESNO, KINGS, AND MADERA
 COUNTIES).....\$ 35.50 27.30
 LABORER, WRECKING: GROUP 2- SEMI-SKILLED WRECKER
 (SALVAGING OF OTHER BUILDING MATERIALS).
 FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM

BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 35.35	27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (1) New Construction. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (FRESNO, KINGS, AND MADERA COUNTIES).....		
	\$ 35.25	27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (2) Establishment Warranty Period. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (FRESNO, KINGS, AND MADERA COUNTIES).....		
	\$ 28.94	27.30

LAB00294-010 07/01/2023

	Rates	Fringes
PLASTERER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS & TUOLUMNE COUNTIES).....		
	\$ 39.77	28.54

LAB00294-011 07/01/2023

	Rates	Fringes
LABORER, PLASTER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (FRESNO, KINGS, AND MADERA COUNTIES).....		
	\$ 39.77	28.54

LAB00304-002 07/01/2023

	Rates	Fringes
LABORER, TRAFFIC CONTROL/LANE CLOSURE: ESCORT DRIVER, FLAG PERSON (ALAMEDA COUNTY).....		
	\$ 37.26	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON I- LAYOUT OF TRAFFIC CONTROL, CRASH CUSHIONS, CONSTRUCTION AREA AND ROADSIDE SIGNAGE. (ALAMEDA COUNTY).....		
	\$ 37.56	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON II- INSTALLATION AND REMOVAL OF TEMPORARY/PERMANENT SIGNS, MARKERS, DELINEATORS AND CRASH CUSHIONS. (ALAMEDA COUNTY).....		
	\$ 35.06	27.30

LAB00304-003 06/26/2023

	Rates	Fringes
TUNNEL AND SHAFT LABORERS: GROUP 1- DIAMOND		

DRILLER; GROUND MEN; GUNITE AND SHOTCRETE NOZZLEMEN (ALAMEDA COUNTY).....	\$ 45.89	27.72
TUNNEL AND SHAFT LABORERS: GROUP 2- RODMEN; SHAFT WORK & RAISE (BELOW ACTUAL OR EXCAVATED GROUND LEVEL) (ALAMEDA COUNTY).....	\$ 45.66	27.72
TUNNEL AND SHAFT LABORERS: GROUP 3- BIT GRINDER; BLASTER, DRILLER, POWDERMEN, HEADING; CHERRY PICKERMEN - WHERE CAR IS LIFTED; CONCRETE FINISHER IN TUNNEL; CONCRETE SCREEDMAN; GROUT PUMPMAN AND POTMAN; GUNITE & SHOTCRETE GUNMAN & POTMAN; HEADERMEN; HIGH PRESSURE NOZZLEMAN; MINER - TUNNEL, INCLUDING TOP AND BOTTOM MAN ON SHAFT AND RAISE WORK; NIPPER; NOZZLEMAN ON SLICK LINE; SANDBLASTER - POTMAN, ROBOTIC SHOTCRETE PLACER, SEGMENT ERECTOR, TUNNEL MUCK HAULER, STEEL FORM RAISER AND SETTER; TIMBERMAN, RETIMBERMAN (WOOD OR STEEL OR SUBSTITUTE MATERIALS THEREFORE); TUGGER (FOR TUNNEL LABORER WORK); CABLE TENDER; CHUCK TENDER; POWDERMAN - PRIMER HOUSE (ALAMEDA COUNTY).....	\$ 45.41	27.72
TUNNEL AND SHAFT LABORERS: GROUP 4- VIBRATOR OPERATOR, PAVEMENT BREAKER; BULL GANG - MUCKERS, TRACKMEN; CONCRETE CREW - INCLUDES RODDING AND SPREADING, DUMP MEN (ANY METHOD) (ALAMEDA COUNTY)....	\$ 44.96	27.72
TUNNEL AND SHAFT LABORERS: GROUP 5- GROUT CREW; REBOUNDMAN; SWAMPER/ BRAKEMAN (ALAMEDA COUNTY).....	\$ 44.42	27.72
TUNNEL AND SHAFT LABORERS: SHOTCRETE SPECIALIST (ALAMEDA COUNTY).....	\$ 46.41	27.72

LAB00304-004 06/26/2023

Rates

Fringes

LABORER (CONSTRUCTION CRAFT LABORERS) GROUP 1-F-
WIRE WINDING MACHINE IN CONNECTION WITH GUNITING OR
SHOT CRETE. FOOTNOTES: LABORERS WORKING OFF OR WITH
OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS
SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE
WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO

APPLYING, DIPPING OR HANDLING OF SUCH MATERIALS);
LAGGING, SHEETING, WHALING, BRACING, TRENCHJACKING,
LAGGING HAMMER; MAGNESITE, EPOXYRESIN, FIBERGLASS,
MASTIC WORKER (WET OR DRY); NO JOINT PIPE AND
STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS;
PAVEMENT BREAKER AND SPADER, INCLUDING TOOL
GRINDER; PERMA CURB; PIPELAYER (INCLUDING GRADE
CHECKING IN CONNECTION WITH PIPELAYING);
PRECAST-MANHOLE SETTER; PRESSURE PIPE TESTER; POST
HOLE DIGGER, AIR, GAS AND ELECTRIC; POWER BROOM
SWEEPER; POWER TAMPERS OF ALL TYPES (EXCEPT AS
SHOWN IN GROUP 2); RAM SET GUN AND STUD GUN; RIPRAP
STONEPAVER AND ROCK-SLINGER, INCLUDING PLACING OF
SACKED CONCRETE AND/OR SAND (WET OR DRY) AND
GABIONS AND SIMILAR TYPE; ROTARY SCARIFIER OR
MULTIPLE HEAD CONCRETE CHIPPING SCARIFIER; ROTO AND
DITCH WITCH; ROTOTILLER; SANDBLASTER, POT, GUN,
NOZZLE OPERATORS; SIGNALLING AND RIGGING; TANK
CLEANER; TREE CLIMBER; TURBO BLASTER; VIBRASCREED,
BULL FLOAT IN CONNECTION WITH LABORERS' WORK;
VIBRATOR; HAZARDOUS WASTE WORKER (LEAD REMOVAL);
ASBESTOS AND MOLD REMOVAL WORKER. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B:
SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE
GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY
WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW
SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK
INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND
ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE
\$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (ALAMEDA COUNTY).....\$ 36.50
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-A-
JOY DRILL MODEL TWM-2A; GARDNER-DENVER MODEL DH143
AND SIMILAR TYPE DRILLS; TRACK DRILLER; JACK LEG
DRILLER; WAGON DRILLER; MECHANICAL DRILLERS, ALL
TYPES REGARDLESS OF TYPE OR METHOD OF POWER;
MECHANICAL PIPE LAYERS, ALL TYPES REGARDLESS OF
TYPE OR METHOD OF POWER; BLASTER AND POWDER; ALL
WORK OF LOADING, PLACING AND BLASTING OF ALL POWDER

27.30

AND EXPLOSIVES OF WHATEVER TYPE REGARDLESS OF METHOD USED FOR SUCH LOADING AND PLACING; HIGH SCALERS (INCLUDING DRILLING OF SAME); TREE TOPPER; BIT GRINDER. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (ALAMEDA COUNTY).....\$ 36.72 27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-C- BURNING AND WELDING IN CONNECTION WITH LABORERS' WORK; SYNTHETIC THERMOPLASTICS AND SIMILAR TYPE WELDING. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (ALAMEDA COUNTY).....\$ 36.55 27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-E- WORK ON AND/OR IN BELL HOLE FOOTINGS AND SHAFTS THEREOF, AND WORK ON AND IN DEEP FOOTINGS. (A DEEP FOOTING IS A HOLE 15 FEET OR MORE IN DEPTH.) IN THE EVENT THE DEPTH OF THE FOOTING IS UNKNOWN AT THE COMMENCEMENT OF EXCAVATION, AND THE FINAL DEPTH

EXCEEDS 15 FEET, THE DEEP FOOTING WAGE RATE WOULD APPLY TO ALL EMPLOYEES FOR EACH AND EVERY DAY WORKED ON OR IN THE EXCAVATION OF THE FOOTING FROM THE DATE OF INCEPTION. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (ALAMEDA COUNTY).....\$ 37.05

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 2- ASPHALT SHOVELER; CEMENT DUMPER AND HANDLING DRY CEMENT OR GYPSUM; CHOKE-SETTER AND RIGGER (CLEARING WORK); CONCRETE BUCKET DUMPER AND CHUTE; CONCRETE CHIPPING AND GRINDING; CONCRETE LABORER (WET OR DRY); DRILLER TENDER, CHUCK TENDER, NIPPER; GUINEA CHASER (STAKE), GROUT CREW; HIGH PRESSURE NOZZLE, ADDUCTOR; HYDRAULIC MONITOR (OVER 100 LBS. PRESSURE); LOADING AND UNLOADING, CARRYING AND HAULING OF ALL RODS AND MATERIALS FOR USE IN REINFORCING CONCRETE CONSTRUCTION; PITTSBURGH CHIPPER AND SIMILAR TYPE BRUSH SHREDDERS; SLOPER; SINGLE FOOT, HAND-HELD, PNEUMATIC TAMPER; ALL PNEUMATIC, AIR, GAS AND ELECTRIC TOOLS NOT LISTED IN GROUPS 1 THROUGH 1-F; JACKING OF PIPE - UNDER 12 INCHES. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR

TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (ALAMEDA COUNTY).....\$ 36.35

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 3-
CONSTRUCTION LABORERS, INCLUDING BRIDGE AND GENERAL
LABORER; DUMP, LOAD SPOTTER; FLAG PERSON; FIRE
WATCHER; FENCE ERECTOR; GUARDRAIL ERECTOR;
GARDENER, HORTICULTURAL AND LANDSCAPE LABORER;
JETTING; LIMBER, BRUSH LOADER AND PILER; PAVEMENT
MARKER (BUTTON SETTER); MAINTENANCE, REPAIR TRACK
AND ROAD BEDS; STREETCAR AND RAILROAD CONSTRUCTION
TRACK LABORER; TEMPORARY AIR AND WATER LINES,
VICTAULIC OR SIMILAR; TOOL ROOM ATTENDANT (JOBSITE
ONLY). FOOTNOTES: LABORERS WORKING OFF OR WITH OR
FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (ALAMEDA COUNTY).....

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 4-
FINAL CLEAN-UP WORK OF DEBRIS, GROUNDS AND BUILDING
INCLUDING BUT NOT LIMITED TO: STREET CLEANER;
CLEANING AND WASHING WINDOWS; BRICK CLEANER
(JOBSITE ONLY); MATERIAL CLEANER (JOBSITE ONLY).
THE CLASSIFICATION ""MATERIAL CLEANER"" IS TO BE
UTILIZED UNDER THE FOLLOWING CONDITIONS: A: AT
DEMOLITION SITE FOR THE SALVAGE OF THE MATERIAL.
B: AT THE CONCLUSION OF A JOB WHERE THE MATERIAL IS
TO BE SALVAGED AND STOCKED TO BE REUSED ON ANOTHER

JOB. C: FOR THE CLEANING OF SALVAGE MATERIAL AT THE JOBSITE OR TEMPORARY JOBSITE YARD. THE MATERIAL CLEANER CLASSIFICATION SHOULD NOT BE USED IN THE PERFORMANCE OF ""FORM STRIPPING, CLEANING AND OILING AND MOVING TO THE NEXT POINT OF ERECTION"". FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (ALAMEDA COUNTY).....\$ 29.94 27.30

LABORER, GUNITE: GROUP 1- STRUCTURAL NOZZLEMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (ALAMEDA COUNTY).....\$ 37.46 27.30

LABORER, GUNITE: GROUP 2- NOZZLEMAN, GUNMAN, POTMAN, GROUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (ALAMEDA COUNTY).....\$ 36.96 27.30

LABORER, GUNITE: GROUP 3- REBOUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (ALAMEDA COUNTY).....\$ 36.37 27.30

LABORER, GUNITE: GROUP 4- GUINTE LABORER. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (ALAMEDA COUNTY).....\$ 36.25 27.30

LABORER, WRECKING: GROUP 1- SKILLED WRECKER (REMOVING AND SALVAGING OF SASH, WINDOWS, AND MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS,

BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (ALAMEDA COUNTY).....	\$ 36.50	27.30
LABORER, WRECKING: GROUP 2- SEMI-SKILLED WRECKER (SALVAGING OF OTHER BUILDING MATERIALS).		
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (ALAMEDA COUNTY).....		
	\$ 36.35	27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (1) New Construction. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (ALAMEDA COUNTY).....		
	\$ 36.25	27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (2) Establishment Warranty Period. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (ALAMEDA COUNTY).....		
	\$ 29.94	27.30

LAB00304-005 07/01/2023

Rates

Fringes

BRICK TENDER. FOOTNOTES: WORK ON JOBS WHERE HEAT-PROTECTIVE CLOTHING IS REQUIRED: \$2.00 PER HOUR ADDITIONAL. WORK AT GRINDERS: \$.25 PER HOUR ADDITIONAL. MANHOLE WORK: \$2.00 PER DAY ADDITIONAL. (ALAMEDA COUNTY)	\$ 37.05	27.45
--	----------	-------

LAB00304-008 07/01/2023

Rates

Fringes

PLASTERER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (ALAMEDA AND CONTRA COSTA COUNTIES)	\$ 41.93	30.32
---	----------	-------

LAB00324-002 07/01/2023

Rates

Fringes

LABORER, TRAFFIC CONTROL/LANE CLOSURE: ESCORT DRIVER, FLAG PERSON. (CONTRA COSTA COUNTY).....	\$ 37.26	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON I- LAYOUT OF TRAFFIC CONTROL, CRASH CUSHIONS, CONSTRUCTION AREA AND ROADSIDE SIGNAGE. (CONTRA COSTA COUNTY).....		
	\$ 37.56	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON II- INSTALLATION AND REMOVAL OF TEMPORARY/PERMANENT SIGNS, MARKERS, DELINEATORS AND		

CRASH CUSHIONS. (CONTRA COSTA COUNTY).....\$ 35.06	27.30
--	-------

LAB00324-006 06/26/2023

	Rates	Fringes
TUNNEL AND SHAFT LABORERS: GROUP 1- DIAMOND DRILLER; GROUND MEN; GUNITE AND SHOTCRETE NOZZLEMEN (CONTRA COSTA COUNTY).....\$ 45.89		27.72
TUNNEL AND SHAFT LABORERS: GROUP 2- RODMEN; SHAFT WORK & RAISE (BELOW ACTUAL OR EXCAVATED GROUND LEVEL) (CONTRA COSTA COUNTY).....\$ 45.66		27.72
TUNNEL AND SHAFT LABORERS: GROUP 3- BIT GRINDER; BLASTER, DRILLER, POWDERMEN, HEADING; CHERRY PICKERMEN - WHERE CAR IS LIFTED; CONCRETE FINISHER IN TUNNEL; CONCRETE SCREEDMAN; GROUT PUMPMAN AND POTMAN; GUNITE & SHOTCRETE GUNMAN & POTMAN; HEADERMEN; HIGH PRESSURE NOZZLEMAN; MINER - TUNNEL, INCLUDING TOP AND BOTTOM MAN ON SHAFT AND RAISE WORK; NIPPER; NOZZLEMAN ON SLICK LINE; SANDBLASTER - POTMAN, ROBOTIC SHOTCRETE PLACER, SEGMENT ERECTOR, TUNNEL MUCK HAULER, STEEL FORM RAISER AND SETTER; TIMBERMAN, RETIMBERMAN (WOOD OR STEEL OR SUBSTITUTE MATERIALS THEREFORE); TUGGER (FOR TUNNEL LABORER WORK); CABLE TENDER; CHUCK TENDER; POWDERMAN - PRIMER HOUSE (CONTRA COSTA COUNTY).....\$ 45.41		27.72
TUNNEL AND SHAFT LABORERS: GROUP 4- VIBRATOR OPERATOR, PAVEMENT BREAKER; BULL GANG - MUCKERS, TRACKMEN; CONCRETE CREW - INCLUDES RODDING AND SPREADING, DUMPMEN (ANY METHOD) (CONTRA COSTA COUNTY).....\$ 44.96		27.72
TUNNEL AND SHAFT LABORERS: GROUP 5- GROUT CREW; REBOUNDMAN; SWAMPER/ BRAKEMAN (CONTRA COSTA COUNTY).\$ 44.42		27.72
TUNNEL AND SHAFT LABORERS: SHOTCRETE SPECIALIST (CONTRA COSTA COUNTY).....\$ 46.41		27.72

LAB00324-012 06/26/2023

	Rates	Fringes
LABORER (CONSTRUCTION CRAFT LABORERS) GROUP 1-F- WIRE WINDING MACHINE IN CONNECTION WITH GUNITING OR SHOT CRETE. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER		

MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CONTRA COSTA COUNTY)(CONTRA COSTA COUNTY).....	\$ 37.08	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: CONSTRUCTION SPECIALIST GROUP- ASPHALT IRONER AND RAKER; CHAINSAW; LASER BEAM IN CONNECTION WITH LABORERS' WORK; CAST-IN- PLACE MANHOLE FORM SETTER; PRESSURE PIPELAYER; DAVIS TRENCHER - 300 OR SIMILAR TYPE (AND ALL SMALL TRENCHERS); BLASTER; DIAMOND DRILLER; MULTIPLE UNIT DRILL; HYDRAULIC DRILL. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CONTRA COSTA COUNTY).....		
\$ 37.20	27.30	
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1- ASPHALT SPREADER BOXES (ALL TYPES); BARKO, WACKER AND SIMILAR TYPE TAMPERS; BUGGYMOBILE; CAULKER, BANDER, PIPEWRAPPER, CONDUIT LAYER, PLASTIC PIPELAYER; CERTIFIED HAZARDOUS WASTE WORKER INCLUDING LEADE ABATEMENT; COMPACTORS OF ALL TYPES; CONCRETE AND MAGNESITE MIXER, 1/2 YD. AND UNDER; CONCRETE PAN WORK; CONCRETE SANDER; CONCRETE SAW; CRIBBER AND/OR SHORING; CUT GRANITE CURB SETTER; DRI-PAK-IT MACHINE; FALLER, LOGLOADER AND BUCKER;		

FORM RAISER, SLIP FORMS; GREEN CUTTER; HEADERBOARD, HUBSETTER, ALIGNER, BY ANY METHOD; HIGH PRESSURE BLOW PIPE (1-1/2" OR OVER, 100 LBS. PRESSURE/OVER); HYDRO SEEDER AND SIMILAR TYPE; JACKHAMMER OPERATOR; JACKING OF PIPE OVER 12 INCHES; JACKSON AND SIMILAR TYPE COMPACTOR; KETTLE TENDER, POT AND WORKER APPLYING ASPHALT, LAY-KOLD, CREOSOTE, LIME, CAUSTIC AND SIMILAR TYPE MATERIALS (APPLYING MEANS APPLYING, DIPPING OR HANDLING OF SUCH MATERIALS); LAGGING, SHEETING, WHALING, BRACING, TRENCHJACKING, LAGGING HAMMER; MAGNESITE, EPOXYRESIN, FIBERGLASS, MASTIC WORKER (WET OR DRY); NO JOINT PIPE AND STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS; PAVEMENT BREAKER AND SPADER, INCLUDING TOOL GRINDER; PERMA CURB; PIPELAYER (INCLUDING GRADE CHECKING IN CONNECTION WITH PIPELAYING); PRECAST-MANHOLE SETTER; PRESSURE PIPE TESTER; POST HOLE DIGGER, AIR, GAS AND ELECTRIC; POWER BROOM SWEEPER; POWER TAMPERS OF ALL TYPES (EXCEPT AS SHOWN IN GROUP 2); RAM SET GUN AND STUD GUN; RIPRAP STONEPAVER AND ROCK-SLINGER, INCLUDING PLACING OF SACKED CONCRETE AND/OR SAND (WET OR DRY) AND GABIONS AND SIMILAR TYPE; ROTARY SCARIFIER OR MULTIPLE HEAD CONCRETE CHIPPING SCARIFIER; ROTO AND DITCH WITCH; ROTOTILLER; SANDBLASTER, POT, GUN, NOZZLE OPERATORS; SIGNALLING AND RIGGING; TANK CLEANER; TREE CLIMBER; TURBO BLASTER; VIBRASCREED, BULL FLOAT IN CONNECTION WITH LABORERS' WORK; VIBRATOR; HAZARDOUS WASTE WORKER (LEAD REMOVAL); ASBESTOS AND MOLD REMOVAL WORKER. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CONTRA COSTA COUNTY).....\$ 36.50

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-A-
JOY DRILL MODEL TWM-2A; GARDNER-DENVER MODEL DH143
AND SIMILAR TYPE DRILLS; TRACK DRILLER; JACK LEG
DRILLER; WAGON DRILLER; MECHANICAL DRILLERS, ALL
TYPES REGARDLESS OF TYPE OR METHOD OF POWER;
MECHANICAL PIPE LAYERS, ALL TYPES REGARDLESS OF
TYPE OR METHOD OF POWER; BLASTER AND POWDER; ALL
WORK OF LOADING, PLACING AND BLASTING OF ALL POWDER
AND EXPLOSIVES OF WHATEVER TYPE REGARDLESS OF
METHOD USED FOR SUCH LOADING AND PLACING; HIGH
SCALERS (INCLUDING DRILLING OF SAME); TREE TOPPER;
BIT GRINDER. GROUP 1-B: SEWER CLEANERS SHALL
RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES.
""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR
COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER
SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE,
LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE
SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE
GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND
REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES
PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25
PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK
PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (CONTRA COSTA COUNTY).....\$ 36.72

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-C-
BURNING AND WELDING IN CONNECTION WITH LABORERS'
WORK; SYNTHETIC THERMOPLASTICS AND SIMILAR TYPE
WELDING. FOOTNOTES: LABORERS WORKING OFF OR WITH
OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS
SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE
WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY

CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CONTRA COSTA COUNTY).....\$ 36.55	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-E- WORK ON AND/OR IN BELL HOLE FOOTINGS AND SHAFTS THEREOF, AND WORK ON AND IN DEEP FOOTINGS. (A DEEP FOOTING IS A HOLE 15 FEET OR MORE IN DEPTH.) IN THE EVENT THE DEPTH OF THE FOOTING IS UNKNOWN AT THE COMMENCEMENT OF EXCAVATION, AND THE FINAL DEPTH EXCEEDS 15 FEET, THE DEEP FOOTING WAGE RATE WOULD APPLY TO ALL EMPLOYEES FOR EACH AND EVERY DAY WORKED ON OR IN THE EXCAVATION OF THE FOOTING FROM THE DATE OF INCEPTION. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (CONTRA COSTA COUNTY).....\$ 37.05	
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-G- PIPELAYER (INCLUDING GRADE CHECKING IN CONNECTION WITH PIPELAYING); CAULKER; BANDER; PIPEWRAPPER; CONDUIT LAYER; PLASTIC PIPE LAYER; PRESSURE PIPE TESTER; NO JOINT PIPE AND STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS; PRECAST MANHOLE SETTERS, CAST IN PLACE MANHOLE FORM SETTERS. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL	
	27.30

EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (CONTRA COSTA COUNTY)\$ 36.70

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 2-
ASPHALT SHOVELER; CEMENT DUMPER AND HANDLING DRY
CEMENT OR GYPSUM; CHOKE-SETTER AND RIGGER (CLEARING
WORK); CONCRETE BUCKET DUMPER AND CHUTE; CONCRETE
CHIPPING AND GRINDING; CONCRETE LABORER (WET OR
DRY); DRILLER TENDER, CHUCK TENDER, NIPPER; GUINEA
CHASER (STAKE), GROUT CREW; HIGH PRESSURE NOZZLE,
ADDUCTOR; HYDRAULIC MONITOR (OVER 100 LBS.
PRESSURE); LOADING AND UNLOADING, CARRYING AND
HAULING OF ALL RODS AND MATERIALS FOR USE IN
REINFORCING CONCRETE CONSTRUCTION; PITTSBURGH
CHIPPER AND SIMILAR TYPE BRUSH SHREDDERS; SLOPER;
SINGLE FOOT, HAND-HELD, PNEUMATIC TAMPER; ALL
PNEUMATIC, AIR, GAS AND ELECTRIC TOOLS NOT LISTED
IN GROUPS 1 THROUGH 1-F; JACKING OF PIPE - UNDER 12
INCHES. FOOTNOTES: LABORERS WORKING OFF OR WITH
OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS
SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE
WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (CONTRA COSTA COUNTY).....\$ 36.35

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 3-
CONSTRUCTION LABORERS, INCLUDING BRIDGE AND GENERAL
LABORER; DUMP, LOAD SPOTTER; FLAG PERSON; FIRE
WATCHER; FENCE ERECTOR; GUARDRAIL ERECTOR;
GARDENER, HORTICULTURAL AND LANDSCAPE LABORER;
JETTING; LIMBER, BRUSH LOADER AND PILER; PAVEMENT

MARKER (BUTTON SETTER); MAINTENANCE, REPAIR TRACK
 AND ROAD BEDS; STREETCAR AND RAILROAD CONSTRUCTION
 TRACK LABORER; TEMPORARY AIR AND WATER LINES,
 VICTAULIC OR SIMILAR; TOOL ROOM ATTENDANT (JOBSITE
 ONLY). FOOTNOTES: LABORERS WORKING OFF OR WITH OR
 FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
 RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
 RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
 \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
 CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
 CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
 THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
 DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
 MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
 TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
 COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
 THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
 UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
 HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO
 APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT
 SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
 CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
 PLACED. (CONTRA COSTA COUNTY).....\$ 36.25 27.30
 LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 4-
 FINAL CLEAN-UP WORK OF DEBRIS, GROUNDS AND BUILDING
 INCLUDING BUT NOT LIMITED TO: STREET CLEANER;
 CLEANING AND WASHING WINDOWS; BRICK CLEANER
 (JOBSITE ONLY); MATERIAL CLEANER (JOBSITE ONLY).
 THE CLASSIFICATION ""MATERIAL CLEANER"" IS TO BE
 UTILIZED UNDER THE FOLLOWING CONDITIONS: A: AT
 DEMOLITION SITE FOR THE SALVAGE OF THE MATERIAL.
 B: AT THE CONCLUSION OF A JOB WHERE THE MATERIAL IS
 TO BE SALVAGED AND STOCKED TO BE REUSED ON ANOTHER
 JOB. C: FOR THE CLEANING OF SALVAGE MATERIAL AT
 THE JOBSITE OR TEMPORARY JOBSITE YARD. THE
 MATERIAL CLEANER CLASSIFICATION SHOULD NOT BE USED
 IN THE PERFORMANCE OF ""FORM STRIPPING, CLEANING
 AND OILING AND MOVING TO THE NEXT POINT OF
 ERECTION"". FOOTNOTES: LABORERS WORKING OFF OR
 WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS,
 BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE
 APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS
 SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE
 RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO
 HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN
 SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE
 RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL
 RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00

PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (CONTRA COSTA COUNTY).....\$ 29.94 27.30
LABORER, GUNITE: GROUP 1- STRUCTURAL NOZZLEMAN.
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. (CONTRA COSTA COUNTY).....\$ 37.46 27.30
LABORER, GUNITE: GROUP 2- NOZZLEMAN, GUNMAN,
POTMAN, GROUNDMAN. FOOTNOTES: LABORERS WORKING
OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING
SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE
THE APPLICABLE WAGE RATE. (CONTRA COSTA COUNTY)....\$ 36.96 27.30
LABORER, GUNITE: GROUP 3- REBOUNDMAN. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
HOUR ABOVE THE APPLICABLE WAGE RATE. (CONTRA
COSTA COUNTY).....\$ 36.37 27.30
LABORER, GUNITE: GROUP 4- GUINTE LABORER.
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. (CONTRA COSTA COUNTY).....\$ 36.25 27.30
LABORER, WRECKING: GROUP 1- SKILLED WRECKER
(REMOVING AND SALVAGING OF SASH, WINDOWS, AND
MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR
WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS,
BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE
APPLICABLE WAGE RATE. (CONTRA COSTA COUNTY).....\$ 36.50 27.30
LABORER, WRECKING: GROUP 2- SEMI-SKILLED WRECKER
(SALVAGING OF OTHER BUILDING MATERIALS).
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. (CONTRA COSTA COUNTY).....\$ 36.35 27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE
LABORERS - (1) New Construction. FOOTNOTES:
LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS,
SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER
HOUR ABOVE THE APPLICABLE WAGE RATE. (CONTRA COSTA
COUNTY).....\$ 36.25 27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE

LABORERS - (2) Establishment Warranty Period. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (CONTRA COSTA COUNTY).....	\$ 29.94	27.30
--	----------	-------

LAB00324-014 07/01/2023

	Rates	Fringes
BRICK TENDER. FOOTNOTES: WORK ON JOBS WHERE HEAT-PROTECTIVE CLOTHING IS REQUIRED: \$2.00 PER HOUR ADDITIONAL. WORK AT GRINDERS: \$.25 PER HOUR ADDITIONAL. MANHOLE WORK: \$2.00 PER DAY ADDITIONAL. (CONTRA COSTA COUNTY)	\$ 37.05	27.45

LAB00324-018 07/01/2023

	Rates	Fringes
PLASTER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (ALAMEDA AND CONTRA COSTA COUNTIES).....	\$ 41.93	30.32

LAB01130-002 07/01/2023

	Rates	Fringes
LABORER, TRAFFIC CONTROL/LANE CLOSURE: ESCORT DRIVER, FLAG PERSON (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 36.26	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON I- LAYOUT OF TRAFFIC CONTROL, CRASH CUSHIONS, CONSTRUCTION AREA AND ROADSIDE SIGNAGE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 36.56	27.30
LABORER, TRAFFIC CONTROL/LANE CLOSURE: TRAFFIC CONTROL PERSON II- INSTALLATION AND REMOVAL OF TEMPORARY/PERMANENT SIGNS, MARKERS, DELINEATORS AND CRASH CUSHIONS. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 34.06	27.30

LAB01130-003 06/26/2023

	Rates	Fringes
TUNNEL AND SHAFT LABORERS: GROUP 1- DIAMOND DRILLER; GROUND MEN; GUNITE AND SHOTCRETE NOZZLEMEN (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 45.89	27.72
TUNNEL AND SHAFT LABORERS: GROUP 2- RODMEN; SHAFT WORK & RAISE (BELOW ACTUAL OR EXCAVATED GROUND LEVEL) (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE		

COUNTIES).....\$ 45.66	27.72	
TUNNEL AND SHAFT LABORERS: GROUP 3- BIT GRINDER; BLASTER, DRILLER, POWDERMEN, HEADING; CHERRY PICKERMEN - WHERE CAR IS LIFTED; CONCRETE FINISHER IN TUNNEL; CONCRETE SCREEDMAN; GROUT PUMPMAN AND POTMAN; GUNITE & SHOTCRETE GUNMAN & POTMAN; HEADERMEN; HIGH PRESSURE NOZZLEMAN; MINER - TUNNEL, INCLUDING TOP AND BOTTOM MAN ON SHAFT AND RAISE WORK; NIPPER; NOZZLEMAN ON SLICK LINE; SANDBLASTER - POTMAN, ROBOTIC SHOTCRETE PLACER, SEGMENT ERECTOR, TUNNEL MUCK HAULER, STEEL FORM RAISER AND SETTER; TIMBERMAN, RETIMBERMAN (WOOD OR STEEL OR SUBSTITUTE MATERIALS THEREFORE); TUGGER (FOR TUNNEL LABORER WORK); CABLE TENDER; CHUCK TENDER; POWDERMAN - PRIMER HOUSE (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 45.41		27.72
TUNNEL AND SHAFT LABORERS: GROUP 4- VIBRATOR OPERATOR, PAVEMENT BREAKER; BULL GANG - MUCKERS, TRACKMEN; CONCRETE CREW - INCLUDES RODDING AND SPREADING, DUMPMEN (ANY METHOD) (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 44.96		27.72
TUNNEL AND SHAFT LABORERS: GROUP 5- GROUT CREW; REBOUNDMAN; SWAMPER/ BRAKEMAN (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 44.42		27.72
TUNNEL AND SHAFT LABORERS: SHOTCRETE SPECIALIST (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 46.41		27.72

LAB01130-005 07/01/2023

Rates

Fringes

LABORER: MASON TENDER-BRICK (MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES).....\$ 36.29	25.55
--	-------

LAB01130-007 06/26/2023

Rates

Fringes

LABORER (CONSTRUCTION CRAFT LABORERS) GROUP 1-F-
WIRE WINDING MACHINE IN CONNECTION WITH GUNITING OR
SHOT CRETE. FOOTNOTES: LABORERS WORKING OFF OR WITH
OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS
SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE
WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1

WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 36.08	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: CONSTRUCTION SPECIALIST GROUP- ASPHALT IRONER AND RAKER; CHAINSAW; LASER BEAM IN CONNECTION WITH LABORERS' WORK; CAST-IN- PLACE MANHOLE FORM SETTER; PRESSURE PIPELAYER; DAVIS TRENCHER - 300 OR SIMILAR TYPE (AND ALL SMALL TRENCHERS); BLASTER; DIAMOND DRILLER; MULTIPLE UNIT DRILL; HYDRAULIC DRILL. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 36.20	27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1- ASPHALT SPREADER BOXES (ALL TYPES); BARKO, WACKER AND SIMILAR TYPE TAMPERS; BUGGYMOBILE; CAULKER, BANDER, PIPEWRAPPER, CONDUIT LAYER, PLASTIC PIPELAYER; CERTIFIED HAZARDOUS WASTE WORKER INCLUDING LEADE ABATEMENT; COMPACTORS OF ALL TYPES; CONCRETE AND MAGNESITE MIXER, 1/2 YD. AND UNDER; CONCRETE PAN WORK; CONCRETE SANDER; CONCRETE SAW; CRIBBER AND/OR SHORING; CUT GRANITE CURB SETTER; DRI-PAK-IT MACHINE; FALLER, LOGLOADER AND BUCKER;	

FORM RAISER, SLIP FORMS; GREEN CUTTER; HEADERBOARD, HUBSETTER, ALIGNER, BY ANY METHOD; HIGH PRESSURE BLOW PIPE (1-1/2" OR OVER, 100 LBS. PRESSURE/OVER); HYDRO SEEDER AND SIMILAR TYPE; JACKHAMMER OPERATOR; JACKING OF PIPE OVER 12 INCHES; JACKSON AND SIMILAR TYPE COMPACTOR; KETTLE TENDER, POT AND WORKER APPLYING ASPHALT, LAY-KOLD, CREOSOTE, LIME, CAUSTIC AND SIMILAR TYPE MATERIALS (APPLYING MEANS APPLYING, DIPPING OR HANDLING OF SUCH MATERIALS); LAGGING, SHEETING, WHALING, BRACING, TRENCHJACKING, LAGGING HAMMER; MAGNESITE, EPOXYRESIN, FIBERGLASS, MASTIC WORKER (WET OR DRY); NO JOINT PIPE AND STRIPPING OF SAME, INCLUDING REPAIR OF VOIDS; PAVEMENT BREAKER AND SPADER, INCLUDING TOOL GRINDER; PERMA CURB; PIPELAYER (INCLUDING GRADE CHECKING IN CONNECTION WITH PIPELAYING); PRECAST-MANHOLE SETTER; PRESSURE PIPE TESTER; POST HOLE DIGGER, AIR, GAS AND ELECTRIC; POWER BROOM SWEEPER; POWER TAMPERS OF ALL TYPES (EXCEPT AS SHOWN IN GROUP 2); RAM SET GUN AND STUD GUN; RIPRAP STONEPAVER AND ROCK-SLINGER, INCLUDING PLACING OF SACKED CONCRETE AND/OR SAND (WET OR DRY) AND GABIONS AND SIMILAR TYPE; ROTARY SCARIFIER OR MULTIPLE HEAD CONCRETE CHIPPING SCARIFIER; ROTO AND DITCH WITCH; ROTOTILLER; SANDBLASTER, POT, GUN, NOZZLE OPERATORS; SIGNALLING AND RIGGING; TANK CLEANER; TREE CLIMBER; TURBO BLASTER; VIBRASCREED, BULL FLOAT IN CONNECTION WITH LABORERS' WORK; VIBRATOR; HAZARDOUS WASTE WORKER (LEAD REMOVAL); ASBESTOS AND MOLD REMOVAL WORKER. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MARIPOSA, MERCED,

STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 35.50

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-A-
JOY DRILL MODEL TWM-2A; GARDNER-DENVER MODEL DH143
AND SIMILAR TYPE DRILLS; TRACK DRILLER; JACK LEG
DRILLER; WAGON DRILLER; MECHANICAL DRILLERS, ALL
TYPES REGARDLESS OF TYPE OR METHOD OF POWER;
MECHANICAL PIPE LAYERS, ALL TYPES REGARDLESS OF
TYPE OR METHOD OF POWER; BLASTER AND POWDER; ALL
WORK OF LOADING, PLACING AND BLASTING OF ALL POWDER
AND EXPLOSIVES OF WHATEVER TYPE REGARDLESS OF
METHOD USED FOR SUCH LOADING AND PLACING; HIGH
SCALERS (INCLUDING DRILLING OF SAME); TREE TOPPER;
BIT GRINDER. GROUP 1-B: SEWER CLEANERS SHALL
RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES.
""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR
COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER
SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE,
LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE
SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE
GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND
REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES
PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25
PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK
PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (MARIPOSA, MERCED,

STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 35.72

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-C-
BURNING AND WELDING IN CONNECTION WITH LABORERS'
WORK; SYNTHETIC THERMOPLASTICS AND SIMILAR TYPE
WELDING. FOOTNOTES: LABORERS WORKING OFF OR WITH
OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS
SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE
WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE
\$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER
CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN
CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS.
THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE
DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER
MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1
WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR
TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK
COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE
THEIR REGULAR RATE FOR ALL WORK PERFORMED ON
UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED
HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO

APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 35.55

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 1-E-
WORK ON AND/OR IN BELL HOLE FOOTINGS AND SHAFTS
THEREOF, AND WORK ON AND IN DEEP FOOTINGS. (A DEEP
FOOTING IS A HOLE 15 FEET OR MORE IN DEPTH.) IN
THE EVENT THE DEPTH OF THE FOOTING IS UNKNOWN AT
THE COMMENCEMENT OF EXCAVATION, AND THE FINAL DEPTH
EXCEEDS 15 FEET, THE DEEP FOOTING WAGE RATE WOULD
APPLY TO ALL EMPLOYEES FOR EACH AND EVERY DAY
WORKED ON OR IN THE EXCAVATION OF THE FOOTING FROM
THE DATE OF INCEPTION. FOOTNOTES: LABORERS WORKING
OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING
SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE
THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER
CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1
WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO
HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN
SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE
RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL
RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00
PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (MARIPOSA, MERCED,

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 2- ASPHALT SHOVELER; CEMENT DUMPER AND HANDLING DRY CEMENT OR GYPSUM; CHOKE-SETTER AND RIGGER (CLEARING WORK); CONCRETE BUCKET DUMPER AND CHUTE; CONCRETE CHIPPING AND GRINDING; CONCRETE LABORER (WET OR DRY); DRILLER TENDER, CHUCK TENDER, NIPPER; GUINEA CHASER (STAKE), GROUT CREW; HIGH PRESSURE NOZZLE, ADDUCTOR; HYDRAULIC MONITOR (OVER 100 LBS. PRESSURE); LOADING AND UNLOADING, CARRYING AND HAULING OF ALL RODS AND MATERIALS FOR USE IN REINFORCING CONCRETE CONSTRUCTION; PITTSBURGH CHIPPER AND SIMILAR TYPE BRUSH SHREDDERS; SLOPER; SINGLE FOOT, HAND-HELD, PNEUMATIC TAMPER; ALL PNEUMATIC, AIR, GAS AND ELECTRIC TOOLS NOT LISTED

IN GROUPS 1 THROUGH 1-F; JACKING OF PIPE - UNDER 12 INCHES. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN PLACED. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 35.35

27.30

LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 3- CONSTRUCTION LABORERS, INCLUDING BRIDGE AND GENERAL LABORER; DUMP, LOAD SPOTTER; FLAG PERSON; FIRE WATCHER; FENCE ERECTOR; GUARDRAIL ERECTOR; GARDENER, HORTICULTURAL AND LANDSCAPE LABORER; JETTING; LIMBER, BRUSH LOADER AND PILER; PAVEMENT MARKER (BUTTON SETTER); MAINTENANCE, REPAIR TRACK AND ROAD BEDS; STREETCAR AND RAILROAD CONSTRUCTION TRACK LABORER; TEMPORARY AIR AND WATER LINES, VICTAULIC OR SIMILAR; TOOL ROOM ATTENDANT (JOBSITE ONLY). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00 PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D: MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND LEVEL IN OPEN CUT. IT

SHALL APPLY TO CUT AND COVER WORK OF SUBWAY
CONSTRUCTION AFTER THE TEMPORARY COVER HAS BEEN
PLACED. (MARIPOSA, MERCED, STANISLAUS, AND
TUOLUMNE COUNTIES).....\$ 35.25 27.30
LABORER, CONSTRUCTION CRAFT LABORERS: GROUP 4-
FINAL CLEAN-UP WORK OF DEBRIS, GROUNDS AND BUILDING
INCLUDING BUT NOT LIMITED TO: STREET CLEANER;
CLEANING AND WASHING WINDOWS; BRICK CLEANER
(JOBSITE ONLY); MATERIAL CLEANER (JOBSITE ONLY).
THE CLASSIFICATION ""MATERIAL CLEANER"" IS TO BE
UTILIZED UNDER THE FOLLOWING CONDITIONS: A: AT
DEMOLITION SITE FOR THE SALVAGE OF THE MATERIAL.
B: AT THE CONCLUSION OF A JOB WHERE THE MATERIAL IS
TO BE SALVAGED AND STOCKED TO BE REUSED ON ANOTHER
JOB. C: FOR THE CLEANING OF SALVAGE MATERIAL AT
THE JOBSITE OR TEMPORARY JOBSITE YARD. THE
MATERIAL CLEANER CLASSIFICATION SHOULD NOT BE USED
IN THE PERFORMANCE OF ""FORM STRIPPING, CLEANING
AND OILING AND MOVING TO THE NEXT POINT OF
ERECTION"". FOOTNOTES: LABORERS WORKING OFF OR
WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS,
BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE
APPLICABLE WAGE RATE. GROUP 1-B: SEWER CLEANERS
SHALL RECEIVE \$4.00 PER DAY ABOVE GROUP 1 WAGE
RATES. ""SEWER CLEANER"" MEANS ANY WORKER WHO
HANDLES OR COMES IN CONTACT WITH RAW SEWAGE IN
SMALL DIAMETER SEWERS. THOSE WHO WORK INSIDE
RECENTLY ACTIVE, LARGE DIAMETER SEWERS, AND ALL
RECENTLY ACTIVE SEWER MANHOLES SHAL RECEIVE \$5.00
PER DAY ABOVE GROUP 1 WAGE RATES. GROUP 1-D:
MAINTENANCE AND REPAIR TRACK AND ROAD BEDS. ALL
EMPLOYEES PERFORMING WORK COVERED HEREIN SHALL
RECEIVE \$0.25 PER HOUR ABOVE THEIR REGULAR RATE FOR
ALL WORK PERFORMED ON UNDERGROUND STRUCTURES NOT
SPECIFICALLY COVERED HEREIN. THIS PARAGRAPH SHALL
NOT BE CONSTRUED TO APPLY TO WORK BELOW GROUND
LEVEL IN OPEN CUT. IT SHALL APPLY TO CUT AND COVER
WORK OF SUBWAY CONSTRUCTION AFTER THE TEMPORARY
COVER HAS BEEN PLACED. (MARIPOSA, MERCED,
STANISLAUS, AND TUOLUMNE COUNTIES).....\$ 28.94 27.30
LABORER, GUNITE: GROUP 1- STRUCTURAL NOZZLEMAN.
FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM
BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL
RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE
RATE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE
COUNTIES).....\$ 36.46 27.30
LABORER, GUNITE: GROUP 2- NOZZLEMAN, GUNMAN,
POTMAN, GROUNDMAN. FOOTNOTES: LABORERS WORKING
OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING

SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 35.96	27.30
LABORER, GUNITE: GROUP 3- REBOUNDMAN. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 35.37	27.30
LABORER, GUNITE: GROUP 4- GUINTE LABORER. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 35.25	27.30
LABORER, WRECKING: GROUP 1- SKILLED WRECKER (REMOVING AND SALVAGING OF SASH, WINDOWS, AND MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 35.50	27.30
LABORER, WRECKING: GROUP 2- SEMI-SKILLED WRECKER (SALVAGING OF OTHER BUILDING MATERIALS). FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 35.35	27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (1) New Construction. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 35.25	27.30
LABORER: GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - (2) Establishment Warranty Period. FOOTNOTES: LABORERS WORKING OFF OR WITH OR FROM BOS'N CHAIRS, SWINGING SCAFFOLDS, BELTS SHALL RECEIVE \$0.25 PER HOUR ABOVE THE APPLICABLE WAGE RATE. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 28.94	27.30

LAB01130-008 07/01/2023

Rates

Fringes

LABORER, PLASTER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS, & TUOLUMNE COUNTIES)	\$ 39.77	28.54
--	----------	-------

LAB01130-009 07/01/2023		
	Rates	Fringes
LABORER, PLASTER TENDER. WORK ON A SWING STAGE SCAFFOLD: \$1.00 PER HOUR ADDITIONAL. (MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES)	\$ 39.77	28.54

PAIN0016-001 01/01/2025		
	Rates	Fringes
PAINTERS. PREMIUMS: EXOTIC MATERIALS - \$1.25 ADDITIONAL PER HOUR. SPRAY WORK: - \$0.50 ADDITIONAL PER HOUR. INDUSTRIAL PAINTING - \$0.25 ADDITIONAL PER HOUR [WORK ON INDUSTRIAL BUILDINGS USED FOR THE MANUFACTURE AND PROCESSING OF GOODS FOR SALE OR SERVICE; STEEL CONSTRUCTION (BRIDGES), STACKS, TOWERS, TANKS, AND SIMILAR STRUCTURES]. HIGH WORK: OVER 50 FEET - \$2.00 PER HOUR ADDITIONAL 100 TO 180 FEET - \$4.00 PER HOUR ADDITIONAL OVER 180 FEET - \$6.00 PER HOUR ADDITIONAL (ALAMEDA, CONTRA COSTA, MONTEREY, SAN BENITO, SAN MATEO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....	\$ 53.38	28.04

PAIN0016-003 01/01/2025		
	Rates	Fringes
DRYWALL FINISHER/TAPER. (ALAMDEA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, & SANTA CLARA COUNTIES)...	\$ 63.76	32.69
DRYWALL FINISHER/TAPER. (CALAVERAS, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN JOAQUIN, SANTA CRUZ, STANISLAUS, & TUOLUMNE COUNTIES).....	\$ 59.63	31.29

PAIN0016-012 01/01/2024		
	Rates	Fringes
SOFT FLOOR LAYER (ALAMEDA, CONTRA COSTA, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN MATEO, SANTA CLARA AND SANTA CRUZ COUNTIES).....	\$ 59.00	33.03

PAIN0016-015 01/01/2025		
	Rates	Fringes
PAINTER: BRUSH. FOOTNOTES: SPRAY/SANDBLAST: \$0.50 ADDITIONAL PER HOUR. EXOTIC MATERIALS: \$1.25 ADDITIONAL PER HOUR. HIGH TIME: OVER 50 FT ABOVE GROUND OR WATER LEVEL \$2.00 ADDITIONAL PER HOUR. 100 TO 180 FT ABOVE GROUND OR WATER LEVEL \$4.00		

ADDITIONAL PER HOUR. OVER 180 FT ABOVE GROUND OR WATER LEVEL \$6.00 ADDITIONAL PER HOUR. (CALAVERAS, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS & TUOLUMNE COUNTIES).....	\$ 43.45	22.80

PAIN0016-022 01/01/2025		
	Rates	Fringes
PAINTER (SAN FRANCISCO COUNTY).....	\$ 57.00	28.04

PAIN0169-001 01/01/2023		
	Rates	Fringes
GLAZIER (FRESNO, KINGS, MADERA, MARIPOSA AND MERCED COUNTIES).....	\$ 44.33	28.88

PAIN0169-005 01/01/2024		
	Rates	Fringes
GLAZIER (ALAMEDA CONTRA COSTA, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN MATEO, SANTA CLARA & SANTA CRUZ COUNTIES).....	\$ 56.22	34.00

PAIN0294-004 07/01/2023		
	Rates	Fringes
PAINTER: BRUSH, ROLLER. FOOTNOTE: SPRAY PAINTERS & PAPERHANGERS RECIVE \$1.00 ADDITIONAL PER HOUR. PAINTERS DOING DRYWALL PATCHING RECEIVE \$1.25 ADDITIONAL PER HOUR. LEAD ABATERS & SANDBLASTERS RECEIVE \$1.50 ADDITIONAL PER HOUR. HIGH TIME - OVER 30 FEET (DOES NOT INCLUDE WORK FROM A LIFT) \$0.75 PER HOUR ADDITIONAL. (FRESNO, KINGS AND MADERA COUNTIES)	\$ 34.49	21.80
PAINTER: DRYWALL FINISHER/TAPER. FOOTNOTE: SPRAY PAINTERS & PAPERHANGERS RECIVE \$1.00 ADDITIONAL PER HOUR. PAINTERS DOING DRYWALL PATCHING RECEIVE \$1.25 ADDITIONAL PER HOUR. LEAD ABATERS & SANDBLASTERS RECEIVE \$1.50 ADDITIONAL PER HOUR. HIGH TIME - OVER 30 FEET (DOES NOT INCLUDE WORK FROM A LIFT) \$0.75 PER HOUR ADDITIONAL. (FRESNO, KINGS AND MADERA COUNTIES)	\$ 35.74	21.80

PAIN0294-005 01/01/2023		
	Rates	Fringes
SOFT FLOOR LAYER (FRESNO, KINGS & MADERA COUNTIES).. -----	\$ 38.53	23.19

PAIN0767-001 01/01/2024

Rates

Fringes

GLAZIER. PAID HOLIDAYS: NEW YEAR'S DAY, MARTIN
LUTHER KING, JR. DAY, PRESIDENT'S DAY, MEMORIAL
DAY, INDEPENDENCE DAY, LABOR DAY, VETERAN'S DAY,
THANKSGIVING DAY, AND CHRISTMAS DAY. EMPLOYEE
REQUIRED TO WEAR A BODY HARNESS SHALL RECEIVE \$1.50
PER HOUR ABOVE THE BASIC HOURLY RATE AT ANY
ELEVATION. (CALAVERAS, SAN JOAQUIN, STANISLAUS AND
TUOLUMNE COUNTIES)\$ 43.25

35.62

PAIN1176-001 07/01/2022

Rates

Fringes

PARKING LOT STRIPING/HIGHWAY MARKING: HIGHWAY
IMPROVEMENT: GROUP 2- GAMECOURT & PLAYGROUND
INSTALLER.....\$ 34.71
PARKING LOT STRIPING/HIGHWAY MARKING: HIGHWAY
IMPROVEMENT: GROUP 1- STRIPER: LAYOUT AND
APPLICATION OF PAINTED TRAFFIC STRIPES AND MARKING;
HOT THERMO PLASTIC; TAPE, TRAFFIC STRIPES AND
MARKINGS.....\$ 40.83
PARKING LOT STRIPING/HIGHWAY MARKING: HIGHWAY
IMPROVEMENT: GROUP 3- PROTECTIVE COATING, PAVEMENT
SEALING.....\$ 35.11

17.62

17.62

17.62

PAIN1237-003 01/01/2024

Rates

Fringes

SOFT FLOOR LAYER (CALAVERAS; SAN JOAQUIN
COUNTIES; STANISLAUS AND TUOLUMNE COUNTIES).....\$ 48.54

26.59

PLAS0066-002 07/01/2019

Rates

Fringes

PLASTERER (ALAMEDA, CONTRA COSTA, SAN MATEO AND SAN
FRANCISCO COUNTIES).....\$ 42.41

30.73

PLAS0300-001 07/01/2018

Rates

Fringes

PLASTERER (AREA 188: FRESNO).....\$ 32.70
PLASTERER (AREA 224: SAN BENITO, SANTA CLARA,
SANTA CRUZ).....\$ 32.88
PLASTERER (AREA 295: CALAVERAS & SAN JOAQUIN
COUNTIES).....\$ 32.70
PLASTERER (AREA 337: MONTEREY COUNTY).....\$ 32.88
PLASTERER (AREA 429: MARIPOSA, MERCED, STANISLAUS,
TUOLUMNE COUNTIES).....\$ 32.70

31.68

31.68

31.68

31.68

31.68

PLAS0300-005 07/01/2016		
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER.....	\$ 32.15	23.27

PLUM0038-001 07/01/2023		
	Rates	Fringes
PLUMBER (PLUMBER, STEAMFITTER, REFRIGERATION FITTER) (SAN FRANCISCO COUNTY).....	\$ 85.50	48.98

PLUM0038-005 07/01/2025		
	Rates	Fringes
LANDSCAPE/IRRIGATION FITTER: UNDERGROUND/UTILITY FITTER (SAN FRANCISCO COUNTY).....	\$ 77.35	36.53

PLUM0062-001 01/01/2026		
	Rates	Fringes
PLUMBER & STEAMFITTER (MONTEREY AND SANTA CRUZ COUNTIES).....	\$ 57.75	43.60

PLUM0159-001 07/01/2025		
	Rates	Fringes
PLUMBER AND STEAMFITTER: (1) REFRIGERATION (CONTRA COSTA COUNTY).....	\$ 67.68	49.04
PLUMBER AND STEAMFITTER: (2) ALL OTHER WORK (CONTRA COSTA COUNTY).....	\$ 68.57	49.04

PLUM0246-001 01/01/2026		
	Rates	Fringes
PLUMBER & STEAMFITTER (FRESNO, KINGS & MADERA COUNTIES).....	\$ 54.50	42.54

PLUM0246-004 01/01/2017		
	Rates	Fringes
PLUMBER: PIPE TRADESMAN. (PIPE TRADESMAN SCOPE OF WORK: INSTALLATION OF CORRUGATED METAL PIPING FOR DRAINAGE, AS WELL AS INSTALLATION OF CORRUGATED METAL PIPING FOR CULVERTS IN CONNECTION WITH STORM SEWERS AND DRAINS; GROUTING, DRY PACKING AND DIAPERING OF JOINTS, HOLES OR CHASES INCLUDING PAVING OVER JOINTS, IN PIPING; TEMPORARY PIPING FOR DIRT WORK FOR BUILDING SITE PREPARATION; OPERATING		

JACK HAMMERS, PAVEMENT BREAKERS, CHIPPING GUNS, CONCRETE SAWS AND SPADES TO CUT HOLES, CHASES AND CHANNELS FOR PIPING SYSTEMS; DIGGING, GRADING, BACKFILLING AND GROUND PREPARATION FOR ALL TYPES OF PIPE TO ALL POINTS OF THE JOBSITE; GROUND PREPARATION INCLUDING GROUND LEVELING, LAYOUT AND PLANTING OF SHRUBBERY, TREES AND GROUND COVER, INCLUDING WATERING, MOWING, EDGING, PRUNING AND FERTILIZING, THE BREAKING OF CONCRETE, DIGGING, BACKFILLING AND TAMPING FOR THE PREPARATION AND COMPLETION OF ALL WORK IN CONNECTION WITH LAWN SPRINKLER AND LANDSCAPING; LOADING, UNLOADING AND DISTRIBUTING MATERIALS AT JOBSITE; PUTTING AWAY MATERIALS IN STORAGE BINS IN JOBSITE SECURE STORAGE AREA; DEMOLITION OF PIPING AND FIXTURES FOR REMODELING AND ADDITIONS; SETTING UP AND TEARING DOWN WORK BENCHES, LADDERS AND JOB SHACKS; CLEAN-UP AND SWEEPING OF JOBSITE; PIPE WRAPPING AND WATERPROOFING WHERE TAR OR SIMILAR MATERIAL IS APPLIED FOR PROTECTION OF BURIED PIPING; FLAGMAN) (FRESNO, MERCED, & SAN JOAQUIN COUNTIES).....	\$ 13.00	10.74
---	----------	-------

PLUM0342-001 07/01/2025

	Rates	Fringes
PIPEFITTER (CONTRA COSTA COUNTY).....	\$ 80.50	50.45
PLUMBER, PIPEFITTER, STEAMFITTER (ALAMEDA COUNTY)...	\$ 80.50	50.45

PLUM0355-004 07/01/2025

	Rates	Fringes
UNDERGROUND UTILITY WORKER /LANDSCAPE FITTER (ALAMEDA, CALAVERAS, CONTRA COSTA, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, AND TUOLUMNE COUNTIES).....	\$ 36.01	18.50

PLUM0393-001 07/01/2021

	Rates	Fringes
PLUMBER/PIPEFITTER (SAN BENITO AND SANTA CLARA COUNTIES).....	\$ 68.76	46.63

PLUM0442-001 01/01/2026

	Rates	Fringes
PLUMBER & STEAMFITTER (CALAVERAS, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS & TUOLUMNE COUNTIES).....	\$ 58.45	38.74

PLUM0467-001 07/01/2025		
	Rates	Fringes
PLUMBER/PIPEFITTER/STEAMFITTER (SAN MATEO COUNTY)...	\$ 87.75	41.44

ROOF0027-002 09/01/2024		
	Rates	Fringes
ROOFER. FOOTNOTE: WORK WITH PITCH, PITCH BASE OF PITCH IMPREGNATED PRODUCTS OR ANY MATERIAL CONTAINING COAL TAR PITCH, ON ANY BUILDING OLD OR NEW, WHERE BOTH ASPHALT AND PITCHERS ARE USED IN THE APPLICATION OF A BUILT-UP ROOF OR TEAR OFF: \$2.00 PER HOUR ADDITIONAL. (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 45.76	16.86

ROOF0040-002 08/01/2024		
	Rates	Fringes
ROOFER (SAN FRANCISCO & SAN MATEO COUNTIES).....	\$ 55.30	22.97

ROOF0081-001 08/01/2024		
	Rates	Fringes
ROOFER (ALAMEDA AND CONTRA COSTA COUNTIES).....	\$ 54.94	23.34

ROOF0081-004 08/01/2024		
	Rates	Fringes
ROOFER (CALAVERAS, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS AND TUOLUMNE COUNTIES).....	\$ 49.65	22.19

ROOF0095-002 08/01/2023		
	Rates	Fringes
ROOFER: BITUMASTIC, ENAMELER, COAL TAR, PITCH AND MASTIC WORKER (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....	\$ 57.17	21.51
ROOFER: JOURNEYMAN (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES).....	\$ 53.17	21.51
ROOFER: KETTLE PERSON (2 KETTLES) (MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES:.).....	\$ 55.17	21.51

SFCA0483-001 01/01/2026		
	Rates	Fringes
SPRINKLER FITTER: FIRE (ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO AND SANTA CLARA COUNTIES).. <td>\$ 81.54</td> <td>41.35</td>	\$ 81.54	41.35

SFCA0669-011 01/01/2026		
	Rates	Fringes
SPRINKLER FITTER (CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN JOAQUIN, SANTA CRUZ, STANISLAUS AND TUOLUMNE COUNTIES).....	\$ 49.69	29.72

SHEE0104-001 07/01/2025		
	Rates	Fringes
SHEET METAL WORKER (MONTEREY & SAN BENITO COUNTIES).....	\$ 58.52	38.67
SHEET METAL WORKER (SANTA CRUZ COUNTY).....	\$ 55.16	34.18
SHEET METAL WORKER: ALL OTHER WORK (ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, SANTA CLARA COUNTIES)).....	\$ 64.06	46.83
SHEET METAL WORKER: MECHANICAL CONTRACTS UNDER \$200,000 (ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, SANTA CLARA COUNTIES)).....	\$ 55.92	45.29

SHEE0104-003 07/01/2021		
	Rates	Fringes
SHEET METAL WORKER (CALAVERAS AND SAN JOAQUIN COUNTIES).....	\$ 44.34	39.22

SHEE0104-005 07/01/2021		
	Rates	Fringes
SHEET METAL WORKER: EXCLUDING METAL DECK AND SIDING (MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES).....	\$ 41.28	45.41

SHEE0104-007 07/01/2021		
	Rates	Fringes
SHEET METAL WORKER (FRESNO, KINGS, AND MADERA COUNTIES).....	\$ 44.07	40.79

SHEE0104-015 07/01/2024		
	Rates	Fringes
SHEET METAL WORKER: METAL DECKING AND SIDING ONLY. (ALAMEDA, CONTRA COSTA, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN MATEO, SANTA CLARA AND SANTA CRUZ COUNTIES).....	\$ 56.23	37.52

SHEE0104-018 07/01/2024

Rates

Fringes

SHEET METAL WORKER: METAL DECKING AND SIDING ONLY.
(CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA,
MERCED, SAN JOAQUIN, STANISLAUS AND TUOLUMNE
COUNTIES).....

\$ 56.23

37.52

TEAM0094-001 07/01/2025

Rates

Fringes

TRUCK DRIVERS: GROUP 1: DUMP TRUCKS, UNDER 6 YDS.;
SINGLE UNIT FLAT RACK (2- AXLE UNIT); NIPPER TRUCK
(WHEN FLAT RACK TRUCK IS USED APPROPRIATE FLAT RACK
SHALL APPLY); CONCRETE PUMP TRUCK (WHEN FLAT RACK
TRUCK IS USED APPROPRIATE FLAT RACK SHALL APPLY);
CONCRETE PUMP MACHINE; FORK LIFT AND LIFT JITNEYS;
FUEL AND/OR GREASE TRUCK DRIVER OR FUEL PERSON;
SNOW BUGGY; STEAM CLEANING; BUS OR PERSONHAUL
DRIVER; ESCORT OR PILOT CAR DRIVER; PICKUP TRUCK;
TEAMSTER OILER/GREASER AND/OR SERVICEPERSON; HOOK
TENDER (INCLUDING LOADING AND UNLOADING); TEAM
DRIVER; TOOL ROOM ATTENDANT (REFINERIES).

FOOTNOTES: ARTICULATED DUMP TRUCK; BULK CEMENT
SPREADER (WITH OR WITHOUT AUGER); DUMPCRETE TRUCK;
SKID TRUCK (DEBRIS BOX); DRY PRE-BATCH CONCRETE MIX
TRUCKS; DUMPSTER OR SIMILAR TYPE; SLURRY TRUCK: USE
DUMP TRUCK YARDAGE RATE. HEATER PLANER; ASPHALT
BURNER; SCARIFIER BURNER; INDUSTRIAL LIFT TRUCK
(MECHANICAL TAILGATE); UTILITY AND CLEAN-UP TRUCK:
USE APPROPRIATE RATE FOR THE POWER UNIT OR THE
EQUIPMENT UTILIZED.

\$ 43.26

34.28

TRUCK DRIVERS: GROUP 2: DUMP TRUCKS, 6 YDS. AND
UNDER 8 YDS.; TRANSIT MIXERS, THROUGH 10 YDS.;
WATER TRUCKS, UNDER 7,000 GALS.; JETTING TRUCKS,
UNDER 7,000 GALS.; SINGLE-UNIT FLAT RACK (3-AXLE
UNIT); HIGHBED HEAVY DUTY TRANSPORT; SCISSOR TRUCK;
RUBBER-TIRED MUCK CAR (NOT SELF-LOADED);
RUBBER-TIRED TRUCK JUMBO; WINCH TRUCK AND ""A"" FRAME
DRIVERS; COMBINATION WINCH TRUCK WITH HOIST; ROAD
OIL TRUCK OR BOOTPERSON; BUGGYMOBILE; ROSS, HYSTER
AND SIMILAR STRADDLE CARRIERS; SMALL RUBBER-TIRED
TRACTOR. FOOTNOTES: ARTICULATED DUMP TRUCK; BULK
CEMENT SPREADER (WITH OR WITHOUT AUGER); DUMPCRETE
TRUCK; SKID TRUCK (DEBRIS BOX); DRY PRE-BATCH
CONCRETE MIX TRUCKS; DUMPSTER OR SIMILAR TYPE;
SLURRY TRUCK: USE DUMP TRUCK YARDAGE RATE. HEATER
PLANER; ASPHALT BURNER; SCARIFIER BURNER;
INDUSTRIAL LIFT TRUCK (MECHANICAL TAILGATE);

UTILITY AND CLEAN-UP TRUCK: USE APPROPRIATE RATE FOR THE POWER UNIT OR THE EQUIPMENT UTILIZED.\$ 43.56	34.28
TRUCK DRIVERS: GROUP 3: DUMP TRUCKS, 8 YDS. AND INCLUDING 24 YDS.; TRANSIT MIXERS, OVER 10 YDS.; WATER TRUCKS, 7,000 GALS. AND OVER; JETTING TRUCKS, 7,000 GALS. AND OVER; VACUUM TRUCKS UNDER 7500 GALS. TRUCKS TOWING TILT BED OR FLAT BED PULL TRAILERS; LOWBED HEAVY DUTY TRANSPORT; HEAVY DUTY TRANSPORT TILLER PERSON; SELF- PROPELLED STREET SWEEPER WITH SELF-CONTAINED REFUSE BIN; BOOM TRUCK - HYDRO-LIFT OR SWEDISH TYPE EXTENSION OR RETRACTING CRANE; P.B. OR SIMILAR TYPE SELF-LOADING TRUCK; TIRE REPAIRPERSON; COMBINATION BOOTPERSON AND ROAD OILER; DRY DISTRIBUTION TRUCK (A BOOTPERSON WHEN EMPLOYED ON SUCH EQUIPMENT, SHALL RECEIVE THE RATE SPECIFIED FOR THE CLASSIFICATION OF ROAD OIL TRUCKS OR BOOTPERSON); AMMONIA NITRATE DISTRIBUTOR, DRIVER AND MIXER; SNOW GO AND/OR PLOW.	
FOOTNOTES: ARTICULATED DUMP TRUCK; BULK CEMENT SPREADER (WITH OR WITHOUT AUGER); DUMPCRETE TRUCK; SKID TRUCK (DEBRIS BOX); DRY PRE-BATCH CONCRETE MIX TRUCKS; DUMPSTER OR SIMILAR TYPE; SLURRY TRUCK: USE DUMP TRUCK YARDAGE RATE. HEATER PLANER; ASPHALT BURNER; SCARIFIER BURNER; INDUSTRIAL LIFT TRUCK (MECHANICAL TAILGATE); UTILITY AND CLEAN-UP TRUCK: USE APPROPRIATE RATE FOR THE POWER UNIT OR THE EQUIPMENT UTILIZED.\$ 43.86	34.28
TRUCK DRIVERS: GROUP 4: DUMP TRUCKS, OVER 25 YDS. AND UNDER 65 YDS.; WATER PULLS - DW 10'S, 20'S, 21'S AND OTHER SIMILAR EQUIPMENT WHEN PULLING AQUA/PAK OR WATER TANK TRAILERS; HELICOPTER PILOTS (WHEN TRANSPORTING MEN AND MATERIALS); LOWBEDK HEAVY DUTY TRANSPORT UP TO INCLUDING 7 AXLES; DW10'S, 20'S, 21'S AND OTHER SIMILAR CAT TYPE, TERRA COBRA, LETOURNEAU PULLS, TOURNOROCKER, EUCLID AND SIMILAR TYPE EQUIPMENT WHEN PULLING FUEL AND/OR GREASE TANK TRAILERS OR OTHER MISCELLANEOUS TRAILERS; VACUUM TRUCKS 7500 GALS AND OVER AND TRUCK REPAIRMAN. FOOTNOTES: ARTICULATED DUMP TRUCK; BULK CEMENT SPREADER (WITH OR WITHOUT AUGER); DUMPCRETE TRUCK; SKID TRUCK (DEBRIS BOX); DRY PRE-BATCH CONCRETE MIX TRUCKS; DUMPSTER OR SIMILAR TYPE; SLURRY TRUCK: USE DUMP TRUCK YARDAGE RATE. HEATER PLANER; ASPHALT BURNER; SCARIFIER BURNER; INDUSTRIAL LIFT TRUCK (MECHANICAL TAILGATE); UTILITY AND CLEAN-UP TRUCK: USE APPROPRIATE RATE FOR THE POWER UNIT OR THE EQUIPMENT UTILIZED.\$ 44.21	
TRUCK DRIVERS: GROUP 5: DUMP TRUCKS, 65 YDS. AND	34.28

OVER; HOLLAND HAULER; LOW BED HEAVY DUTY TRANSPORT
OVER 7 AXLES. FOOTNOTES: ARTICULATED DUMP TRUCK;
BULK CEMENT SPREADER (WITH OR WITHOUT AUGER);
DUMPCRETE TRUCK; SKID TRUCK (DEBRIS BOX); DRY
PRE-BATCH CONCRETE MIX TRUCKS; DUMPSTER OR SIMILAR
TYPE; SLURRY TRUCK: USE DUMP TRUCK YARDAGE RATE.
HEATER PLANER; ASPHALT BURNER; SCARIFIER BURNER;
INDUSTRIAL LIFT TRUCK (MECHANICAL TAILGATE);
UTILITY AND CLEAN-UP TRUCK: USE APPROPRIATE RATE
FOR THE POWER UNIT OR THE EQUIPMENT UTILIZED.\$ 44.56 34.28

WELDERS - Receive rate prescribed for craft performing
operation to which welding is incidental.

=====

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at <https://www.dol.gov/agencies/whd/government-contracts>.

Note: Executive Order 13658 generally applies to contracts subject to the Davis-Bacon Act that were awarded on or between January 1, 2015 and January 29, 2022, and that have not been renewed or extended on or after January 30, 2022. Executive Order 13658 does not apply to contracts subject only to the Davis-Bacon Related Acts regardless of when they were awarded. If a contract is subject to Executive Order 13658, the contractor must pay all covered workers at least \$13.65 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract from May 11, 2026, through December 31, 2026. The applicable Executive Order minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under Executive Order 13658 is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than SU, UAVG, SA, or SC denotes that a union rate was prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for the classifications reflected union rates. EXAMPLE: UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number used in producing the wage determination. The date, 01/01/2024 in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The SU identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

SU wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The SA identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the SA identifier took effect under state law in the state from which the rates were adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

- a) a survey underlying a wage determination
- b) an existing published wage determination
- c) an initial WHD letter setting forth a position on a wage determination matter
- d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch

of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.

=====
END OF GENERAL DECISION"

PROPOSAL SUBMITTAL CHECKLIST

The bidder shall provide a complete proposal in a sealed envelope before 2:00:00 pm local time on July 28, 2026 at the address shown on the cover sheet of these specifications.

FAILURE TO PROVIDE ALL THE REQUIRED DOCUMENTS LISTED IN THE TABLE BELOW MAY CAUSE THE PROPOSAL TO BE CONSIDERED NON-RESPONSIVE.

Complete Proposal	Page No.
☐ PROPOSAL AND BIDDING FORM.....	5-19
☐ AFFIDAVIT	20
☐ INFORMATION REQUIRED OF BIDDER.....	21-22
☐ BIDDER'S BOND	23-24
☐ LIST OF SUBCONTRACTORS.....	25
☐ IRAN CONTRACTING ACT CERTIFICATION.....	26
☐ EQUAL EMPLOYMENT OPPORTUNITY CERTIFICATION	27
☐ PUBLIC CONTRACT CODE STATEMENTS.....	28-29
☐ NON-COLLUSION AFFIDAVIT*	30
☐ DEBARMENT AND SUSPENSION CERTIFICATION*	31
☐ NONLOBBYING CERTIFICATION FOR FEDERAL-AID CONTRACTS*.....	32
☐ DISCLOSURE OF LOBBYING ACTIVITIES*	33
☐ EXHIBIT 12-B: BIDDERS LIST OF SUBCONTRACTORS (DBE AND NON-DBE)	35-37

* Signing the bid form constitutes acceptance and certification

The Successful Bidder shall submit within one week after receipt of Bids, one copy of all documentary information generated in preparation of Bid prices for this Project. This material is hereinafter referred to as "Escrow Bid Documents." The Escrow Bid Documents of the Successful Bidder will be held in escrow for the duration of the contract. See Special Provisions Section "Escrow Bid Documents."

In accordance with the annexed Notice to Contractors, the undersigned, as bidder, declares that he has carefully examined the location of the proposed work, the plans, specifications and technical requirements therefore, and the proposed forms of contract and bonds mentioned or referred to in said Notice and on file in the office of the City Engineer of the City of Turlock, together with the prevailing rate of per diem wages for each craft or type of workmen needed to execute said contract; and he proposes and agrees that if this proposal is accepted, he will furnish all labor, materials, equipment, plant transportation, service, sales taxes, permit fees and other costs necessary to complete the construction in strict conformity to the plans and specifications and he will enter into a written contract with the City of Turlock in the form of contract on file in the Office of the City Engineer for such purposes, and that he will execute and/or provide all bonds and insurance certificates required by law and/or by said contract and/or mentioned in said Notice to Contractors all in accordance with and subject to all applicable laws, and that he will take in full payment therefore the following unit prices, to wit:

10.21 FULL DEPTH RECLAMATION - CEMENT

Full depth reclamation - cement shall comply with Section 30, "Recycled Pavement" and Section 30-4, "Full Depth Recycling - Cement," of the State Standard Specifications.

Work shall consist of pulverizing existing asphalt concrete, base, and subgrade soil following cold planing of existing asphalt concrete. Re-grade based on PG grades on plans and haul away excess material to allow for the net placement of new asphalt concrete. At the contractor's option, in lieu of cold planing the existing asphalt concrete, the entire asphalt concrete section may be pulverized and mixed into the base and subgrade soil prior to regrading and hauling away the excess material to allow for the net placement of new asphalt concrete. Where fabric is present within the existing asphalt concrete on Geer Rd between Hawkeye Ave to 300 feet north of Calaveras Way, the Contractor shall remove it by cold planing a portion of the existing asphalt concrete pavement prior to pulverization operations. Following removal, the remaining asphalt concrete may be pulverized and blended with the base and subgrade materials prior to regrading. Add cement and water to the blended material in accordance with these and State Standard Specifications. Compact, fine grade to the grades required, cure and micro-crack the completed cement treated surface, prior to placement of asphalt concrete. Micro-cracking of the cement treated surface must be completed 48 to 56 hours after placement.

Obtain and test material every **500 feet** of the existing pavement structure by coring. Samples need to be taken randomly from NB, SB, and different lanes for a representative sample. A representation of the total roadway section needs to be accounted for in the Mix Design in the section identified below. The Contractor may perform additional sampling and testing to optimize the cement content and adjust for varying underlying materials. Determine the exact locations of the sampling locations between wheel paths. Do not sample in the shoulders. Sampling locations must provide sufficient representative material for the mix design.

The cement content must be **5 percent** by dry weight of FDR—cement with a dry unit weight of **6.5 lb/sf**, except an increase or decrease in the cement content may be ordered based on the Contractor's mix design. The cement quantity and application rate shown are provided for cost estimating and bidding purposes only. The actual cement content and application rate shall be determined by the Contractor's mix design and approved Job Mix Formula. The mix design shown on the plans and specification is based on the removal of all existing AC pavement. The actual mix design used for the project shall be determined by the Contractor in accordance with 30-4.01C(2)(b) "Mix Design," of the State Standard Specifications. The mix designs shall be submitted to and authorized by the Engineer prior to cold planning the AC pavement. During progress of the work, if the Contractor encounters an isolated area that requires more cement than described in the mix design for that area, notify the Engineer before applying the cement.

A test strip per Section 30-1.01D(3) of the State Standard Specifications is not required.

At a minimum, separate mix designs must be developed for the following roadway segments:

1. Geer Rd, Canal Dr to Starr Ave
2. Geer Rd, Starr Ave to Wayside Dr
3. Geer Rd, Wayside Dr to Hawkeye Ave
4. Geer Rd, Hawkeye Ave to Pedras Rd
5. Geer Rd, Pedras Rd to Minnesota Ave
6. Geer Rd, Minnesota Ave to Regis St

7. Geer Rd, Regis St to Hayes Dr
8. Geer Rd, Hayes Dr to 300 feet north of Calaveras Way

Attention is directed to the presence of shallow utilities within the limits of work. The Contractor shall anticipate the existing utility mains and laterals within the project limits that have not been potholed to be within the 18" to 12" vertical clearance range from the bottom of the FDR-C section. The Contractor must choose appropriate means and methods during construction to avoid damaging the existing shallow underground utilities. The depth of existing utilities, where identified by potholing has been provided on the plans. It is the Contractor's responsibility to pothole existing utilities, as described elsewhere in the specifications, and provide a report on the depth of the existing facilities to the Engineer.

Full depth reclamation - cement will be measured by the square yard, determined from horizontal measurements of the pavement surface to be recycled.

The quantities of cement (full depth reclamation - cement) used in the mix will be measured by the ton.

Mix design for the full depth reclamation - cement will be paid for on the basis of lump sum prices.

The contract price paid per square yard for full depth reclamation - cement shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing the full depth reclamation - cement, complete in place, including cleaning the surface, compacting and grading and surface finishing, all as shown on the plans, and as specified in State Standard Specifications and these Special Provisions, and as directed by the Engineer.

The contract price paid per ton for cement (full depth reclamation - cement) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in furnishing cement in the mix, complete in place, as shown on the plans, and as specified in State Standard Specifications and these Special Provisions, and as directed by the Engineer.

The contract lump sum prices paid for mix design (full depth reclamation - cement) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in preparing and testing the mix, including adding water, supplementary aggregate if required by the Engineer, setting control additives, mixing water with asphaltic emulsion, and applying sand cover, complete in place, as shown on the plans, as specified in State Standard Specifications and these Special Provisions, and as directed by the Engineer.

10.22 HOT MIX ASPHALT (TYPE A)

Preconstruction Meetings

Hold a preconstruction meeting with the Engineer per section 36-1.01D(2) of the State Standard Specifications. Discuss project specifications and the processes for producing materials and quality control measures for pavement smoothness including visual inspection of finished Hot Mix Asphalt (HMA) surface.

Prepare Existing Surface

Contractor shall prep the existing surface prior to placing HMA. Prepping the surface shall consist of sweeping and vacuuming the entire area to remove debris, organic matter, dirt, etc. Any work that will be required to fill potholes or make the surface suitable for paving shall be paid as extra work, through force account.

SECTION 8 PROSECUTION AND PROGRESS

8.01 START OF JOBSITE ACTIVITIES

The Engineer will issue a Notice to Proceed letter within 10 days after contract approval. The Notice to Proceed letter will state the earliest date on which the Contractor may commence jobsite activities. The Contractor shall not commence jobsite activities, subject to the exceptions listed in this section, prior to:

1. The date stated in the Notice to Proceed letter or
2. The Contractor receives authorization to start or
3. The following listed items are authorized or accepted by the Engineer:
 - 3.1. CPM baseline schedule
 - 3.2. SWPPP
 - 3.3. Contingency plan for opening closures to public traffic
 - 3.4. QC plan
 - 3.5. Material Safety Data Sheets
 - 3.6. Construction surveys
 - 3.7. Utility verification plan
 - 3.8. Notice of Materials to be Used form

Other than the submittals listed above, the Engineers' review times for any other submittals will not begin until the working days for the project have begun.

For purposes of determining time of completion, if the Contractor fails to accomplish all of the above listed items to the Engineer's satisfaction within 10 business-days following the earliest date for starting work as stated in the Notice to Proceed letter, work will be deemed to commence on the 11th business-day after the earliest date for starting work as stated in the Notice to Proceed letter, and each subsequent business-day until the Contractor accomplishes the above listed items to the Engineer's satisfaction will be considered to be a working-day as defined in section 1-1.07B of the State Standard Specifications.

Provided the Contractor has accomplished all of the above listed items to the Engineer's satisfaction, the Contractor shall begin work within 10 working-days after the earliest date for starting work as stated in the Notice to Proceed letter. The Contractor shall diligently prosecute the work to completion within the time limit provided. For purposes of determining time of completion, work will be deemed to commence on the day the Contractor begins work or 11 working-days after the date specified in the Notice to Proceed letter, whichever is earlier, and in accordance with contract requirements.

The Contractor may enter the jobsite prior to the first working day only to:

1. Measure controlling field dimensions and verifying conform locations per Section 5.28 "SURVEYING" of these specifications.
2. Construction area signs.
3. Implementation of SWPPP best management practices once the SWPPP has been accepted.

Submit a notification 72 hours before starting job site activities.

8.02 PROJECT MILESTONES

This section describes damages due to the City should the Contractor fail to meet certain project milestones. Attention is directed to Section 5 "Time of Performance" of the Agreement for liquidated damages for the Contractor's failure to perform all work on this project by the Completion Date.

The final lift of paving shall be placed no later than 3 working days after the first lift of paving. If the final lift of paving is not placed in the same shift as the initial lift(s) of paving, the Contractor shall place uneven surface warning signs every 50-feet along the lip of gutter. The cost of uneven surface warning signs shall be considered as included in the various contract bid items and no additional compensation will be allowed therefore.

The Contractor shall perform all required earthwork, grading, and initial paving (first lift) no later than eight (8) calendar days after the date when existing asphalt concrete surfaces have been demolished by way of cold plane grinding from any given area. On road sections that require video inspections of the sewer and storm drain mains in accordance with Section 10.09 "VIDEO SEWER AND STORM DRAIN", this time restriction may be extended to twelve (12) total calendar days. In the event the Contractor fails to complete the required work in the timeframe indicated, the City may deduct from payments or credits due Contractor a sum equal to two thousand five hundred dollars (\$2,500) for each and every calendar day delay in finishing the work.

During road closures, the work must progress continuously until the work is complete and the roadway is fully reopened to traffic.